

UBC Social Ecological Economic Development Studies (SEEDS) Sustainability Program

Student Research Report

**Redesign of Chancellor Boulevard / Wesbrook Mall Intersection at UBC**

**Alexander Liaw, Howard Ho Yin Wong, Jordan Yang, Kimberly Subianto, Kellie Liu,  
Lorena Polovina**

**University of British Columbia**

**CIVL446**

**April 7, 2017**

*Disclaimer: "UBC SEEDS Sustainability Program provides students with the opportunity to share the findings of their studies, as well as their opinions, conclusions and recommendations with the UBC community. The reader should bear in mind that this is a student research project/report and is not an official document of UBC. Furthermore, readers should bear in mind that these reports may not reflect the current status of activities at UBC. We urge you to contact the research persons mentioned in a report or the SEEDS Sustainability Program representative about the current status of the subject matter of a project/report".*

# Executive Summary

In September 2016, UBC SEEDS Sustainability Program tasked Jade Consulting with the re-design of the Wesbrook Mall and Chancellor Blvd intersection to provide a safe and comfortable travel experience for pedestrians, cyclists and motorists. The current design configuration does not promote safety and user friendliness in addition to the anticipated, increased traffic demands of UBC. The new design aims to mitigate issues arising from the current configuration with a roundabout intersection coupled with a vertical structure that prominently features the intersection as one of UBC's welcoming gateways.

The proposed intersection design features a single-lane roundabout consistent with the BC MoT roundabouts "first" policy to address existing safety and inefficiency concerns. For the structural component, a 9 meter tall, timber frame lookout tower with glass facade that supplements UBC's sustainability goals while maintaining driver sight line and intersection safety was designed.

The forecasted class B cost estimate which entails a 15% contingency for the construction of the intersection and lookout tower is **\$1.3 million CDN**. To minimize disruption to the neighbourhood, staff, students and UBC's daily operations, construction will commence in **May 2017** and finish in **August 2017**.

The following report outlines the specific design features of the project as well as the design inputs and estimated costs.

# Table of Contents

|   |    |
|---|----|
| <b>Executive Summary</b> .....                  | i  |
| <b>1.0 INTRODUCTION</b> .....                   | 1  |
| <b>2.0 DESIGN COMPONENTS</b> .....              | 3  |
| 2.1 Transportation Component .....              | 3  |
| 2.1.1 Roundabout Description.....               | 3  |
| 2.1.2 Road User Accommodation .....             | 4  |
| 2.2 Structural Component.....                   | 5  |
| <b>3.0 TRANSPORTATION DESIGN ANALYSIS</b> ..... | 6  |
| 3.1 Design Criteria.....                        | 6  |
| 3.2 Standards and Software .....                | 7  |
| 3.3 Traffic Analysis .....                      | 8  |
| 3.3.1 Traffic Volume Projection .....           | 8  |
| 3.3.2 Synchro Model Output.....                 | 8  |
| 3.4 Sightline Analysis .....                    | 9  |
| <b>4.0 STRUCTURAL DESIGN ANALYSIS</b> .....     | 10 |
| 4.1 Standards and Software .....                | 10 |
| 4.2 Design Criteria and Analysis.....           | 10 |
| 4.3 Foundation Design .....                     | 11 |
| 4.3.1 Soil Conditions .....                     | 11 |
| 4.3.2 Bearing Capacity.....                     | 12 |
| 4.4 Bracing Design .....                        | 12 |
| 4.5 Connection Design .....                     | 12 |
| 4.6 Member Design .....                         | 13 |
| <b>5.0 COST MANAGEMENT</b> .....                | 15 |
| 5.1 Traffic Design Costs .....                  | 15 |
| 5.1.1 Initial Capital Costs .....               | 16 |
| 5.1.2 Maintenance Costs .....                   | 16 |
| 5.2 Structural Design Costs.....                | 16 |
| <b>6.0 SCHEDULE MANAGEMENT</b> .....            | 17 |
| 6.1 Construction Planning.....                  | 17 |
| 6.2 Construction Zones .....                    | 17 |
| 6.3 Construction Schedule.....                  | 18 |

|  |           |
|--|-----------|
| 6.4 Construction Progress Tracking.....                            | 20        |
| <b>7.0 STAKEHOLDER MANAGEMENT .....</b>                            | <b>21</b> |
| 7.1 Stakeholder Identification .....                               | 21        |
| 7.2 Stakeholder Assessment .....                                   | 21        |
| 7.3 Stakeholder Communication Plan.....                            | 22        |
| 7.4 Stakeholder Engagement .....                                   | 23        |
| <b>8.0 CONSTRUCTION MANAGEMENT.....</b>                            | <b>25</b> |
| 8.1 Safety Management .....  | 25        |
| 8.2 Public Safety Management Plan.....                             | 25        |
| 8.3 Traffic Management.....  | 26        |
| 8.4 Emergency Response Plan .....                                  | 27        |
| <b>9.0 RISK MANAGEMENT .....</b>                                   | <b>28</b> |
| <b>10.0 ENVIRONMENTAL MANAGEMENT.....</b>                          | <b>31</b> |
| 10.1 Greenhouse Gas Emission.....                                  | 31        |
| 10.2 Storm Water Management and Landscaping.....                   | 32        |
| 10.3 Environmental Impacts Management.....                         | 32        |
| <b>11.0 CONCLUSIONS .....</b>                                      | <b>34</b> |
| <b>12.0 RECOMMENDATIONS .....</b>                                  | <b>35</b> |
| REFERENCES .....   | 36        |
| APPENDICES.....  | 38        |
| APPENDIX A – TRANSPORTATION .....                                  | 39        |
| APPENDIX B – STRUCTURAL.....                                       | 41        |
| Appendix B1 – List of Assumptions for Lookout Tower Analysis ..... | 42        |
| Appendix B2 – List of Assumptions for Member Design .....          | 42        |
| Appendix B3 – NBCC Load Calculations .....                         | 43        |
| Appendix B4 – Foundation Design .....                              | 47        |
| Appendix B5 – Member Design Calculations .....                     | 48        |
| Appendix B6 – Structural Drawings .....                            | 55        |
| APPENDIX C – COST.....   | 57        |
| APPENDIX D – STAKEHOLDER REGISTER.....                             | 64        |
| APPENDIX E – GANTT CHART .....                                     | 66        |
| APPENDIX F – TRAFFIC MANAGEMENT PLAN.....                          | 71        |

## Table of Figures

|  |    |
|--|----|
| Figure 1 Intersection of Chancellor Boulevard and Wesbrook Mall .....  | 1  |
| Figure 2 Proposed roundabout design at Wesbrook Mall & Chancellor Blvd.....  | 3  |
| Figure 3 Rectangular Rapid Flash Beacons ( <a href="http://www.solar-traffic-controls.com">http://www.solar-traffic-controls.com</a> ) ..... | 4  |
| Figure 4 Short Pedestrian Crossings (Google earth).....  | 4  |
| Figure 5 A Rendering of the Lookout Tower Located to the East of the Roundabout .....  | 5  |
| Figure 6 Proposed Single-lane Roundabout.....  | 6  |
| Figure 7 Roundabout Sightline Analysis .....   | 9  |
| Figure 8 Construction zones at the intersection .....  | 18 |
| Figure 9 Stakeholder Analysis Map.....   | 22 |
| Figure 10. Timeline of Implementation of Communication Plan .....  | 23 |

## List of Tables

|  |    |
|--|----|
| Table 1 Student Contribution.....                            | 2  |
| Table 2 Key Roundabout Design Criteria.....                  | 7  |
| Table 3 Existing and Projected Vehicle Traffic Volumes ..... | 8  |
| Table 4 Roundabout Volume to Capacity Ratio Projection.....  | 8  |
| Table 5 Factored Loads for NBCC Load Cases.....              | 11 |
| Table 6 Summary of Load Analysis .....                       | 11 |
| Table 7 Targeted completion dates of project milestones..... | 19 |
| Table 8 Methods of Stakeholder Engagement .....              | 24 |
| Table 9. Risk rating matrix .....                            | 29 |
| Table 10 Potential Conflicts and Management Strategy .....   | 30 |
| Table 11 Greenhouse Gas Emissions.....                       | 32 |
| Table 12 Management Strategies for Environmental Issues..... | 33 |

## 1.0 INTRODUCTION

The design of the intersection at Chancellor Boulevard and Wesbrook Mall has been identified to be unsafe and inefficient. Jade Consulting has been tasked to develop an adequate design of the intersection as well as a welcoming structure to meet with UBC's requested criteria. These criteria include increasing user safety, sustainability, cost-effectiveness and the requirement of meeting the future traffic demand.

The project is located at Chancellor Boulevard and Wesbrook Mall, one of the main entry points to UBC from West 4th Avenue. Figure 1 below shows the location of the project:



*Figure 1 Intersection of Chancellor Boulevard and Wesbrook Mall*

This important intersection sees over 1,000 vehicles during the peak hour and serves the #44 and #84 busses. The current design configuration is unconventional and poses deficiencies for cyclists, pedestrians and motorists.

The main objective of the project is to design an intersection that improves the safety and provides a pleasant travel experience for all modes of traffic. The new design will:

- Meet future anticipated demands for all modes of transportation
- Improve safety for pedestrians, cyclists and vehicles
- Maximize operational efficiency

- Optimize project costs
- Promote sustainability
- Incorporate a welcoming gateway to the UBC campus

Table 1 below breaks down each team member’s contribution to the preliminary design report. If the same section appears twice it means that those two team members collaborated on that specific section.

*Table 1 Student Contribution*

| <b>Student</b>           | <b>Contribution</b>  |
|--------------------------|--|
| <b>Alexander Liaw</b>    | 3 Transportation Design Analysis   |
| <b>Kellie Liu</b>        | 8.1 Construction Safety Management<br>9 Risk Management<br>10 Environmental Management   |
| <b>Lorena Polovina</b>   | 1 Introduction<br>2 Design Components  |
| <b>Kimberly Subianto</b> | 6 Schedule Management<br>7 Stakeholder Management<br>8.2 Public Safety Management<br>8.3 Traffic Management<br>8.4 Emergency Response Plan |
| <b>Howard Wong</b>       | 4 Structural Design Analysis   |
| <b>Jordan Yang</b>       | 5 Cost Management<br>11 Conclusion & Recommendations   |


## 2.0 DESIGN COMPONENTS

### 2.1 Transportation Component

#### 2.1.1 Roundabout Description

The proposed solution for the Wesbrook Mall and Chancellor Blvd intersection features a single-lane roundabout configuration, designed according to the British Columbia Ministry of Transportation (BC MOT) standards. This design targets the existing poor vehicle level of service by better controlling vehicle movement and also accommodates pedestrians and cyclists with marked crossing lanes that have flashing beacons to capture driver's attention. These modifications greatly increase the efficiency and safety of the intersection.

A drawing of the proposed roundabout design is presented in Figure 2.



*Figure 2 Proposed roundabout design at Wesbrook Mall & Chancellor Blvd.*

Key components of the roundabout include:

- A shared path that facilitates safe pedestrian and cyclist movements
- A low profile mountable apron surrounding the central island to facilitate and accommodate bus and WB 17 semi-truck movements



- Preserved landscaping in existing boulevards along with new landscaping at reclaimed green space

### 2.1.2 Road User Accommodation

The roundabout enhances the overall pedestrian experience and improves accessibility with proper sidewalk, curb ramps, and truncated domes. Clear, well-marked crossings coupled with rectangular rapid flash beacons at all legs of the intersection inform motorists of their requirement to yield. The usage of short crossings allows pedestrians to cross a busy two-way street one section at a time, which greatly improves pedestrian safety. In addition to proper yield signage and zebra crossing, the roundabout road geometry naturally reduces vehicle speeds and contributes to pedestrian comfort at the intersection.



*Figure 4 Short Pedestrian Crossings (Google earth)*



*Figure 3 Rectangular Rapid Flash Beacons (<http://www.solar-traffic-controls.com>)*

The roundabout accommodates cyclists in two ways. Cyclists with more experience may share the roadway operating the intersection as a vehicle would and yielding to pedestrians. All other cyclists may use the 3m wide shared path and cross the intersection safely. The roundabout resolves many existing cycling issues, including the requirement to merge across an active vehicle through lanes to make a left turn.

As mentioned in the previous section, the roundabout design accommodates passenger vehicles, as well as busses and WB 17 semi-trucks. Key benefits of the roundabout include a reduction of conflict points and collisions for drivers. Furthermore, crash severity is reduced as roundabout eliminates head-on collisions. The roundabout also reduces delay and fuel consumption compared to other intersection treatments as drivers are not required to fully stop at the intersection.

## 2.2 Structural Component

As requested by UBC SEEDS Sustainability Program, a welcoming gateway component has been considered as part of the complete design. Through multiple criteria and constraints relating to spacing requirements, aesthetics and safety, a lookout tower composed of wood was designed.

The tower is a timber frame system comprising of glulam columns and beams with glass panels for the walls and CLT for the floors. The structure contains two cantilevered walkways, located on both floors, where visitors are welcome to appreciate the luscious surroundings. The structure complements the roundabout design which is located at the southeast corner of the roundabout. Most importantly, the lookout tower does not obstruct the sightlines of drivers. A rendering of the lookout tower can be shown on Figure 5 on the next page:



*Figure 5 A Rendering of the Lookout Tower Located to the East of the Roundabout*

### 3.0 TRANSPORTATION DESIGN ANALYSIS

The proposed single-lane roundabout adheres to the BC MOT “roundabouts first” policy that supports the Province’s Climate Action Program of 2007. A drawing of the proposed design has been provided below in Figure 6. As seen and documented in many precedent examples, a roundabout design provides safety and accessibility benefits for all users. It also facilitates driver expectation by providing design consistency between the W 16<sup>th</sup> Avenue at Wesbrook Mall and East Mall intersections. The following sections outline the proposed roundabout’s design criteria, traffic analysis and sightline analysis components.




Figure 6 Proposed Single-lane Roundabout

#### 3.1 Design Criteria

The proposed roundabout was designed to meet several criteria including safety, pedestrian accommodation, cyclist accommodation, vehicle accommodation, serviceability, sustainability, vehicle level of service (LOS) and aesthetics. The following table goes into detail with respect to each design criteria and explains how the proposed design meets the design criteria.

Table 2 Key Roundabout Design Criteria

| Design Criteria                 | Significance   |
|---------------------------------|--|
| <b>Safety</b>                   | <p>The most important criteria of the design were to ensure the safety of all modes of travel including pedestrians, cyclists and vehicles. The proposed design incorporates proper signage and utilizes driver expectancy by having a design like the Wesbrook Mall and W 16<sup>th</sup> Ave roundabout intersection.</p> <p>The roundabout also reduces collision severity as it eliminates all head-on-collisions associated with traditional intersections.</p> |
| <b>Pedestrian Accommodation</b> | <p>The existing intersection lacked proper crosswalks and curb ramps. The proposed design incorporates clear, well-marked crossings coupled with rectangular rapid flash beacons to inform motorists of their requirement to yield.</p>  |
| <b>Cyclist Accommodation</b>    | <p>The existing intersection is unsafe and proves very difficult for cyclists to make turns. The proposed design incorporates a 3m wide shared path that allows cyclists to operate the intersection as a pedestrian would safely and comfortably.</p>   |
| <b>Vehicle Accommodation</b>    | <p>The proposed roundabout accommodates passenger vehicles, articulated busses and WB17 semi-trucks.</p>   |
| <b>Sustainability</b>           | <p>The roundabout reduces greenhouse gas emissions as total vehicle delay time is reduced at the intersection.</p>   |
| <b>Serviceability</b>           | <p>The roundabout requires landscape maintenance with the introduction of landscaped medians.</p>  |
| <b>Aesthetics</b>               | <p>The roundabout design incorporates pleasing aesthetic components including landscaped boulevards and roundabout centre.</p>   |

### 3.2 Standards and Software

The geometric design of the roundabout is governed by the TAC Geometric Design Guide and the BC MOT Roundabouts Supplement. In addition to the design standards, the UBC Transportation Plan was consulted to ensure that the design promotes and enables UBC’s sustainability goals and mode share targets. Software used during the design process includes AutoCAD 2014 for the design drawing and Synchro 6.0 for traffic analysis.

### 3.3 Traffic Analysis

#### 3.3.1 Traffic Volume Projection

2015 AM and PM peak hour traffic count data for the Wesbrook Mall and Chancellor Blvd intersection was provided by UBC. Given UBC’s target to maintain or reduce daily private automobile traffic, a 1% growth rate was applied. The following table provides existing 2015 peak hour traffic volumes, projected 2017 opening day traffic volumes and a 30-year project of traffic volumes in 2047.

*Table 3 Existing and Projected Vehicle Traffic Volumes*

|                     | <b>Eastbound through</b> | <b>Eastbound Right</b> | <b>Westbound Left</b> | <b>Westbound Through</b> | <b>Northbound Left</b> | <b>Northbound Right</b> |
|---------------------|--------------------------|------------------------|-----------------------|--------------------------|------------------------|-------------------------|
| <b>2015 AM Peak</b> | 124                      | 75                     | 428                   | 404                      | 71                     | 114                     |
| <b>2017 AM Peak</b> | 126                      | 77                     | 437                   | 412                      | 72                     | 116                     |
| <b>2047 AM Peak</b> | 167                      | 101                    | 577                   | 545                      | 96                     | 154                     |
|                     |                          |                        |                       |                          |                        |                         |
| <b>2015 PM Peak</b> | 365                      | 80                     | 96                    | 107                      | 53                     | 243                     |
| <b>2017 PM Peak</b> | 372                      | 82                     | 98                    | 109                      | 54                     | 248                     |
| <b>2047 PM Peak</b> | 502                      | 110                    | 132                   | 147                      | 73                     | 334                     |

#### 3.3.2 Synchro Model Output

Due to limitations of the Synchro 6.0 software provided, intersection delay and LOS for the proposed roundabout cannot be determined. The following table displays the volume to capacity ratio output based on applying a 1% growth rate as mentioned above.

*Table 4 Roundabout Volume to Capacity Ratio Projection*

|                          | <b>Eastbound</b> | <b>Westbound</b> | <b>Northbound</b> |
|--------------------------|------------------|------------------|-------------------|
| <b>2017 AM Peak Hour</b> | 0.23             | 0.71             | 0.16              |
| <b>2017 PM Peak Hour</b> | 0.39             | 0.17             | 0.33              |
| <b>2047 AM Peak Hour</b> | 0.35             | 0.96             | 0.23              |
| <b>2047 PM Peak Hour</b> | 0.54             | 0.23             | 0.49              |

As expected, the AM volume to capacity ratio for the westbound leg is the highest as students and staffs commute to UBC in the morning. It should be noted that the 1% growth rate applied may represent a worse-case scenario. As UBC continues to work towards its sustainability goals of achieving two-thirds of all trips to and from UBC be made by walking, cycling or transit by 2040, traffic volumes may decrease and the roundabout will remain operational beyond its 30-year design life.

### 3.4 Sightline Analysis

Adequate sightline and stopping sight distance is paramount to the safe operation of the roundabout. Due to incomplete sightline analysis within the BC MOT Roundabouts Guideline, the Kansas Roundabout Guide Second Edition was consulted.

A complete sightline analysis was carried out based on the requirements outlined in the Kansas Roundabout Guide. Sight distances checked include the stopping sight distance on the approach, stopping sight distance on the circulatory roadway, sight distance to crosswalk on exit and the intersection sight distance. The following diagram illustrates sightlines required by vehicles to safely travel through the roundabout. It should be noted that all areas shaded in green will be low growth landscaping to maintain driver sightlines.




Figure 7 Roundabout Sightline Analysis

## 4.0 STRUCTURAL DESIGN ANALYSIS

### 4.1 Standards and Software

Standards including the National Building Code of Canada 2005 (NBCC) and Canadian Wood Council (CWC) Design Manual were followed for the design of the lookout tower. On top of the design standards, guidelines including the UBC Technical Guidelines outline the code of quality and performance of the design. SAP2000 was used for the finalized analysis approach for the building and to check member forces for adequate member sizing. Detailed sample hand calculations through the CWC Design Manual were used to verify limit states design of members with the obtained forces in SAP2000.

### 4.2 Design Criteria and Analysis

In compliance with the design standards, primary criteria that were considered in the lookout tower were the following:

1. Compliance to the load combination and used in structural analysis for sizing members.
2. Bracing system required for horizontal loads (Wind and Earthquake Loads).
3. Design checks and correct section properties in accordance to the Canadian Wood Council Design Manual.
4. Compliance of UBC Technical Guidelines for un-factored design loads.
5. Compliance of traffic sightline design issues

In the above design criteria, the design life was considered to be 1 in 50 year as this was common for most building structures and is a minimum for design load data for Vancouver in the NBCC.

As a part of the design of the structural lookout tower, the components must comply with the design loads. Therefore, a structural analysis on SAP2000 was performed. A simplified 2D frame analysis of the lookout tower was decided to represent one face of the lookout tower. The following table below represents the factored loads used in the analysis in SAP2000 in accordance to NBCC:

Table 5 Factored Loads for NBCC Load Cases

| Component                                      | Dead Load | Live Load | Snow Load | Wind Load | Earthquake Load |
|--|-----------|-----------|-----------|-----------|-----------------|
| <b>Roof</b>                                    | 1.1 kN/m  | 2.25 kN/m | 13 kN/m   | 4.65 kN/m | 2kN             |
| <b>1<sup>st</sup> and 2<sup>nd</sup> Floor</b> | 1.38 kN/m | 10.8 kN/m | -         | 4.65 kN/m | 0.82kN & 1.64kN |
| <b>Balcony</b>                                 | 1.38 kN/m | 10.8 kN/m | -         | -         | -               |

Factored load calculations for the above table can be found in Appendix B3. With the factored loads in the above table, two analyses were carried out. These were:

- Vertical Direction Load Analysis (Dead, Live, Snow Load) – NBCC Load Case 2& 3
- Horizontal Direction Load Analysis (Wind, Earthquake Load) – NBCC Load Case 4 or Case 5

In addition, while simplifying the tower into a 2D frame analysis, some assumptions were made during the modelling and analysis of the tower. The list of assumptions can also be found in Appendix B1. For our lookout tower analysis, case 2 and case 4 were the governing cases and will be used in designing the structural members. After running the analysis in SAP2000, the two cases give the governing loads in each member type are as follows in the below table:

Table 6 Summary of Load Analysis

|                               | Columns | Beams | Bracing |
|-------------------------------|---------|-------|---------|
| <b>Shear Force (kN):</b>      | 10      | 65    | 30      |
| <b>Axial Force (kN):</b>      | 450     | 30    | 55      |
| <b>Bending Moments (kNm):</b> | 10      | 100   | 50      |

## 4.3 Foundation Design

### 4.3.1 Soil Conditions

For the design of the lookout tower foundation, a geotechnical investigation is required to obtain the soil profile and parameters. Due to the lack of site-specific information, available soil profiles for other parts of UBC are assumed for foundation calculations as seen in the Appendix B4. The assumed specific weight of the soil is 16 kN/m<sup>3</sup>. This value is based on variations of past geotechnical related report from past projects at UBC.



### 4.3.2 Bearing Capacity

Based on the assumed soil profile and soil parameters, 2m by 2m square concrete footings at 1.5m deep with a bearing capacity of 124 kPa is recommended. This total bearing capacity converts to an allowable force of 496 kN which is suitable for our structure thus extra piling reinforcement will not be required. The capacity is derived from using the formula found in Budhu's Foundation and Earth Retaining Structures and the Allowable Stress Design Method (Budhu, 2007). The following formula was used:

$$q_{ult} = \sigma'_D N_q + 0.4\gamma' B N_\gamma$$

### 4.4 Bracing Design

With a moment released frame design, the emphasis on an effective bracing system is important as horizontal forces need to be resisted. For the lookout tower, full cross bracing is implemented in between the floor sections where space is opened. However, for floor sections with a balcony opening, a modified bracing is required. This is to resolve the accessibility issues if full cross braces were to be placed. Through careful considerations and research advice from UBC Professor Thomas Tannert, knee braces were chosen to be placed at the corners of the frames. To simplify calculations, capacities of these knee bracing should be equal to those of a full bracing.

### 4.5 Connection Design

Considering a moment released frame design, the connections of the entire structure will be pinned with steel bolts and plates. The required capacity for the bolts and plates for the frame is taken to be the governing axial force of the design members. This corresponds to 55 kN. The finalized connection design accordingly to CSA standards given in the CWC Wood Design Manual is (design calculations found in Appendix B5):

- Two 6 mm steel internal plates with 2 rows of 3 fasteners spaced at 80 mm

The resistance of the connection is 56 kN which is less than the member capacities resulting in a connection failure before member failure. This is considered to be ideal as the connection will provide ductile yielding effects in steel rather than a brittle failure mode due to the properties of wood products.

## 4.6 Member Design

Based on the structural analysis done in SAP2000, member design of the columns and beams have been performed based on CWC Wood Design Manual 2015 and Canadian Standards Association. The member design accounts for various capacity checks due to applied factored loads. Certain assumptions have been made during the member design which primarily involves service conditions of the members. These can be found in the Appendix B5 with detailed calculations of member design.

Member design comprised of checking serviceability limit state and ultimate limit state. These apply to columns and beam members of the lookout tower. For easy of construction and limiting repetition of work, the building is assumed to have the same column and beam members. The following are resistance forces and limit state conditions components for the building members that have been checked accordingly to the code:

For Column Members:

- Factored Compressive Resistance
- Factored Combined Loading (Axial and Moment)
- Shear Force Member Capacity
- Serviceability Deflection

For Beam Members:

- Moment Member Capacity
- Shear Force Member Capacity
- Serviceability Deflection
- Maximum Distributed Load

For Bracing Members:

- Row Shear Resistance
- Group Tear-Out Resistance

- Net Tension Resistance

After compiling together the design check, the finalized dimensions of the member are given below with the grade of wood:

- **COLUMN:** Glulam Douglas Fir Larch 24f-EX : 315mm x 380mm
- **BEAM:** Glulam Douglas Fir Larch 24f-EX : 365mm x 380mm
- **BRACING:** Glulam Douglas Fir Larch 24f-EX: 265mm x 342mm

## 5.0 COST MANAGEMENT

The estimated costs for the project were based upon the implementation of the roundabout under BC MOT standards and the installation of the new lookout tower. After the consideration of construction costs and engineering costs, project management and environmental factors were scaled on a percentage basis from those values as suggested by APEGBC and BC MOT standards.

A final cost of **\$1.3 million** is forecasted under the assumption that it is class B cost estimation. This entails a 15% contingency for several aspects of the estimate which may be reduced further into the project as more certainty is developed in the detailed design stage. Roughly \$50 thousand of the total value is allocated towards the creation of the lookout tower factoring in material, labour, and engineering costs to the owner.

### 5.1 Traffic Design Costs

Following the Ministry of Transportation's framework in cost estimating, we were able to follow a step-by-step process in the projected values given for this design project. The estimating process derived from precedent examples and unit costs of materials for this specific location and was the basis of where many of the assumptions are created. One of the more notable assumptions was that property values and levies would be assumed to be waived because the property is under the jurisdiction of UBC Endowment Lands as well as the Ministry of Transportation. Furthermore, any planning, project management, and environmental costs were appropriately scaled accordingly to construction costs of the project by certain percentages as suggested by APEGBC or the Ministry of Transportation samples. Refer to Appendix C for a more comprehensive list of project information and assumptions made for the intersection location.

### 5.1.1 Initial Capital Costs

The initial capital costs include a variety of elements which include

- Project Management
- Planning
- Design
- Environmental Factors
- Construction
- Past Costs

After applying contingency values, a mark-up was considered for outsourced contractors and applicable taxes which resulted in a sum of \$602,267.40. A cost breakdown can be found in Appendix C.

### 5.1.2 Maintenance Costs

The yearly maintenance costs considered is very low because it lacks any traffic signals. Unlike other intersections, the use of those signals allows for lower cost and maintenance for only landscaping and electrical for the rectangular rapid flashing beacons. Please refer to Appendix C for the breakdown of yearly costs that sum up to a total of \$1,655.81/year.

## 5.2 Structural Design Costs

The structural design portion of the project included the cost of engineering, skilled workers required, as well as material costs. Sigma estimates and the libraries of an RSMeans Database were used to project these costs to be \$70,687 with the inclusion of the 15% contingency. All of the design measurements were provided through a building information model created in Revit to assume a more accurate estimate in both lengths and areas.

## 6.0 SCHEDULE MANAGEMENT

To ensure a smooth and timely project delivery, a project master schedule is developed with the aid of Microsoft Project software. In addition, the schedule management process allows project and construction managers to plan the construction of project more efficiently and smoothly.

### 6.1 Construction Planning

Construction is scheduled to begin in May 2017 and will commence for duration of 55 days up to August 2017. A 10%-time contingency has been included in the construction duration to address potential construction conflicts that may arise. This start date is selected due to the lower traffic volumes in and out of the UBC campus throughout the summer months. This mitigates the impact construction has on traffic and allows full closure of intersection. In addition to the lower traffic impact, the weather during the summer months is preferable for certain construction activities, such as concrete pour.

In the development of the construction schedule, precedent studies have been conducted and project scheduling workshops attended by design teams, construction operations and other key stakeholders have been held. All necessary Work Breakdown Structure (WBS) were created and the durations for each work were determined based on historical information and known project-specific conditions. It is also essential to determine the task dependencies between work activities and assess the possibility of scheduling simultaneous work to increase inefficiency and decrease project duration.

### 6.2 Construction Zones

For the purposes of progress tracking and effective management of physical works, the construction of the project at the intersection has been sectioned to the following construction zones (shown in Figure 8):

- **Zone A:** North of the intersection
- **Zone B:** South-East of the intersection
- **Zone C:** South-West of the intersection
- **Lookout Tower:** East of the intersection on the median




Figure 8 Construction zones at the intersection

### 6.3 Construction Schedule

Table 7 summarizes the targeted completion dates of different milestones throughout the construction phase. As seen in the table, the expected duration for all construction work is 64 working days, and it will proceed from May 5 to July 14, 2017. This is a reasonable duration for a project of such scale, however, to take into account the potential conflict that may arise, a 10% time contingency is added to the schedule. The duration of construction, with the added time float, is 61 days. For most activities, work is coordinated to commence simultaneously in order to decrease the project duration and therefore, the disruption of traffic.

Table 7 Targeted completion dates of project milestones

| Activity                              | Start Date | Finish Date | Duration (days) |
|---------------------------------------|------------|-------------|-----------------|
| <b>CONSTRUCTION</b>                   | May 1      | Jul 14      | 55              |
| <b>Site Preparation</b>               | May 1      | May 12      | 10              |
| <b>Grading</b>                        | May 15     | May 30      | 12              |
| <b>Reinstallation</b>                 | May 31     | Jun 6       | 5               |
| <b>New Medians Build</b>              | May 31     | Jun 15      | 12              |
| <b>Structural Lookout Tower Build</b> | Jun 9      | Jul 6       | 20              |
| <b>Curbs and Ramp Build</b>           | Jun 7      | Jun 23      | 13              |
| <b>Sidewalks Build</b>                | Jun 26     | Jun 27      | 2               |
| <b>Streets Paving</b>                 | Jun 28     | Jun 29      | 2               |
| <b>Roundabout Build</b>               | Jun 30     | Jul 5       | 4               |
| <b>Finishing</b>                      | Jul 6      | Jul 11      | 4               |
| <b>Construction Close-Out</b>         | Jul 12     | Jul 14      | 3               |

Because the lookout tower components are prefabricated off-site, a delivery date will be scheduled a week prior to installation to ensure a complete set of materials and resources are available in time for installation. In addition to the coordination of materials delivery, the following pre-construction requirements are expected to be completed to ensure a timely starting date for construction:

1. Issuance of IFC Drawings: March 1, 2017
2. Soil Contamination Test: March 31, 2017
3. Project Permit: April 14, 2017
4. First Nations Permit (if required): April 14, 2017
5. Geotechnical Assessment: April 14, 2017
6. Topographic Survey: April 19, 2017
7. WorkSafe BC Notice of Project: April 21, 2017
8. Delivery of Structural Component: June 9, 2017

A detailed project Gantt chart is attached in this report as Appendix E, with the critical path marked in red line.



## 6.4 Construction Progress Tracking

The project team is required to adhere to the schedule developed and commit resources as necessary to meet the target dates. The master schedule will be reviewed bi-weekly and actual site progress will be tracked against the baseline progress. The results of the progress updates will be reported on the project monthly report. In addition, to ensure that construction progresses in a manner that is timely, the following construction management processes are to be followed:

1. Hold weekly construction meetings to review progress, address issues, plan actions to be taken and develop a 3-week look ahead schedule
2. Hold bi-weekly project coordination meetings to be attended by design leads, construction superintendents, finance department and other key stakeholders to ensure coordination of all work on site
3. Maintain clear, complete and updated documentation of construction progress and productivity
4. Site superintendent to produce weekly schedule progress report to be submitted to project manager
5. Consistently update Master Schedule on Microsoft Project according to actual site progress

## 7.0 STAKEHOLDER MANAGEMENT

Stakeholder management is an essential aspect of the project as it considers the expectations and requirements of key stakeholders throughout the lifecycle of the project. There are four key activities that are associated with stakeholder management, as follows:

- Identification of stakeholders
- Assessment of interests and influence
- Development of communication management plan
- Engagement of stakeholders

### 7.1 Stakeholder Identification

Stakeholders are individuals who have a certain degree of interest in the project, as well as those who may be directly or indirectly impacted by the outcome of the project. Identification of stakeholders in this project was done through group brainstorming and studies on previous projects. The stakeholders identified to provide input to the project is shown in APPENDIX D. Stakeholder identification is a continuous process, and any additional stakeholders identified will be incorporated into the stakeholder management process.

### 7.2 Stakeholder Assessment

To achieve success in a project, it is important to understand the expectations each stakeholder has in the improvement made by the project. It is also important to assess the level of influence each of the project stakeholders has in the project, as it will affect the decision-making process. Each stakeholder will be classified based on their level of interest and influence in the project on a scale of low, medium and high. The level of interest and influence will then be used to identify the appropriate stakeholder engagement approach (i.e. consult, collaborate or inform) as shown in the stakeholder analysis map in Figure 9, which will be further explored in the next section. Appendix D presents the stakeholder register that outlines the stakeholders identified, along with the assessment of their interest and influence on the project.




Figure 9 Stakeholder Analysis Map

### 7.3 Stakeholder Communication Plan

A stakeholder communication plan is required for the project to ensure relevant information is delivered to the right stakeholders through an appropriate means in a timely manner. The communication plan is developed to improve the overall operational effectiveness, build relationships with stakeholders and eventually achieve the project objectives. The project team will implement the communication strategies through the following channels throughout the project lifecycle to ensure stakeholders are well-notified:

- **Project Website**  
Content of website is to be updated regularly with announcements regarding any project changes, construction schedule and impacts. The website can also offer the public with opportunities to provide feedbacks on the project.
- **Notification Letters**  
Any impact from construction, such as detours, road closures and utility shutdown, is to be communicated to residents and the UBC communities through letters. These notification letters are expected to be delivered one week prior to the impact.
- **Media Releases**  
News release can be the most cost-effective way of gaining publicity for the project, as well as in educating the public about the project background and the outcome it wishes to accomplish.
- **Public Consultation and Open House**  
This provides stakeholders with opportunity to raise concerns, express support and ask questions regarding the project.

It is essential to develop an on-going and consistent communication with the stakeholders, to listen and consider any inputs they may have, as well as to maintain an appropriate level of transparency. Figure 10

briefly outlines the timeline of the implementation of the communication strategy throughout the project lifecycle.




Figure 10. Timeline of Implementation of Communication Plan

Figure 10 Timeline of Implementation of Communication Plan

## 7.4 Stakeholder Engagement

As seen on the stakeholder analysis map, the stakeholders can be categorized into three levels of engagement based on their level of interest and influence. Table 8 below summarizes the goal, approach and methods for the three levels of engagement: inform, consult and collaborate. All efforts will be done to ensure healthy relationship is maintained throughout the lifecycle. The stakeholder engagement plan is to be continually maintained and updated as the project progresses.

Table 8 Methods of Stakeholder Engagement

|                 | <b>INFORM</b>   | <b>CONSULT</b>   | <b>COLLABORATE</b>  |
|-----------------|---|--|---|
| <b>GOAL</b>     | To notify stakeholders with relevant and necessary information regarding the project.                                     | To obtain feedback from stakeholders with regards to the project's objectives, decisions and/or alternatives.      | To cooperate with stakeholders in approaching design solution, developing alternatives and making decisions.  |
| <b>APPROACH</b> | Stakeholders will be kept informed of any project's progress and changes.   | Stakeholders' needs and concerns will be acknowledged and considered throughout the project lifecycle.             | Stakeholders' input and expectations will be directly reflected in solutions developed, and any requirements will be incorporated to the maximum extent possible. |
| <b>METHODS</b>  | <ul style="list-style-type: none"> <li>• Open house</li> <li>• Notification letters</li> <li>• Project website</li> </ul> | <ul style="list-style-type: none"> <li>• Public consultation</li> <li>• Focus groups</li> <li>• Surveys</li> </ul> | <ul style="list-style-type: none"> <li>• Workshops</li> <li>• Joint planning</li> <li>• Decision-making meetings</li> </ul>                                       |

## 8.0 CONSTRUCTION MANAGEMENT

### 8.1 Safety Management

A construction safety plan is a written document that describes the necessary procedures to prevent accidents and steps to take when accidents do occur. With acknowledgement to the Work Safe BC and OHS (Occupational Health and Safety) regulations, a construction safety plan can be constructed with the following components:

- Hire a superintendent who is in charge of all safety related issues on construction site during construction period
- Create a safety manual for the workers to strictly follow
- Organize weekly safety meetings for the employees and contractors
- Arrange mandatory worker orientation and training sessions
- Ensure the equipment are used in a safely manner
- Access to first aid on construction site
- Inform the public with a clearly labeled construction zone
- Understand and carry out emergency/accident response when necessary

Additionally, a traffic management plan, public safety management plan and an emergency response plan are discussed to further evaluate safety related concerns during the construction of a roundabout.

### 8.2 Public Safety Management Plan

The objective of the public safety management plan is to analyze the requirements in public safety. The public safety management plan evaluates all the activities associated with the construction of the project. The evaluation is conducted through a public safety risk assessment. The risk assessment examines the hazards to the public associated with the project construction. The hazards are then ranked and scored based on a combination of likelihood and consequence. *“Likelihood refers to the possibility that members of the public will suffer an injury from the activity. Consequence refers to the severity of injury as a result of the worst probable outcome.”* (Construction Safety Management Plan) The risk rating can evaluate the grading of the score for the hazards and the table for the risk rating is shown below.

### 8.3 Traffic Management

According to UBC Campus + Community Planning requirements, a Traffic Management Plan (TMP) needs to be implemented when construction activities pose impact on the circulation and access on the UBC Campus for pedestrians, cyclists, public transit and motorists. It is our goal to best accommodate traffic while work is performed, while ensuring public safety is maintained at all times. A TMP has been developed for the implementation of the project with the consideration of accepted standards, safety, site-specific conditions and impacts on stakeholders.

Throughout the construction phase, a full intersection closure will be taking place, allowing local access only. Although this would result in disruption to the traffic flow and access on campus, a full intersection closure has been deemed most appropriate due to the following reasons:

- Limited work area to provide adequate safety zone for road users
- Road signage and pavement markings to be removed and replaced during construction
- Work area to be used for storage of prefabricated materials delivered by supplier
- Lower traffic volumes at UBC due to the summer season

With the full intersection closure taking place, transit and motor vehicles movement will be impacted. As such, alternate routes have been planned as follow:

1. **East-West Connection:** Motorists to use Acadia Road/NW Marine Drive in place of Chancellor Boulevard
2. **North-South Connection:** Motorists travelling on West 4<sup>th</sup> Ave to turn left at Blanca Street and proceed on University Boulevard for access to UBC
3. **Transit Detour:** Bus 84 and 44 to turn left at Blanca Street and proceed on University Boulevard for access to UBC Bus loop
4. **Shuttle Bus Provision:** To address the missed bus stops along Chancellor Boulevard, a shuttle bus will operate between the bus stop and the Blanca Loop
5. **Shuttle Bus Detour:** Bus C18 to use Iona Drive for access to Chancellor Boulevard and Wesbrook Mall

A complete detour plan for the intersection closure can be found in Appendix F.

In addition to the detour plans to be implemented, the project team will also station flaggers in various areas, as well as install road signage to direct road users. In coordination with Translink, the project team will develop a public information plan to ensure stakeholders are well informed of the traffic impact they can expect. To maintain healthy relationship with stakeholders, a proactive approach will be taken to address any issues and concerns from local residents and users who are directly impacted by the construction activity.

## 8.4 Emergency Response Plan

An emergency response plan provides a structure and guideline to how to respond and manage an emergency that may affect the public, employee or contractor during the construction process. The plan identifies and assesses the potential hazards and risks that may require emergency response. It then develops and implements an effective emergency management and response procedure relevant to the identified potential hazards and risks. The plan also includes a detailed contact list and communication and notification strategy for emergency situations. Lastly, the emergency response plan recommends all employees and contractors to attend worker orientation and training session to bring awareness and help prevent potential hazards and risks.



## 9.0 RISK MANAGEMENT

Risk management is an essential part of construction management. A risk management plan requires preparation to the unforeseen events that happen in construction. This is either through allocating the risk to the respective management team or referring to the contingency plan. Uncertainties in construction are oftentimes inevitable, therefore preparations to mitigate impacts on the overall construction is necessary. Throughout the construction phase of the project, the project team will closely monitor the progress and continually anticipate future tasks to maintain a timely schedule. Following are several considerations that were taken into account during the development of schedule and actions will be taken to manage them:

- *Health and Safety*

Every effort will be made to maintain compliance to WorkSafeBC Standards and Occupational Health and Safety (OHS) Regulations and Guidelines. A more thorough construction safety plan can be found in Section 8 of the report.

- *Traffic Impacts*

Being one of the main entry and exit points into and out of UBC, construction of this intersection is expected to disrupt traffic. As such, construction of project will be sequenced accordingly to avoid full intersection closure and to maintain roadway open to traffic. Traffic planning will be coordinated with a traffic control company to ensure all guidelines and requirements are satisfied. Road signage will be placed and flaggers will be stationed to direct traffic. Work that may require full closure of intersection, such as paving, will be scheduled on the weekends, and project team will ensure the designated stakeholders will be notified. Any information on detours and road closures will also be passed on to Translink, BC Ambulance, RCMP and Vancouver Fire and Rescue Services.

- *Critical Path*

As seen in the schedule Gantt chart attached in Appendix E, the critical path of this project has been identified. A critical path is a network of activities sequence with little to no time float allocated. Any delay in one of the tasks will delay the entire project. The project team will monitor closely the tasks that lie on this path and ensure that all resources are made available in a timely manner.

- *Construction Progress*

Weekly construction meeting is to be held on-site, in which superintendents and the project team may discuss any health and safety matter, review site progress, anticipate construction look-ahead schedule, record stakeholder issues and agree on actions to be taken. Any additional potential schedule conflict will also be discussed in meetings and appropriate actions will be taken. In addition, superintendents are also expected to issue weekly construction status reports to communicate the progress of project.

- *Potential Construction Conflict*

An important aspect in construction management is to anticipate any potential conflict that may arise to allow the project team to take the necessary preventive or mitigating actions. Table 10 below outlines several conflicts that can be expected throughout the construction phase, along with the management strategy.

*Table 9. Risk rating matrix*

| Risk Rating         |                |   | Incident Consequences |     |        |        |          |          |
|---------------------|----------------|---|-----------------------|-----|--------|--------|----------|----------|
|                     |                |   | Insignificant         |     | Minor  | Major  | Critical | Fatality |
|                     |                |   | 1                     | 2   | 3      | 4      | 5        |          |
| Incident Likelihood | Almost Certain | 5 | Med                   | Low | High   | High   | High     | High     |
|                     | Common         | 4 | Low                   |     | High   | High   | High     | High     |
|                     | Possible       | 3 | Low                   |     | Medium | High   | High     | High     |
|                     | Unlikely       | 2 | Low                   |     | Low    | Medium | High     | High     |
|                     | Rare           | 1 | Low                   |     | Low    | Low    | Low      | Low      |

Table 10 Potential Conflicts and Management Strategy

| Potential Conflicts                                  | Risk Classifications             | Level of Impact | Management Strategy   |
|--|----------------------------------|-----------------|---|
| <b>Scheduling related conflicts and delays</b>       | Operational                      | High            | Adding adequate float to accommodate schedule changes; refer to the scheduling contingency  |
| <b>Budget and Cost</b>                               | Financial                        | High            | Refer to the cost contingency (15 percent) for any funding for any scope creep  |
| <b>Traffic Impacts</b>                               | Operational                      | Medium          | Consult traffic management team; refer to traffic management plan   |
| <b>Construction Methodology</b>                      | Technical                        | High            | Consult construction team; refer to the construction management plan  |
| <b>Poor weather condition</b>                        | Health, Safety and Environmental | Low             | Superintendents to monitor weather forecast regularly and have contingency plans in place   |
| <b>Differing site conditions (e.g. hard grounds)</b> | Technical                        | Medium          | Geotechnical assessment to be completed prior to construction   |
| <b>Third-party utilities</b>                         | Operational                      | Medium          | Designers and utilities department to thoroughly study and review the drawings to ensure no third-party utilities is in conflict with the construction zone   |
| <b>Stakeholder issues</b>                            | Reputational                     | Medium          | Project team to be proactive in adopting the stakeholder engagement plan  |
| <b>Archaeological finds</b>                          | Environmental                    | High            | Archaeological impact assessment to be completed prior to construction  |
| <b>Delay in IFC drawings issuance</b>                | Technical                        | High            | Designers to meet the required timelines of design completion   |
| <b>Delay in material deliveries</b>                  | Operational                      | Medium          | Project manager and superintendent to ensure that all procurement and deliveries are scheduled in time for construction                                       |
| <b>Unexpected changes in project scope</b>           | Technical and Operational        | Medium          | Project manager to regularly update the construction Gantt schedule and actively communicate with the designers and owner of any project requirements changes |

## 10.0 ENVIRONMENTAL MANAGEMENT

### 10.1 Greenhouse Gas Emission

The impacts of roundabouts on greenhouse gas emissions depend on the effect on traffic flow. The traffic speed, acceleration, deceleration and most importantly the traffic delay may all effect the greenhouse gas emission at an intersection. The roundabout design encourages slow and consistent traffic speed with minimum idling; all of which can reduce fuel consumption and/or greenhouse gas emission.

The greenhouse gas emission can be computed through the fuel consumption and total delay at the intersection. The total delay time can be converted to fuel consumption: an hour queue is equivalent to one gallon of gas at an intersection. The fuel consumption can then be converted to greenhouse gas emission through a conversion factor of 8,887 grams of CO<sub>2</sub> emissions per gallon of gasoline consumed. Following the mentioned calculation procedure, a greenhouse gas emission for the roundabout design at the intersection of Wesbrook Mall and Chancellor Blvd. at a one hour interval during AM Peak can therefore be computed:

$$\begin{aligned} & \text{Roundabout Configuration (One hour interval)} \\ & = 2.4 \text{ hour} \times 1 \frac{\text{gallon of gasoline}}{\text{hour}} \times \left( 8.887 \times 10^{-3} \frac{\text{metric tons CO}_2}{\text{gallon of gasoline}} \right) \\ & = 0.021 \text{ metric tons CO}_2 \end{aligned}$$

With the synchro analysis being able to analyze every type of intersection configuration, a comparison for the greenhouse gas from the different configurations can be evaluated. From the table below, signalized intersection projects the highest annual greenhouse gas emission due to the long total delay time.

Although the total delay time difference on an hourly basis for the roundabout and stop sign is not significant, the projected annual emission difference between the two configurations is around 0.6 metric tons CO<sub>2</sub> which is considerably notable.

Table 11 Greenhouse Gas Emissions

| <b>Greenhouse Gas Emissions (One hour interval – AM Peak)</b> |                                 |  |   |
|---|---------------------------------|--|---|
| <b>Configurations</b>   | <b>Total delay time (hours)</b> | <b>GHG Emission (metric tons CO<sub>2</sub>)</b> | <b>Annual Projection (metric tons CO<sub>2</sub>)</b> |
| <b>Roundabout</b>   | 2.4                             | 0.021  | 7.78  |
| <b>Signalized</b>   | 9.6                             | 0.056  | 20.44   |
| <b>Stop Sign</b>  | 2.6                             | 0.023  | 8.40  |

## 10.2 Storm Water Management and Landscaping

Storm water in UBC mostly refers to rain, however during winter season melted snow and ice can be a factor as well. The storm water usually runs off from roof, driveway and other hard surfaces into the municipal sewer system. As the water travels to sewers, it picks up pollution along the way; it can contain harmful substances and contaminates. If the storm water is not properly treated, the pollution from the water is released directly into the nearest body of water. This may harm the local water quality and aquatic habitat, therefore awareness to manage the storm water can be very beneficiary in a sustainability standpoint. A landscaping adjustment can be a solution to storm water management.

In terms of landscaping adjustment, a rain garden is a terrific option as it not only helps with the storm water runoff but it also provides an aesthetic appeal to the intersection. A rain garden is a planted/stone covered bed that is specifically designed to receive storm water as the soil absorbs all the storm water that comes in contact. Through the hydrologic cycle, the storm water that is infiltrating into the soil is naturally filtered and cleansed and used by the plants in the garden. The use of landscaping at a roundabout is one of the unique features that separate roundabouts with other traditional intersection configuration as it gives the roundabout design an aesthetic advantage.

## 10.3 Environmental Impacts Management

In unison with the goals of UBC, Jade Consulting commits to minimize the environmental impacts made on the surrounding by the redesign of Chancellor Boulevard and Wesbrook Mall intersection. Construction may have a negative impact on the environment; however, with proper planning and strategy, impacts can be mitigated. During construction stage, the project team will adopt proper

environmental management techniques to meet several sustainability goals. The project team has identified several possible environmental issues associated with the construction of the project which are addressed in Table 12 on the following page.

*Table 12 Management Strategies for Environmental Issues*

| <b>Environmental Issues</b>                | <b>Management Strategy</b>  |
|--|---|
| <b>Carbon Footprint and Emissions</b>      | <ul style="list-style-type: none"> <li>• Choice of less polluting materials will be preferred whenever possible</li> <li>• Proper planning and scheduling of materials sourcing will be done ahead to ensure an efficient transportation logistics</li> </ul> |
| <b>Management of Garbage and Recycling</b> | <ul style="list-style-type: none"> <li>• Comply with UBC’s waste management regulations</li> <li>• Recycling bins to be placed on site</li> </ul>   |
| <b>Dust</b>                                | <ul style="list-style-type: none"> <li>• Water to be sprayed regularly to damp down dust clouds generated from construction</li> <li>• All workers to wear masks or other respiratory protection equipment at all times</li> </ul>                            |
| <b>Wastewater</b>                          | <ul style="list-style-type: none"> <li>• Temporary site drainage to be constructed for collection of construction site wastewater</li> <li>• Stockpile of soil materials to be covered to avoid contamination of surface runoff</li> </ul>                    |
| <b>Hazardous Materials</b>                 | <ul style="list-style-type: none"> <li>• In the case where hazardous materials are found, no construction work will commence until all necessary assessment is conducted and approval to proceed has been given</li> </ul>                                    |

## 11.0 CONCLUSIONS

In conclusion, Jade Consulting proposes to build a single lane roundabout system at the intersection of Chancellor Boulevard and Wesbrook Mall, along with a welcoming gateway structure. The design criteria of the roundabout include increasing user safety, sustainability, cost-effectiveness and the requirement of meeting the future traffic demand. The new design accommodates more modes of transportation, has an increased level of service and is safer.

The welcoming gateway structure is proposed to be a lookout tower composed of wood. Located towards the east of the roundabout, the tower is a nine-meter-tall, timber-frame system with glass panels. There are two cantilevered walkways, located on both floors where visitors can appreciate nature. The tower is designed to not obstruct the sightlines of drivers.

Under a “Class B” Cost Estimate with 15% contingency, the final cost of the roundabout and lookout tower will be \$1.3 million. Approximately \$50,000 of the total project is allocated to the lookout tower, taking things such as material labour and engineering costs into consideration.

Construction is scheduled to start in May 2017 and will last for approximately 55 days. This includes a 10%-time contingency to anticipate potential construction conflicts. The start date was chosen due to lower traffic volumes in and out of UBC during the summer months. A full closure of the intersection is planned during construction. A Traffic Management Plan will address the closure, such as rerouting bus routes, north-south connections, east-west connections and providing shuttle buses.

A detailed Stakeholder Management Plan outlines the steps for stakeholder identification, assessment, communication plan and engagement. There are three different levels of communicating with stakeholders and that includes: inform, consult and collaborate. Different communication methods will be used based on the level of involvement that a stakeholder has.

To take safety into consideration, a Construction Management Plan was written. A Risk Management Plan was also written to consider management strategies for conflicts that may occur on site. Jade Consulting also considers sustainability a priority and looked into greenhouse gas emissions and storm water management of the project.

## 12.0 RECOMMENDATIONS

Jade Consulting recommends the following action items to be complete before construction commences:

1. Further Site Assessments and Impact Analyses
2. Geotechnical Assessments and Topographic Surveys
3. Project Permits and Insurances Procurement
4. Finalize procurement on prefabricated materials
5. On-going stakeholder engagement as planned

These are to ensure all necessary ground conditions and stakeholders' concerns are considered before the hiring of construction workers and contractors to work on-site for implementation planning.

The construction processes are recommended to operate in sections to minimize interference with the intersection being altered. Excavations and all construction practices should follow the safety plan to ensure a more secure and protected working process.

Ongoing measures will take place to ensure the intended purposes of prioritizing safety and sustainable features will be pursued during construction. Any contingencies or unavoidable conflicts will be resolved with these aspects in mind. There will be regular consultation with all involved parties such as the stakeholders and professional working experts under MOTI guidelines as well as environmental experts.



## REFERENCES



1. *Stakeholder Management*, APM Knowledge,  
<http://knowledge.apm.org.uk/bok/stakeholder-management>  
Accessed 1 Nov. 2016
2. British Columbia Government. (2016, July). *Engineering Standards & Guidelines*. Retrieved from Landmark Kilometre Inventory:  
<http://www2.gov.bc.ca/gov/content/transportation/transportation-infrastructure/engineering-standards-guidelines/landmark-kilometre-inventory>
3. *CLT Milestone in Montana - Case Study*, Woodworks,  
<http://www.woodworks.org/wp-content/uploads/CLT-Milestone-Montana.pdf>  
Accessed 23 Nov. 2016
4. *Concrete Price List*, Oceanconcrete, <http://oceanconcrete.com/price-list>, Accessed 23 Nov. 2016
5. *Construction Safety Management Plan*, BC Hydro ,  
<https://www.sitecproject.com/sites/default/files/Construction%20Safety%20Management%20Plan.pdf>. Accessed 24 Nov. 2016.
6. Environmental Issues in Construction, Green Building Solutions.  
<https://greenbuildingsolutions.org/life-cycle-assessment/environmental-issues-construction/>  
Accessed 23 Nov. 2016
7. *Greenhouse Gas Equivalencies Calculator*, US Environmental Protection Agency ,  
<https://www.epa.gov/energy/greenhouse-gas-equivalencies-calculator>. Accessed 24 Nov. 2016.
8. Handy, Susan. *Impacts of Roundabouts on Passenger Vehicle Use and Greenhouse Gas Emissions*, University of Southern California,  
[https://www.arb.ca.gov/cc/sb375/policies/rndabt/roundabout\\_brief.pdf](https://www.arb.ca.gov/cc/sb375/policies/rndabt/roundabout_brief.pdf). Accessed 24 Nov. 2016.
9. *Level of Service*, Wikipedia, [https://en.wikipedia.org/wiki/Level\\_of\\_service](https://en.wikipedia.org/wiki/Level_of_service), Accessed 23 Nov. 2016
10. *Metals and Alloys - Densities*, The Engineering ToolBox,  
[http://www.engineeringtoolbox.com/metal-alloys-densities-d\\_50.html](http://www.engineeringtoolbox.com/metal-alloys-densities-d_50.html), Accessed 23 Nov. 2016
11. Ministry of Transportation. (2013, September). *Highway Planning and Programming Applications*. Retrieved from Guidelines: <https://www.th.gov.bc.ca/Publications/planning/index.htm>
12. *Mississauga Scrap Metal Pricing*, Premier Recycling,  
<http://www.premierrecycling.ca/contact/premier-recycling-mississauga-ltd/pricing/>  
Accessed 23 Nov. 2016

13. Morris, J. & Baddache, F. (2012). Back to Basics: How to make stakeholder engagement meaningful for your company, BSR. [https://www.bsr.org/reports/BSR\\_Five-Step\\_Guide\\_to\\_Stakeholder\\_Engagement.pdf](https://www.bsr.org/reports/BSR_Five-Step_Guide_to_Stakeholder_Engagement.pdf). Accessed 6 Nov. 2016
14. *OHS Regulation & related materials*, Work Safe BC, <https://www.worksafebc.com/en/law-policy/occupational-health-safety/searchable-ohs-regulation>. Accessed 24 Nov. 2016.
15. Project Management Institute. (2013). *A guide to the project management body of knowledge (PMBOK guide) – Fifth Edition*. Newton Square, Pa: Project Management Institute.
16. *Roundabout Workshop Module 4: Construction & Maintenance*, NE Roundabouts. <http://www.roundabouts.cc/2%20Day%20Roundabout%20Workshop%20-%20Part%202.pdf>  
Accessed 9 Nov. 2016
17. *Supplement to TAC Geometric Design Guide*, BC MoT, [www.th.gov.bc.ca/roundabouts/documents/740\\_roundabouts.pdf](http://www.th.gov.bc.ca/roundabouts/documents/740_roundabouts.pdf). Accessed 24 Nov. 2016
18. *Sustainable Development*, International Institute for Sustainable Development, <https://www.iisd.org/topic/sustainable-development>, Accessed 23 Nov. 2016
19. *Wastewater Management*, Environmental Protection Department The Government of Hong Kong, [http://www.epd.gov.hk/epd/english/greenconstruction/poll\\_pro/wastewater\\_management.html](http://www.epd.gov.hk/epd/english/greenconstruction/poll_pro/wastewater_management.html)  
Accessed Nov. 23, 2016
20. *Greenhouse Gas Equivalencies*, EPA United States Environmental Protection Agency, <https://www.epa.gov/energy/greenhouse-gas-equivalencies-calculator>  
Accessed Mar. 6, 2017

# APPENDICES

## **APPENDIX A – TRANSPORTATION**

PRODUCED BY AN AUTODESK EDUCATIONAL PRODUCT



6250 Applied Science Lane  
 Vancouver, BC V6T 1Z4  
 Phone: (604) 583 – 6443  
 www.jadeconsulting.ca

APPENDIX A  
 TRANSPORTATION  
 CONSTRUCTION  
 DRAWING  
 CHANCELLOR BLVD  
 &  
 WESBROOK MALL

**ATTENTION**  
 JADE CONSULTING ASSUMES NO  
 RESPONSIBILITY FOR THE CORRECTNESS OF  
 THE INFORMATION SHOWN.  
 ALL DIMENSIONS SHOWN ON THIS PLAN ARE  
 AS DESIGNED AND NOT AS CONSTRUCTED  
 AND SHOULD BE FIELD CHECKED BY USER  
 OR THEIR AGENT.

Directory: 2017-143-G-00

Date: March 31, 2017

Drawn By: AL

Checked By: HW

T101

SCALE: 1:500

LEGEND

- |  |                 |  |                   |
|--|-----------------|--|-------------------|
|  | CONCRETE MEDIAN |  | BRICK PAVER       |
|  | LANDSCAPING     |  | CONCRETE SIDEWALK |
|  | ASPHALT ROAD    |  |                   |

PRODUCED BY AN AUTODESK EDUCATIONAL PRODUCT

## **APPENDIX B – STRUCTURAL**

## Appendix B1 - List of Assumptions for the Lookout Tower Analysis

### For SAP2000

1. Structure is simplified into a 2D simply supported, moment released frame (pinned-pinned connection).
2. Model is analyzed in simplified 2D combined loads
3. Assume only dead loads and live loads contribute from the second, third and roof assembly members.
4. NBCC Design Manual is applied to each dead load, live load, snow load, earthquake load, wind load.
5. Douglas Fir Larch 24f-EX Material Properties used:
  - a. Modulus of Elasticity: 13100 MPa
  - b. Weight per Unit Volume: 4.8 kN/m<sup>3</sup>
  - c. Poisson Ratio: 0 -> because it is assumed a brittle material
  - d. Coefficient of Thermal Expansion:

### For Load Hand Calculations

1. In the load hand calculations, assume even load distribution within the members of the frame to verify the load outputs in SAP2000.
2. Structure is considered "Normal" hazard in a likelihood of a disaster
3. Class C Soil Conditions
4. Ignore corner effects of wind load.

## Appendix B2 - List of Assumptions for Member Design

1. Dry Service Conditions
2. Load duration is based on standard term loading
3. Glulam will be untreated
4. Simply supported conditions
5. No eccentric loads applied

## NBCC Load Combinations

Case 1:  $1.4D$

Case 2:  $1.25D + 1.5L$


Case 3:  $1.25D + 1.5S$

Case 4:  $1.25D + 1.4W$

Case 5:  $1.0 E$

## APPENDIX B3 – NBCC Load Calculations

### Dead Loads – Distributed Loads



#### **Column and Beam**

Douglas Fir Larch – Glulam: 4800 N/m<sup>3</sup>

#### **Flooring and Façade**

Cedar Wood: 3500 N/m<sup>3</sup>

#### **Roofing**

Skylight Glass: 580 N/m<sup>3</sup>

#### Loads on 2D Frame:

##### Roof Floor

$$\text{Skylight Glass: } 580 \text{ N/m}^3 \times \frac{(6 \text{ meters} \times 5 \text{ centimeters})}{4} = 0.0435 \text{ kN/m}$$

$$\text{Beams: } 4800 \text{ N/m}^3 \times (0.365 \text{ meters} \times 0.38 \text{ meters}) = 0.666 \text{ kN/m}$$

$$\text{Wall: } 580 \text{ N/m}^3 \times (6 \text{ meters} \times 5 \text{ centimeters}) = 0.174 \text{ kN/m}$$

$$\text{Total Dead Load} = \text{Skylight Glass} + \text{Beams} + \text{Walls} = 0.884 \text{ kN/m}$$

##### 1<sup>st</sup> and 2<sup>nd</sup> Floor

$$\text{Beams: } 4800 \frac{\text{N}}{\text{m}^3} \times (0.365 \text{ meters} \times 0.38 \text{ meters}) = 0.666 \text{ kN/m}$$

$$\text{Wall: } 580 \text{ N/m}^3 \times (6 \text{ meters} \times 5 \text{ centimeters}) = 0.174 \text{ kN/m}$$

$$\text{Floor/Balcony: } 3500 \text{ N/m}^3 \times \frac{(6 \text{ meters} \times 50 \text{ centimeters})}{4} = 0.263 \text{ kN/m}$$


$$\text{Total Dead Load} = \text{Beams} + \text{Wall} + \text{Floor} = 1.1 \text{ kN/m}$$

#### **Assumptions:**

- Beam sizes are 0.365m x 0.38m
- 2x4 area of façade



## Live Loads – Distributed Loads



### Per Minimum Specified Load (kPa) [NBCC T3.4]

Roof: 1.0 kPa

Exterior Balcony: 4.8 kPa

Interior Assembly: 4.8 kPa

### Loads on 2D Frame:

$$\text{Roof Load} = 1 \text{ kPa} \times \frac{6 \text{ meters}}{4} = 1.5 \text{ kN/m}$$

$$\text{Floor Load} = 4.8 \text{ kPa} \times \frac{6 \text{ meters}}{4} = 7.2 \text{ kN/m}$$

$$\text{Balcony Load (Cantilever)} = 4.8 \text{ kPa} \times \frac{6 \text{ meters}}{4} = 7.2 \text{ kN/m}$$

## Snow Loads – Distributed Loads

$$S = I_s[S_a(C_b C_w C_s C_a) + S_r] \text{ designed for } \frac{1}{50} \text{ event}$$

$$C_b = \text{Basic Roof Snow Load Factor} = 0.8$$

$$C_w = \text{Wind Exposure Factor} = 0.75$$

$$C_s = \text{Roof Slope Factor} = 1.0$$

$$C_a = \text{Shape Factor} = 1.0$$

$$I_s = \text{Importance Factor} = 1.0$$

$$S_a = \text{Vancouver conditions} = 1.9 \text{ kPa}$$

$$S_r = \text{Vancouver conditions} = 0.3 \text{ kPa}$$

$$S = 1.0 \times [1.9 \text{ kPa} \times (0.8 \times 0.75 \times 1.0 \times 1.0) + 0.3 \text{ kPa}] = 1.44 \text{ kPa}$$

$$S = 1.44 \text{ kPa} \times 6 \text{ meters} = 8.64 \text{ kN/m}$$

### Assumptions

- Building is exposed to wind in all directions
- Incline of roof is less than 15 degrees
- Structure is regarded as “Normal” hazard in a likelihood of a disaster

## Wind Loads – External Pressure Loads

$$P = I_w q C_e C_g C_p$$

$$I_w = \text{importance factor for wind load} = 1.0$$

$$q = \text{reference velocity pressure} = 0.48 \text{ for } \frac{1}{50} \text{ year wind velocity}$$

$$C_e = \text{exposure factor} = 0.97$$

$$C_g = \text{gust effect factor} = 2.0$$

$$C_p = \text{external pressure coefficient factor over area of surface} = 1.0$$

$$P = 1.0 \times 0.48 \times 0.97 \times 2 \times 1 = 0.93 \text{ kPa}$$

$$F_{wind} = P \times \text{Floor Width} = 0.93 \text{ kPa} \times 5 \text{ meters} = 4.65 \text{ kN/m}$$

### Assumptions

- Structure is regarded as “Normal” hazard in a likelihood of a disaster
- Ignore corner effects of wind load

## Seismic Loads – Horizontal Load per Floor

$$V = \frac{S(T_a)M_v I_E W}{R_d R_o}$$

$$I_E = \text{Importance Factor} = 1.0$$

$$R_d = \text{Force Modification Factor} = 3.0$$

$$R_o = \text{Force Modification Factor} = 1.7$$

$$I_E = \text{Importance Factor} = 1.0$$

$$S_a(0.5) = \text{for Vancouver} = 0.65$$

$$S_a(0.2) = \text{for Vancouver} = 0.95$$

$$F_a \ \& \ F_v = 1.0$$

$$T_a = \text{Seismic Period} = 0.05(h)^{3/4} = 0.05(5 \text{ meters})^{3/4} = 0.17$$

$$S(T_a) = \text{Spectral Response Acceleration} = \min\{F_v S_a(0.5) | F_a S_a(0.2)\} = 0.65 \text{ for wood structure}$$

$$\frac{S_a(0.2)}{S_a(2.0)} = 5.33 \text{ with } T_a \leq 1.0 \text{ then } M_v = 1.0$$

$$V = \frac{0.65 \times 1.0 \times 1.0 \times W}{3.0 \times 1.7} = 0.125W \text{ where } W = \text{Dead Load [kN]}$$

$$W = \left(0.844 \frac{\text{kN}}{\text{m}} + 1.1 \frac{\text{kN}}{\text{m}} + 1.1 \frac{\text{kN}}{\text{m}} + 1.1 \frac{\text{kN}}{\text{m}}\right) \times 6 \text{ meters}$$

$$+ \left(4.8 \frac{\text{kN}}{\text{m}^3} \times 3 \text{ meters} \times 0.315 \text{ meters} \times 0.38 \text{ meters}\right) \times 6 = 35.2 \text{ kN}$$

$$V = 0.125W = 0.125 \times 35.2 \text{ kN} = 4.4 \text{ kN}$$

## Distribution of Base Shear

$$W_{\text{roof}} = 0.844 \frac{\text{kN}}{\text{m}} \times 6 \text{ meters} = 5.1 \text{ kN}$$

$$W_{1\text{st}} = W_{2\text{nd}} = 1.1 \frac{\text{kN}}{\text{m}} \times 6 \text{ meters} = 6.6 \text{ kN}$$

$$\sum (W \times h) = W_{1\text{st}} \times h_1 + W_{2\text{nd}} \times h_2 + W_{\text{roof}} \times h_{\text{roof}} = 106 \text{ kNm}$$

$$V_{1\text{st}} = V \times \frac{W_{1\text{st}} \times h}{\sum (W \times h)} = 4.4 \text{ kN} \times \frac{6.6 \text{ kN} \times 3 \text{ meters}}{106 \text{ kNm}} = 0.82 \text{ kN}$$

$$V_{2\text{nd}} = V \times \frac{W_{2\text{nd}} \times h_2}{\sum (W \times h)} = 4.4 \text{ kN} \times \frac{6.6 \text{ kN} \times 6 \text{ meters}}{106 \text{ kNm}} = 1.64 \text{ kN}$$

$$V_{\text{roof}} = V \times \frac{W_{\text{roof}} \times h_{\text{roof}}}{\sum (W \times h)} = 4.4 \text{ kN} \times \frac{5.1 \text{ kN} \times 9 \text{ meters}}{106 \text{ kNm}} = 2 \text{ kN}$$

### Assumptions

- Structure is regarded as “Normal” hazard in a likelihood of a disaster
- Wood Diaphragms – ductile condition
- For Vancouver conditions only
- Class C Soil conditions

## APPENDIX B4 – Foundation Design

$$q_{ult} = \sigma'_D N_q + 0.4\gamma' B N_\gamma$$

$q_{ult}$  = ultimate bearing capacity

$$\sigma'_D = \text{effective stress} = 0.5 \cdot 16 + 1(16 - 9.81) = 14.2 \text{ kPa}$$
$$N_q = e^{\pi \tan \phi'} \tan^2 \left( 45 + \frac{\phi'}{2} \right) = 18.4$$
$$\gamma' = \gamma - \gamma_w = 14.2 - 9.81 = 4.4 \text{ kN/m}^3$$
$$N_\gamma = 2(N_q + 1) \tan \phi' = 22.4$$
$$q_{ult} = 14.2 \cdot 18.4 + 0.4 \cdot 4.4 \cdot 2 \cdot 22.4 = 372 \text{ kPa}$$
$$q_{allowable} = \frac{q_{ult}}{FOS} = \frac{372}{3} = 124 \text{ kPa}$$

### Assumptions

- 2x2m square footing at the depth of 1.5m
- Groundwater table depth of 1m
- Moist and saturated glacial till specific weight of 17 kN/m<sup>3</sup>
- Glacial till angle of friction equal to 30°
- FOS of 3

## APPENDIX B5 - MEMBER DESIGN CALCULATIONS

### **COLUMN DESIGN**

For Glulam

**Member Size:** 315 mm by 380 mm

b: 315 mm

d: 380 mm

L: 3000 mm

#### Factored Compressive Resistance

$$Pr = \phi^* F_c^* A^* K_{zcg}^* K_c$$

$\phi^* F_c$  = factored compressive resistance strength given in **TABLE 3.8**

$$K_{zcg}: 0.68 (Z)^{-0.13} \leq 1.0$$

$$K_c: [1 + F_c/E' * K_{zcg} * C_c^3]^{-1}$$

where Z = member volume in m<sup>3</sup>

$C_c = \text{greater}(K_e * L_d/d, K_e * L_b/b) < 50$        $L_b, L_d = \text{unsupported length}$

$F_c/E' = \text{strength to stiffness ratio given in TABLE 3.9}$

$K_e = \text{effective length factor in FIGURE 3.1}$

A: 119700 mm<sup>2</sup>

Z: 359.1 m<sup>3</sup>

$F_c/E'$ : 0.0000667

$K_e$ : 1

$\phi^* F_c$ : 18.1 MPa

$L_b$ : 3000 mm

$L_d$ : 3000 mm

$C_c$ : 9.5238095 **GOOD**

$$K_{zcg}: 0.316468807$$

$$K_c: 0.982092246$$

$$Pr = 673373.339 \text{ N}$$

$$673 \text{ kN}$$

>  $P_f$

**GOOD**

#### Combined Loading

$$(P_f / Pr)^2 + (M_f / Mr) * (1 / (1 - P_f / P_e)) \leq 1.0$$

$M_r = \text{from Beam Selections Table}$

$E_05 * I = 0.87 * E_s * I \text{ from Beam Selections Table}$

$$P_e: \pi^2 * E_05 * I / (K_e * L)^2$$

Es\*I: 1.84E+13  
E05\*I: 1.601E+13  
L: 3000  
Mr: 209  
Pe: 17554736

$$(P_f / P_r)^2 + (M_f / M_r) * (1 / (1 - P_f / P_e)) = 0.50 \leq 1.0 \quad \text{GOOD}$$

### Shear Force Check

$V_f < V_r$

$$V_r = 1.15 * V_r' \quad V_r' = \text{from Beam Selections Table}$$

Vr': 144

$$V_r = 165.6 \geq V_f \quad \text{GOOD}$$

### L/180 Deflection Check

$E_s * I > E_s * I_{req}$        $E_s * I$  from Beam Selections Table

Es\*I: 1.84E+13 Nmm  
Wind Load: 2 kN

$$E_s * I_{req} = 180 * (\text{Wind Load} * L^2 / 48)$$

$$E_s * I_{req}: 67500000000 < E_s * I \quad \text{GOOD}$$

## BEAM DESIGN

For Glulam

**Member Size:** 365 mm by 380 mm

b: 365 mm

d: 380 mm

L: 6000 mm

### Moment Capacity

$M_r = \text{lesser of } M_r' * K_I \text{ or } M_r' * K_{zbg} \text{ [Nmm]}$

$M_r' = \phi * F_b * S$

$F_b = f_b * (K_d * K_h * K_{sb} * K_t) \text{ [MPa]}$

$S = b * d^2 / 6$

$C_b = \text{Sqrt}(L_e * d / b^2)$

$K_I = \text{determine from Table 2.9 with } C_b$

$K_{zbg} = (130/b)^{0.1} * (610/d)^{0.1} * (9100/L)^{0.1} \leq 1.3$

|      |      |     |
|------|------|-----|
| fb:  | 19.5 | Mpa |
| Kd:  | 1    |     |
| Kh:  | 1    |     |
| Ksb: | 0.8  |     |
| Kt:  | 1    |     |
| Ke:  | 1    |     |

Fb: 15.6 MPa

S: 8784333.33 mm<sup>3</sup>

Cb: 4.13689558 -----> K I: 1

Kzbg: 0.98584511  $\leq 1.3$  **GOOD**

$M_r' = 123.33204 \text{ kNm}$

$M_r = 121.59 > M_f$  **GOOD**

### Shear Capacity

$V_r = \phi * F_v * 2 * A_g / 3 \text{ [N]}$

$F_v = f_v * (K_d * K_h * K_{sv} * K_t) \text{ [MPa]}$

$A_g = b * d$

|      |      |     |
|------|------|-----|
| fv:  | 1.5  | Mpa |
| Kd:  | 1    |     |
| Kh:  | 1    |     |
| Ksv: | 0.87 |     |
| Kt:  | 1    |     |

Fv: 1.305 Mpa

Ag: 138700 mm<sup>2</sup>

$V_r = 108.60 > V_f$  **GOOD**

**Deflection Check:**

$$Eslreq\ 1 = 180 * (5wL^3/384)$$

where w is the total load

$$Eslreq\ 2 = 360 * (5w'L^3/384)$$

where w' is the live load

$$Eslreq\ 1: \quad 5.8725E+12\ Nmm$$

$$Eslreq\ 2: \quad 7.29E+12\ Nmm$$

----->

$$GOVERN: \quad 7.29E+12\ Nmm$$

< Esl

**GOOD**

**Distributed Load Check:**

$$Wr\ L^{0.18} = \phi * Fv * 0.48 * Ag * Cv * (bd)^{-0.18} [Nm^{0.18}]$$

$$Fv: \quad 1.305\ Mpa$$

$$Ag: \quad 138700\ mm^2$$

$$Cv: \quad 3.69$$

$$Wr\ L^{0.18} = 34.2470622\ kNm^{0.18}$$

$$Wr = 24.67 > Wf \quad \mathbf{GOOD}$$



## BEAM DESIGN

For Glulam

**Member Size:** 265 mm by 342 mm

b: 265 mm

d: 342 mm

L: 6708 mm

### Moment Capacity

$M_r = \text{lesser of } M_r' \cdot K_l \text{ or } M_r' \cdot K_{zbg} \text{ [Nmm]}$

$M_r' = \phi \cdot F_b \cdot S$

$F_b = f_b \cdot (K_d \cdot K_h \cdot K_{sb} \cdot K_t) \text{ [MPa]}$

$S = b \cdot d^2 / 6$

$C_b = \sqrt{\text{Le} \cdot d / b^2}$

$K_l = \text{determine from Table 2.9 with } C_b$

$K_{zbg} = (130/b)^{0.1} \cdot (610/d)^{0.1} \cdot (9100/L)^{0.1} \leq 1.3$

|      |          |
|------|----------|
| fb:  | 19.5 Mpa |
| Kd:  | 1        |
| Kh:  | 1        |
| Ksb: | 0.8      |
| Kt:  | 1        |
| Ke:  | 1        |

Fb: 15.6 MPa

S: 5165910 mm<sup>3</sup>

Cb: 5.7157116 ----->

Kl: 1

Kzbg: 1.01728733 ≤ 1.3

GOOD

$M_r' = 72.5293764 \text{ kNm}$

$M_r = 72.53 > M_f$

GOOD

### Shear Capacity

$V_r = \phi \cdot F_v \cdot 2 \cdot A_g / 3 \text{ [N]}$

$F_v = f_v \cdot (K_d \cdot K_h \cdot K_{sv} \cdot K_t) \text{ [MPa]}$

$$A_g = b \cdot d$$

fv: 1.5 Mpa  
 Kd: 1  
 Kh: 1  
 Ksv: 0.87  
 Kt: 1

Fv: 1.305 Mpa  
 Ag: 90630 mm<sup>2</sup>

$$V_r = 70.96 > V_f \quad \text{GOOD}$$

### Factored Compressive Resistance

$$P_r = \phi^* F_c \cdot A \cdot K_{zcg} \cdot K_c$$

$\phi^* F_c$  = factored compressive resistance strength given in **TABLE 3.8**

$$K_{zcg} = 0.68 (Z)^{-0.1} \leq 1.0$$

$$K_c = [1 + F_c/E' \cdot K_{zcg} \cdot C_c^3]^{-1}$$

where Z = member volume in m<sup>3</sup>  
 C<sub>c</sub> = greater(Ke\*L<sub>d</sub>/d, Ke\*L<sub>b</sub>/b) < 50  
 F<sub>c</sub>/E' = strength to stiffness ratio given in **TABLE 3.9**  
 Ke = effective length factor in **FIGURE 3.1**

A: 90630 mm<sup>2</sup>  
 Z: 607.96452 m<sup>3</sup>  
 F<sub>c</sub>/E': 0.0000667  
 Ke: 1  
 $\phi^* F_c$ : 18.1 MPa  
 L<sub>b</sub>: 6708 mm  
 L<sub>d</sub>: 6708 mm  
 C<sub>c</sub>: 25.314 **GOOD**

$$K_{zcg} = 0.29553216$$

$$K_c = 0.75771877$$

$$P_r = 367335.873 \text{ N}$$

$$367 \text{ kN} > P_f \quad \text{GOOD}$$

## CONNECTION DESIGN

For Steel Bolts

Refer to: Pg 320 CWC Design Manual, Double Shear, 6 mm Steel Internal Plate

Required Force: 55 kN

From Bolt Selection Table:

Try: 0.5" diameter bolts

PRf: 14.3 kN/bolt

Grt: 12.2 kN

Spacing: 80 mm

| Interpolation |                 |
|---------------|-----------------|
| Spacing:      | Force:          |
| 88            | 11.8            |
| 74            | 16.2            |
| <b>80</b>     | <b>14.31429</b> |

$$PR_{rt} = \text{lesser}[PRf \cdot n_c \cdot n_r \cdot (K_d \cdot K_{sv} \cdot K_t), N'u \cdot n_c \cdot n_r \cdot (K_{dy} \cdot K_{sf} \cdot K_t)]$$

$$PG_{rt} = PRf \cdot n_c \cdot (K_d \cdot K_{sv} \cdot K_t) + Grt \cdot J_{tr} \cdot (K_d \cdot K_{st} \cdot K_t)$$

|      |   |      |      |
|------|---|------|------|
| Kd:  | 1 | nc:  | 3    |
| Ksv: | 1 | nr:  | 2    |
| Kt:  | 1 | N'u: | 14.3 |
| Kdy: | 1 | Jtr: | 1    |
| Ksf: | 1 |      |      |
| Kst: | 1 |      |      |


$$PR_{rt} = 85.9 \text{ kN} > Pf \quad \text{GOOD}$$

$$PG_{rt} = 55 \text{ kN} > Pf \quad \text{GOOD}$$


### Net Tension:

$$Tr = 0.75 \cdot \phi_b \cdot A_b \cdot F_u$$


$$Tr = 188.7992 \text{ kN} > Pf \quad \text{GOOD}$$




Plan View



**Section A - A**  
Connection  
Scale: 1:250




Elevation View


 315 mm x 380 mm D.Fir.L 24f-EX Columns

 265 mm x 342 mm D.Fir.L 24f-EX Braces

 Staircase

 365 mm x 380 mm D.Fir.L 24f-EX Beams

 Double Shear, 6mm Steel Internal Plate  
0.5" Bolts



6250 Applied Science Lane  
Vancouver, BC V6T 1Z4  
Phone: (604) 583 - 6443  
www.jadeconsulting.ca

APPENDIX B6  
Structural Drawing

PLAN & ELEVATION  
DRAWING  
CHANCELLOR BLVD  
&  
WESBROOK MALL

Wood Lookout  
Tower

**ATTENTION**

JADE CONSULTING ASSUMES NO  
RESPONSIBILITY FOR THE CORRECTNESS  
OF THE INFORMATION SHOWN.

ALL DIMENSIONS SHOWN ON THIS PLAN ARE  
AS DESIGNED AND NOT AS CONSTRUCTED  
AND SHOULD BE FIELD CHECKED BY USER  
OR THEIR AGENT.

Directory: 2017-143-0-00


Date: March 31, 2017

Drawn By: HW

Checked By: AL

**S101**

SCALE: 1:500



JADE CONSULTING

6250 Applied Science Lane  
Vancouver, BC V6T 1Z4  
Phone: (604) 583 - 6443  
www.jadeconsulting.ca

APPENDIX B6  
Structural Drawings

ELEVATION DRAWING  
CHANCELLOR BLVD  
&  
WESBROOK MALL

Foundation  
Drawing

**ATTENTION**

JADE CONSULTING ASSUMES NO  
RESPONSIBILITY FOR THE CORRECTNESS  
OF THE INFORMATION SHOWN.

ALL DIMENSIONS SHOWN ON THIS PLAN ARE  
AS DESIGNED AND NOT AS CONSTRUCTED  
AND SHOULD BE FIELD CHECKED BY USER  
OR THEIR AGENT.

Directory: 2017-143-0-00


Date: March 31, 2017

Drawn By: AL

Checked By: HW


**S102**


SCALE: 1:500



 315 mm x 380 mm D.Fir.L 24f-EX Columns

 Soil Bed Material

 2 m x 2 m Concrete Foundation

 6mm Plate Anchor Connection with 0.5" Bolts

## **APPENDIX C – COST**

# PROJECT COST ESTIMATE

Project No. XXXXX

**Worksheet 1 of 3**

## Project Worksheet

### Project Information

*Project Description:* Roundabout Intersection of Wesbrook Mall and Chancellor Boulevard

*Project Location:* Vancouver, BC

*LKI:* 914-0602

*Longitude:* 49.273302

*Latitude:* 9123.249109

*Scope Statement:* The scope of the preliminary design report is to design an intersection that increases user safety, is sustainable, cost-effective, meets the future traffic demand and develops an inviting gateway to UBC.

*Length of Roadway:* 0.15 kms

*Number of lanes:* Two

*Development Density:* Suburban

*Terrain Type:* Flat

*Key Plan/Sketch:* attached

*Other information:* See Assumptions Worksheet <insert other relevent information to the cost estimate>

### Estimate Information

**Cost Estimate (excluding escalation):**

**\$1,326,975**

*Constant Year Dollars (\$):* 2016\$

*Estimate Level:* Conceptual

*Date Prepared:* 11/28/16

*Prepared By:* Jordan Yang

**PROJECT COST ESTIMATE**  
**Project No. XXXX**

**Worksheet 2 of 3**

**Assumptions Worksheet**

**NOTE:** The Assumptions Worksheet may differ depending the 'Level of Estimate' being prepared (conceptual, planning, prelim, detailed, pre-tender) and the approach of the Estimator. This is a SAMPLE of areas and items to consider and include. It is not an exhaustive list and/or may include items not applicable to all estimates.

**Overall Estimating Assumptions**

How was the estimate developed ?

- i.e. elemental parametric method or using historical cost comparisons on relevant, similar projects
- i.e. was the estimate developed by project team or independently

Precedent Example and Unit Costs  
Independently

Explain other assumptions and how they may influence or impact costs?

- i.e. Type of terrain - extreme, mountainous, rolling, level.
- i.e. Geographic location within BC - Lower Mainland; Northern; Southern Interior; Vancouver Island etc.
- i.e. Development Density (ie.Urban, Suburban, Rural) impacts work complexity, traffic management and utilities etc.
- i.e. Scope Uncertainty: What is the quality/quantity of available project information? current, complete, & accurate?
- i.e. Overall complexity and constructability issues

Flat  
UBC Endowment Lands  
Suburban  
Information is provided by client and AutoCAD drawing from original creation of intersection  
Medium Complexity

Any other overall assumption or costing decisions to document ?

**Project Management and Planning Calculations**

How is planning and project management cost determined as a % of total cost or some other method?

Percentage Cost

**Design Calculations**

Is design amount determined as a % of Construction or some other method?

Example: Calculated as a 7% of Grade Construction and/or 8% of Structural

Percentage Cost

**Property Assumptions**

What was the basis for determining property information and impacts?

What types of properties are involved (residential, commercial, industrial) ? And how many?

How was market values of the property established?

How are the variable costs determined? What's included? Is there an allowance for internal costs and legal fees?

Attach property detailed sheets as necessary outlining calculations

Residential  
These values ignored, under jurisdiction of UBC Endowment Lands

**Environmental Assumptions**

Is the work within an sensitive area? Is this a CEAA project?

How was compensation value determined?

How much mitigation work is anticipated? How was it valued?

No  
Percentage of Costs  
Floodwater Control/ Percentage

**Construction Assumptions**

What is the project delivery/procurement method? (Design-Bid-Build/Design-Build/Day Labour/P3/DBFO)

Is there a Design Criteria Sheet completed for the project?

Geotechnical information: What were the significant material assumptions: solid rock, boulders, mixed, dirt ?

Were there any structures included? How many watercourses were identified or assumed?

What was the assumed road cross-section? Material depths? Asphalt?

Detailed calculations for construction cost elements contained on estimate 'detail sheets'

- i.e include 'detail sheets' outlining **quantity calculations (based on most probable?)**
- i.e. provide **explanation of unit prices** (e.g. prices of similar projects, MOT cost data; labour, matrl, equip)
- i.e traffic management considerations
- i.e mobilization and demobilization considerations

Design-Bid-Build  
Dirt  
100mm Asphalt, 150mm base, 300mm sub-base  
Taken from AutoCAD  
Under Cost Breakdowns

**Construction Supervision Calculation**

How was the construction supervision determined?

Example: Calculated as a % of each Construction component (including contingency) as follows:

Grading 7%, Operational and Other 8%, Structural and Paving 6.5%, and Environmental Compensation 8%

**Risks Assessment**

Was a comprehensive Risk Assessment conducted?

What are the major risk items? How were they identified and quantified?

How were these risks allowed for in the estimate? Are they covered by contingency or included in base Cost Elements

No  
A more comprehensive risk assessment will be implemented further into the project  
Covered by contingencies

**Contingency Assumptions**

Was contingency applied as a set % basis or was a Risk Assessment conducted identifying and quantifying Risks?

Was contingency applied uniformly to all Cost Elements and project segments (Yes or No) ?

What is the amount or % that was applied ?

Is contingency based on the current level of project knowledge and associated risk to deliver the project scope ?

Percentage Basis  
Yes  
Associated Risk/Preliminary Phase

**Inclusion and Exclusions**

Is there anything **NOT included** in the estimate? (i.e. pre-project development costs etc.)

Is there anything **specifically included** in the estimate that may be unusual or not normally be part of project cost?

Property Value, Property Levies  
No



# PROJECT COST ESTIMATE

Project No. XXXX

## Worksheet 3 of 3

### Cost Element Worksheet

**Notes:**

**Data Entry Cells =**   Amounts entered are **SAMPLES ONLY**. These cells are directly data entered and used as the basis for calculating amounts in other cells. The amounts shall be established by the Estimator based on knowledge and information available at the time the estimate is developed.

**Contingency % Cells =**   Percentage (%) shown is a **SAMPLE ONLY** and should only be used as a guide. The actual %'ages used in these cells shall be set by the Estimator based on the assessed level of risk and uncertainty associated with each cost element at the time the estimate is developed.

**Non-Data Entry Cells =**   Amounts calculated are **SAMPLES ONLY**. These cells contain formulas. The formulas should be used as a guide only. The calculated amounts for each cost element shall be reviewed, adjusted and established by the Estimator as necessary for each cost element based on their knowledge and information at the time the estimate is developed.

| COST ELEMENT                                      | BASE ESTIMATE  | CONTINGENCY |                | TOTAL ESTIMATE   | COMMENTS                                  |
|---|----------------|-------------|----------------|------------------|---|
|   |                | %           | \$             |                  |   |
| <b>PROJECT MANAGEMENT</b>                         | 30,000         | 15%         | 4,500          | 34,500           | 3.5% of Total Project Estimate            |
| <b>PLANNING</b>                                   | 6,610          | 15%         | 991            | 7,601            | 1% of Construction Base Estimate          |
| <b>DESIGN</b>                                     |                |             |                |                  |   |
| PRELIMINARY DESIGN                                | 13,219         | 15%         | 1,983          | 15,202           | 2% of Construction Base Estimate          |
| DETAILED DESIGN SERVICES                          | 60,000         | 15%         | 9,000          | 69,000           | See Assumptions Worksheet                 |
| <b>DESIGN TOTAL</b>                               | <b>73,219</b>  | <b>15%</b>  | <b>10,983</b>  | <b>84,202</b>    |   |
| <b>PROPERTY</b>                                   |                |             |                |                  |   |
| MARKET VALUE OF LAND                              | 0              | 15%         | 0              | 0                |   |
| VARIABLE COSTS                                    | 0              | 15%         | 0              | 0                | 25% of Market Value                       |
| LESS: SURPLUS LAND RECOVERIES                     | 0              | 15%         | 0              | 0                | Residual land sales from surplus property |
| <b>PROPERTY TOTAL</b>                             | <b>0</b>       | <b>0%</b>   | <b>0</b>       | <b>0</b>         |   |
| <b>ENVIRONMENT</b>                                |                |             |                |                  |   |
| ENVIRONMENTAL COMPENSATION                        | 48,141         | 15%         | 7,221          | 55,362           |   |
| <b>ENVIRONMENT TOTAL</b>                          | <b>48,141</b>  | <b>15%</b>  | <b>7,221</b>   | <b>55,362</b>    |   |
| <b>CONSTRUCTION</b>                               |                |             |                |                  |   |
| <b>ROAD CONSTRUCTION</b>                          |                |             |                |                  |   |
| GRADE CONSTRUCTION                                | 76,243         | 15%         | 11,436         | 87,679           |   |
| PAVING CONSTRUCTION                               | 53,606         | 15%         | 8,041          | 61,647           |   |
| UTILITY CONSTRUCTION                              | 161,500        | 15%         | 24,225         | 185,725          |   |
| OPERATIONAL CONSTRUCTION                          | 29,000         | 15%         | 4,350          | 33,350           |   |
| ROADSIDE CONSTRUCTION                             | 59,880         | 15%         | 8,982          | 68,862           |   |
| OTHER CONSTRUCTION                                | 219,256        | 15%         | 32,888         | 252,144          |   |
| <b>ROAD CONSTRUCTION SUB-TOTAL</b>                | <b>599,485</b> | <b>15%</b>  | <b>89,923</b>  | <b>689,408</b>   |   |
| STRUCTURAL CONSTRUCTION                           | 61,467         | 15%         | 9,220          | 70,687           |   |
| <b>CONSTRUCTION TOTAL</b>                         | <b>660,952</b> | <b>15%</b>  | <b>99,143</b>  | <b>760,095</b>   |   |
| <b>CONSTRUCTION SUPERVISION</b>                   | <b>60,000</b>  | <b>15%</b>  | <b>9,000</b>   | <b>69,000</b>    | See Assumptions Worksheet                 |
| <b>OTHER COSTS</b>                                |                |             |                |                  |   |
| <INSERT ITEMS>                                    | 0              | 15%         | 0              | 0                | describe each item in detail              |
| <b>OTHER COSTS TOTAL</b>                          | <b>0</b>       | <b>15%</b>  | <b>0</b>       | <b>0</b>         |   |
| <b>PAST COSTS (prior to &lt;insert date&gt; )</b> | 19,500         | 0%          | 0              | 19,500           |   |
| <b>MANAGEMENT RESERVE (if applicable)</b>         |                |             |                |                  | maintained by CPB (5% of total estimate)  |
| <b>TOTAL</b>                                      | <b>898,422</b> | <b>15%</b>  | <b>131,838</b> | <b>1,030,260</b> |   |

|                    |              |     |                 |
|--------------------|--------------|-----|-----------------|
| Contractor Mark-up | 154,539      | 15% | \$ 1,184,798.76 |
| PST+GST            | \$142,175.85 | 12% | \$ 1,326,974.61 |

| Initial Costs          |                                     |          |                     |              |               |
|------------------------|-------------------------------------|----------|---------------------|--------------|---------------|
| Task Type              | Task                                | Quantity | Unit of Measurement | Unit Rate    | Price         |
| Site Assessment        | Overall Site Assessment             | 1        |                     | \$ 6,000.00  | \$ 6,000.00   |
| Construction           | Construction Crew Mobilization      | 1        |                     | \$ 2,000.00  | \$ 2,000.00   |
|                        | Traffic Control                     | 64       | day                 | \$ 2,000.00  | \$ 128,000.00 |
|                        | Traffic Management                  | 1        | tmp                 | \$ 1,000.00  | \$ 1,000.00   |
|                        | Removal of Asphalt                  | 2500     | m^2                 | \$ 8.00      | \$ 20,000.00  |
|                        | Removal of Curb                     | 108.2    | m^3                 | \$ 80.00     | \$ 8,656.00   |
| Grading                | Excavation                          | 461.5    | m^3                 | \$ 50.00     | \$ 23,075.00  |
|                        | Prepare/Compact Sub-base            | 1476.9   | Tonnes              | \$ 26.00     | \$ 38,399.40  |
|                        | Place and Compact Gravel            | 492.3    | Tonnes              | \$ 30.00     | \$ 14,769.00  |
| New Medians Build      | Form Pour Finish Meeting Curbs      |          |                     |              |               |
|                        | Pour Concrete                       | 220      | LM                  | \$ 35.00     | \$ 7,700.00   |
| Reinstallations        | Catch Basin                         | 5        |                     | \$ 1,800.00  | \$ 9,000.00   |
|                        | Rectangular Rapid Flashing Beacons  | 10       |                     | \$ 15,000.00 | \$ 150,000.00 |
|                        | Hydrants                            | 1        |                     | \$ 2,500.00  | \$ 2,500.00   |
| Welcome Sign           | Installation                        | 1        |                     | \$ 2,782.00  | \$ 2,782.00   |
| Curbs and Ramps        | Forms/Concrete and Finish           | 533      | LM                  | \$ 60.00     | \$ 31,980.00  |
| Sidwalks               | Pour Concrete                       | 558      | m^2                 | \$ 50.00     | \$ 27,900.00  |
| Streets                | Paving                              | 536.06   | Tonnes              | \$ 100.00    | \$ 53,606.00  |
| Finish                 | Install Road Signage and Paintlines | 1        |                     | \$ 3,500.00  | \$ 3,500.00   |
|                        | Landscaping                         | 848      | m^2                 | \$ 50.00     | \$ 42,400.00  |
| Construction Close-Out | Site Clean-Up                       | 1        |                     | \$ 2,000.00  | \$ 2,000.00   |
|                        | Crew Demobilization                 | 1        |                     | \$ 2,000.00  | \$ 2,000.00   |
| Electrical             | Electrical Use                      | 1        |                     | \$ 25,000.00 | \$ 25,000.00  |
| Sub Total              |                                     |          |                     |              | \$ 602,267.40 |

| Maintenance Costs |                                       |          |                     |           |          |
|-------------------|---------------------------------------|----------|---------------------|-----------|----------|
| Task Type         | Task                                  | Quantity | Unit of Measurement | Unit Rate | Price    |
| Landscaping       | Mowing, Weed Control, Fertilizing     | 848      | M^2                 | 0.8       | 678.4    |
| Electrical        | Electrical Recalibrations/Maintenance | 1        |                     | 800       | 800      |
| Total             |                                       |          |                     |           | 1478.4   |
| PST+GST           |                                       |          |                     |           | 1655.808 |

# Calculation

| Pos      | Text  | Num                   | Category  | Unit          | Quantity     | Unit Cost       | Cost             | Total UC        | Total Cost       | Reg.     |
|----------|---|-----------------------|-----------|---------------|--------------|-----------------|------------------|-----------------|------------------|----------|
|          | <b>Observation Tower</b>  |                       |           |               |              |                 | <b>70,687.81</b> |                 | <b>70,687.81</b> |          |
|          | <b>Total supplement (15.00% of 61,467.00)</b>                                   |                       |           |               |              |                 |                  | 9,220.05        |                  | 9,220.05 |
| 1.       | <b>Cost by Assembly</b>   |                       |           |               |              |                 | <b>61,467.76</b> |                 | <b>61,467.76</b> |          |
| 1.1.     | <b>Curtain wall, aluminum, stock, double glazed, including glazing, average</b> | <b>22-08 44 13 10</b> |           | <b>S.F.</b>   | <b>54</b>    | <b>81.46</b>    | <b>4,398.98</b>  | <b>81.46</b>    | <b>4,398.98</b>  | <b>1</b> |
| 1.1.1.   | Curtain wall, aluminum, stock, double glazed, including glazing, average        | 084413100150          | Materials | S.F.          | 1            | 71.00           | 71.00            | 69.08           | 69.08            | 0.973    |
| 1.1.2.   | <b>Crew</b>   | <b>H-1</b>            |           | <b>S.F.</b>   | <b>1</b>     | <b>12.38</b>    | <b>12.38</b>     | <b>12.38</b>    | <b>12.38</b>     | <b>1</b> |
| 1.1.2.1. | Glaziers  | GLAZ                  | Labor     | Hours         | 0.0889       | 47.80           | 4.25             | 62.06           | 5.52             | 1.298    |
| 1.1.2.2. | Structural Steel Workers  | SSWK                  | Labor     | Hours         | 0.0889       | 54.30           | 4.83             | 77.21           | 6.86             | 1.422    |
| 1.2.     | <b>Exterior wood door frames, oak, 5/4" x 4-9/16" deep, incl. exterior trim</b> | <b>22-06 48 13 10</b> |           | <b>L.F.</b>   | <b>24</b>    | <b>26.97</b>    | <b>647.32</b>    | <b>26.97</b>    | <b>647.32</b>    | <b>1</b> |
| 1.2.1.   | Exterior wood door frames, oak, 5/4" x 4-9/16" deep, incl. exterior trim        | 064813100600          | Materials | L.F.          | 1            | 21.00           | 21.00            | 23.92           | 23.92            | 1.139    |
| 1.2.2.   | Carpenters  | CARP                  | Labor     | Hours         | 0.0457       | 49.25           | 2.25             | 66.77           | 3.05             | 1.356    |
| 1.3.     | <b>6" x 6" wood, column framing</b>   | <b>22-06 11 10 14</b> |           | <b>M.B.F.</b> | <b>4.806</b> | <b>3,636.92</b> | <b>17,479.04</b> | <b>3,636.92</b> | <b>17,479.04</b> | <b>1</b> |
| 1.3.1.   | 6" x 6" wood, column framing  | 061110140460          | Materials | M.B.F.        | 1            | 1,750.00        | 1,750.00         | 1,993.25        | 1,993.25         | 1.139    |
| 1.3.2.   | Carpenters  | CARP                  | Labor     | Hours         | 24.6154      | 49.25           | 1,212.31         | 66.77           | 1,643.67         | 1.356    |
| 1.4.     | <b>Beam and girder framing, single, 2" x 8", pneumatic nailed</b>               | <b>22-06 11 10 10</b> |           | <b>M.B.F.</b> | <b>3.844</b> | <b>1,823.34</b> | <b>7,008.92</b>  | <b>1,823.34</b> | <b>7,008.92</b>  | <b>1</b> |
| 1.4.1.   | Beam and girder framing, single, 2" x 8", pneumatic nailed                      | 061110103525          | Materials | M.B.F.        | 1            | 660.00          | 660.00           | 751.74          | 751.74           | 1.139    |
| 1.4.2.   | Carpenters  | CARP                  | Labor     | Hours         | 16.0481      | 49.25           | 790.37           | 66.77           | 1,071.60         | 1.356    |
| 1.5.     | <b>2" x 4" wood joist, framing</b>  | <b>22-06 11 10 18</b> |           | <b>M.B.F.</b> | <b>0.2</b>   | <b>1,987.70</b> | <b>397.54</b>    | <b>1,987.70</b> | <b>397.54</b>    | <b>1</b> |
| 1.5.1.   | 2" x 4" wood joist, framing   | 061110182650          | Materials | M.B.F.        | 1            | 615.00          | 615.00           | 700.49          | 700.49           | 1.139    |
| 1.5.2.   | Carpenters  | CARP                  | Labor     | Hours         | 19.2771      | 49.25           | 949.40           | 66.77           | 1,287.21         | 1.356    |
| 1.6.     | <b>Wood block flooring, end grain, natural finish, fir, 1" thick</b>            | <b>22-09 64 16 10</b> |           | <b>S.F.</b>   | <b>108</b>   | <b>9.44</b>     | <b>1,019.82</b>  | <b>9.44</b>     | <b>1,019.82</b>  | <b>1</b> |
| 1.6.1.   | Wood block flooring, end grain, natural finish, fir, 1" thick                   | 096416100400          | Materials | S.F.          | 1            | 3.76            | 3.76             | 5.05            | 5.05             | 1.344    |
| 1.6.2.   | Carpenters  | CARP                  | Labor     | Hours         | 0.064        | 49.25           | 3.15             | 68.59           | 4.39             | 1.393    |

| Pos       | Text   | Num                   | Category  | Unit         | Quantity   | Unit Cost       | Cost             | Total UC        | Total Cost       | Reg.     |
|-----------|--|-----------------------|-----------|--------------|------------|-----------------|------------------|-----------------|------------------|----------|
| 1.7.      | <b>Stair, industrial ships ladder, aluminum, grating treads, 24" wide, incl 2 line pipe rail, per riser</b>  | <b>22-05 51 33 16</b> |           | <b>Riser</b> | <b>34</b>  | <b>514.72</b>   | <b>17,500.33</b> | <b>514.72</b>   | <b>17,500.33</b> | <b>1</b> |
| 1.7.1.    | Stair, industrial ships ladder, aluminum, grating treads, 24" wide, incl 2 line pipe rail, per riser   | 055133164000          | Materials | Riser        | 1          | 299.00          | 299.00           | 420.99          | 420.99           | 1.408    |
| 1.7.2.    | <b>Crew</b>  | <b>E-4</b>            |           | <b>Riser</b> | <b>1</b>   | <b>93.72</b>    | <b>93.72</b>     | <b>93.72</b>    | <b>93.72</b>     | <b>1</b> |
| 1.7.2.1.  | Structural Steel Workers Outside Foreman   | SSWKO                 | Labor     | Hours        | 0.2667     | 56.30           | 15.01            | 85.69           | 22.85            | 1.522    |
| 1.7.2.2.  | Structural Steel Workers   | SSWK                  | Labor     | Hours        | 0.8        | 54.30           | 43.44            | 82.64           | 66.11            | 1.522    |
| 1.7.2.3.  | Welder, Gas Engine, 300 amp  | 015433408000          | Equipment | Days         | 0.0333     | 129.80          | 4.33             | 142.78          | 4.76             | 1.1      |
| 1.8.      | <b>Doors, glass, sliding, vinyl clad, 8'-0" x 6'-10" high, 1" insulated glass</b>  | <b>22-08 32 19 15</b> |           | <b>Opng.</b> | <b>3</b>   | <b>2,227.76</b> | <b>6,683.29</b>  | <b>2,227.76</b> | <b>6,683.29</b>  | <b>1</b> |
| 1.8.1.    | Doors, glass, sliding, vinyl clad, 8'-0" x 6'-10" high, 1" insulated glass   | 083219150100          | Materials | Opng.        | 1          | 2,025.00        | 2,025.00         | 1,970.33        | 1,970.33         | 0.973    |
| 1.8.2.    | Carpenters   | CARP                  | Labor     | Hours        | 4          | 49.25           | 197.00           | 64.36           | 257.44           | 1.307    |
| 1.9.      | <b>Railing, ornamental, aluminum, 3'-6" high, posts @ 6' O.C., panelized, fancy</b>  | <b>22-05 73 23 50</b> |           | <b>L.F.</b>  | <b>42</b>  | <b>109.36</b>   | <b>4,593.31</b>  | <b>109.36</b>   | <b>4,593.31</b>  | <b>1</b> |
| 1.9.1.    | Railing, ornamental, aluminum, 3'-6" high, posts @ 6' O.C., panelized, fancy   | 057323500300          | Materials | L.F.         | 1          | 25.50           | 25.50            | 35.90           | 35.90            | 1.408    |
| 1.9.2.    | Structural Steel Workers   | SSWK                  | Labor     | Hours        | 0.8889     | 54.30           | 48.27            | 82.64           | 73.46            | 1.522    |
| 1.10.     | <b>Building footings and foundations demolition, floors, concrete slab on grade, plain concrete, 6" thick, excludes disposal costs and dump fees</b> | <b>22-02 41 16 17</b> |           | <b>S.F.</b>  | <b>54</b>  | <b>0.92</b>     | <b>49.46</b>     | <b>0.92</b>     | <b>49.46</b>     | <b>1</b> |
| 1.10.1.   | <b>Crew</b>  | <b>B-13L</b>          |           | <b>S.F.</b>  | <b>1</b>   | <b>0.92</b>     | <b>0.92</b>      | <b>0.92</b>     | <b>0.92</b>      | <b>1</b> |
| 1.10.1.1. | Equipment Operators, Crane or Shovel   | EQHV                  | Labor     | Hours        | 0.004      | 55.70           | 0.22             | 90.43           | 0.36             | 1.623    |
| 1.10.1.2. | Hyd. Excavator, 1.5 C.Y.   | 015433200200          | Equipment | Days         | 0.0003     | 965.00          | 0.24             | 1,061.50        | 0.27             | 1.1      |
| 1.10.1.3. | Hyd. Hammer, 5000 ft-lb  | 015433200347          | Equipment | Days         | 0.0003     | 376.20          | 0.09             | 413.82          | 0.10             | 1.1      |
| 1.10.1.4. | Hyd. Excavator, .75 C.Y.   | 015433200140          | Equipment | Days         | 0.0003     | 674.20          | 0.17             | 741.62          | 0.19             | 1.1      |
| 1.11.     | <b>1" x 6" board bracing, studs @ 24" O.C., let-in</b>   | <b>22-06 11 10 04</b> |           | <b>L.F.</b>  | <b>530</b> | <b>3.19</b>     | <b>1,689.75</b>  | <b>3.19</b>     | <b>1,689.75</b>  | <b>1</b> |
| 1.11.1.   | 1" x 6" board bracing, studs @ 24" O.C., let-in  | 061110040202          | Materials | L.F.         | 1          | 0.76            | 0.76             | 0.87            | 0.87             | 1.139    |
| 1.11.2.   | Carpenters   | CARP                  | Labor     | Hours        | 0.0348     | 49.25           | 1.71             | 66.77           | 2.32             | 1.356    |

## **APPENDIX D – STAKEHOLDER REGISTER**

## STAKEHOLDER REGISTER

| Stakeholders  | Expectations  | Level of Interest | Level of Influence | Engagement Method |
|---|---|-------------------|--------------------|-------------------|
| <b>UBC Transportation Planning</b>  | <ul style="list-style-type: none"> <li>Ensure intersection will meet future traffic demands in a safe manner for all modes of transport</li> </ul>  | High              | High               | Collaborate       |
| <b>UBC Sustainability</b>   | <ul style="list-style-type: none"> <li>Promote alternative modes of transport in UBC</li> <li>Incorporate sustainable features in design</li> </ul> | High              | High               | Collaborate       |
| <b>UBC Community (Faculty, staff, students, Alma Mater Society)</b>           | <ul style="list-style-type: none"> <li>Ensure safety to all road users (motorists, pedestrians and cyclists)</li> </ul>                             | Medium            | Medium             | Consult           |
| <b>University Neighbourhood Association (i.e. Chancellor Place residents)</b> | <ul style="list-style-type: none"> <li>Construction impacts to be minimized and coordinated</li> </ul>  | High              | Medium             | Consult           |
| <b>University Endowment Lands</b>   | <ul style="list-style-type: none"> <li>Redesign of intersection to respect existing property line</li> </ul>  | High              | High               | Collaborate       |
| <b>First Nations</b>  | <ul style="list-style-type: none"> <li>Ensure any archaeological impacts are assessed and dealt with accordingly</li> </ul>                         | Medium            | High               | Consult           |
| <b>Vancouver Fire and Rescue Services</b>                                     | <ul style="list-style-type: none"> <li>Detour to be coordinated during construction</li> </ul>  | Low               | High               | Consult           |
| <b>BC Ambulance</b>   | <ul style="list-style-type: none"> <li>Detour to be coordinated during construction</li> </ul>  | Low               | High               | Consult           |
| <b>RCMP</b>   | <ul style="list-style-type: none"> <li>Detour to be coordinated during construction</li> </ul>  | Medium            | Medium             | Consult           |
| <b>Translink</b>  | <ul style="list-style-type: none"> <li>Ensure feasible design for bus turns</li> <li>Detour to be coordinated during construction</li> </ul>        | Medium            | Low                | Inform            |
| <b>Residents</b>  | <ul style="list-style-type: none"> <li>Construction impacts and disturbance to be minimized</li> </ul>  | Medium            | Low                | Inform            |

## **APPENDIX E – GANTT CHART**


| ID | Task Mode | Task Name  | Duration       | Start               | Finish              | Predecessors | Gantt Chart |  |            |   |  |   |  |   |  |            |   |  |   |  |            |   |  |   |  |  |  |  |  |  |  |  |
|----|-----------|--|----------------|---------------------|---------------------|--------------|-------------|--|------------|---|--|---|--|---|--|------------|---|--|---|--|------------|---|--|---|--|--|--|--|--|--|--|--|
|    |           |  |                |                     |                     |              | S           |  | '17 May 07 | T |  | M |  | F |  | '17 Jun 04 | T |  | S |  | '17 Jul 02 | W |  | S |  |  |  |  |  |  |  |  |
| 1  |           | <b>Redesign of Chancellor Blvd and Wesbrook Mall Intersect</b> | <b>95 days</b> | <b>Mon 17-03-06</b> | <b>Fri 17-07-14</b> |              | [Gantt Bar] |  |            |   |  |   |  |   |  |            |   |  |   |  |            |   |  |   |  |  |  |  |  |  |  |  |
| 2  |           | <b>SITE ASSESSMENT (PRE-CONSTRUCTION)</b>                      | <b>35 days</b> | <b>Mon 17-03-06</b> | <b>Fri 17-04-21</b> |              | [Gantt Bar] |  |            |   |  |   |  |   |  |            |   |  |   |  |            |   |  |   |  |  |  |  |  |  |  |  |
| 3  |           | First Nations Archaeological Impact Assessment                 | 30 days        | Mon 17-03-06        | Fri 17-04-14        |              | [Gantt Bar] |  |            |   |  |   |  |   |  |            |   |  |   |  |            |   |  |   |  |  |  |  |  |  |  |  |
| 4  |           | Project Permitting   | 30 days        | Mon 17-03-06        | Fri 17-04-14        | 3SS          | [Gantt Bar] |  |            |   |  |   |  |   |  |            |   |  |   |  |            |   |  |   |  |  |  |  |  |  |  |  |
| 5  |           | Geotechnical Assessment  | 30 days        | Mon 17-03-06        | Fri 17-04-14        | 3SS          | [Gantt Bar] |  |            |   |  |   |  |   |  |            |   |  |   |  |            |   |  |   |  |  |  |  |  |  |  |  |
| 6  |           | Soil Contamination Test  | 20 days        | Mon 17-03-06        | Fri 17-03-31        | 3SS          | [Gantt Bar] |  |            |   |  |   |  |   |  |            |   |  |   |  |            |   |  |   |  |  |  |  |  |  |  |  |
| 7  |           | Topographic Survey   | 3 days         | Mon 17-04-17        | Wed 17-04-14        | 4            | [Gantt Bar] |  |            |   |  |   |  |   |  |            |   |  |   |  |            |   |  |   |  |  |  |  |  |  |  |  |
| 8  |           | Health and Safety Assessment                                   | 5 days         | Mon 17-04-17        | Fri 17-04-21        | 4            | [Gantt Bar] |  |            |   |  |   |  |   |  |            |   |  |   |  |            |   |  |   |  |  |  |  |  |  |  |  |
| 9  |           | <b>CONSTRUCTION</b>  | <b>55 days</b> | <b>Mon 17-05-01</b> | <b>Fri 17-07-14</b> |              | [Gantt Bar] |  |            |   |  |   |  |   |  |            |   |  |   |  |            |   |  |   |  |  |  |  |  |  |  |  |
| 10 |           | <b>Site Preparation</b>  | <b>10 days</b> | <b>Mon 17-05-01</b> | <b>Fri 17-05-12</b> |              | [Gantt Bar] |  |            |   |  |   |  |   |  |            |   |  |   |  |            |   |  |   |  |  |  |  |  |  |  |  |
| 11 |           | Construction Crew Mobilization                                 | 1 day          | Mon 17-05-01        | Mon 17-05-01        |              | [Gantt Bar] |  |            |   |  |   |  |   |  |            |   |  |   |  |            |   |  |   |  |  |  |  |  |  |  |  |
| 12 |           | Set Up Traffic Control   | 2 days         | Tue 17-05-02        | Wed 17-05-03        | 11           | [Gantt Bar] |  |            |   |  |   |  |   |  |            |   |  |   |  |            |   |  |   |  |  |  |  |  |  |  |  |
| 13 |           | Removal of Trees   | 3 days         | Thu 17-05-04        | Mon 17-05-07        | 12           | [Gantt Bar] |  |            |   |  |   |  |   |  |            |   |  |   |  |            |   |  |   |  |  |  |  |  |  |  |  |
| 14 |           | Removal of Signage   | 1 day          | Tue 17-05-09        | Tue 17-05-09        | 13           | [Gantt Bar] |  |            |   |  |   |  |   |  |            |   |  |   |  |            |   |  |   |  |  |  |  |  |  |  |  |
| 15 |           | Removal of Medians   | 1 day          | Wed 17-05-10        | Wed 17-05-10        | 14           | [Gantt Bar] |  |            |   |  |   |  |   |  |            |   |  |   |  |            |   |  |   |  |  |  |  |  |  |  |  |
| 16 |           | Removal of Street Lights                                       | 2 days         | Wed 17-05-10        | Thu 17-05-11        | 14           | [Gantt Bar] |  |            |   |  |   |  |   |  |            |   |  |   |  |            |   |  |   |  |  |  |  |  |  |  |  |
| 17 |           | Removal of Catch Basins  | 2 days         | Thu 17-05-11        | Fri 17-05-12        | 15           | [Gantt Bar] |  |            |   |  |   |  |   |  |            |   |  |   |  |            |   |  |   |  |  |  |  |  |  |  |  |
| 18 |           | Removal of Hydrants  | 1 day          | Fri 17-05-12        | Fri 17-05-12        | 16           | [Gantt Bar] |  |            |   |  |   |  |   |  |            |   |  |   |  |            |   |  |   |  |  |  |  |  |  |  |  |
| 19 |           | <b>Grading</b>   | <b>12 days</b> | <b>Mon 17-05-15</b> | <b>Tue 17-05-30</b> |              | [Gantt Bar] |  |            |   |  |   |  |   |  |            |   |  |   |  |            |   |  |   |  |  |  |  |  |  |  |  |
| 20 |           | Excavation   | 7 days         | Mon 17-05-15        | Tue 17-05-22        | 10           | [Gantt Bar] |  |            |   |  |   |  |   |  |            |   |  |   |  |            |   |  |   |  |  |  |  |  |  |  |  |
| 21 |           | Prepare Sub-base   | 4 days         | Wed 17-05-24        | Mon 17-05-28        | 20           | [Gantt Bar] |  |            |   |  |   |  |   |  |            |   |  |   |  |            |   |  |   |  |  |  |  |  |  |  |  |
| 22 |           | Place Gravel   | 4 days         | Thu 17-05-25        | Tue 17-05-30        | 21SS+1 day   | [Gantt Bar] |  |            |   |  |   |  |   |  |            |   |  |   |  |            |   |  |   |  |  |  |  |  |  |  |  |
| 23 |           | Compact  | 4 days         | Thu 17-05-25        | Tue 17-05-30        | 22SS         | [Gantt Bar] |  |            |   |  |   |  |   |  |            |   |  |   |  |            |   |  |   |  |  |  |  |  |  |  |  |
| 24 |           | <b>Reinstallation</b>  | <b>5 days</b>  | <b>Wed 17-05-31</b> | <b>Tue 17-06-06</b> |              | [Gantt Bar] |  |            |   |  |   |  |   |  |            |   |  |   |  |            |   |  |   |  |  |  |  |  |  |  |  |
| 25 |           | Reinstallation of Catch Basin                                  | 5 days         | Wed 17-05-31        | Tue 17-06-06        | 19           | [Gantt Bar] |  |            |   |  |   |  |   |  |            |   |  |   |  |            |   |  |   |  |  |  |  |  |  |  |  |
| 26 |           | Reinstallation of Street Lights                                | 2 days         | Wed 17-05-31        | Thu 17-06-01        | 19           | [Gantt Bar] |  |            |   |  |   |  |   |  |            |   |  |   |  |            |   |  |   |  |  |  |  |  |  |  |  |
| 27 |           | Reinstallation of Hydrants                                     | 1 day          | Thu 17-06-01        | Thu 17-06-01        | 26SS+1 day   | [Gantt Bar] |  |            |   |  |   |  |   |  |            |   |  |   |  |            |   |  |   |  |  |  |  |  |  |  |  |
| 28 |           | <b>New Medians Build</b>                                       | <b>12 days</b> | <b>Wed 17-05-31</b> | <b>Thu 17-06-15</b> | <b>23</b>    | [Gantt Bar] |  |            |   |  |   |  |   |  |            |   |  |   |  |            |   |  |   |  |  |  |  |  |  |  |  |
| 29 |           | <b>East of Wesbrook Mall</b>                                   | <b>7 days</b>  | <b>Wed 17-05-31</b> | <b>Thu 17-06-08</b> | <b>23</b>    | [Gantt Bar] |  |            |   |  |   |  |   |  |            |   |  |   |  |            |   |  |   |  |  |  |  |  |  |  |  |
| 30 |           | Form   | 5 days         | Wed 17-05-31        | Tue 17-06-06        | 23           | [Gantt Bar] |  |            |   |  |   |  |   |  |            |   |  |   |  |            |   |  |   |  |  |  |  |  |  |  |  |
| 31 |           | Pour Concrete  | 1 day          | Wed 17-06-07        | Wed 17-06-07        | 30           | [Gantt Bar] |  |            |   |  |   |  |   |  |            |   |  |   |  |            |   |  |   |  |  |  |  |  |  |  |  |
| 32 |           | Strip Forms  | 1 day          | Thu 17-06-08        | Thu 17-06-08        | 31           | [Gantt Bar] |  |            |   |  |   |  |   |  |            |   |  |   |  |            |   |  |   |  |  |  |  |  |  |  |  |
| 33 |           | <b>West of Wesbrook Mall</b>                                   | <b>7 days</b>  | <b>Wed 17-06-07</b> | <b>Thu 17-06-15</b> | <b>23</b>    | [Gantt Bar] |  |            |   |  |   |  |   |  |            |   |  |   |  |            |   |  |   |  |  |  |  |  |  |  |  |
| 34 |           | Form   | 5 days         | Wed 17-06-07        | Tue 17-06-13        | 30           | [Gantt Bar] |  |            |   |  |   |  |   |  |            |   |  |   |  |            |   |  |   |  |  |  |  |  |  |  |  |
| 35 |           | Pour Concrete  | 1 day          | Wed 17-06-14        | Wed 17-06-14        | 34,31        | [Gantt Bar] |  |            |   |  |   |  |   |  |            |   |  |   |  |            |   |  |   |  |  |  |  |  |  |  |  |
| 36 |           | Strip Forms  | 1 day          | Thu 17-06-15        | Thu 17-06-15        | 35           | [Gantt Bar] |  |            |   |  |   |  |   |  |            |   |  |   |  |            |   |  |   |  |  |  |  |  |  |  |  |
| 37 |           | Delivery of Structural Component                               | 1 day          | Fri 17-06-09        | Fri 17-06-09        | 32           | [Gantt Bar] |  |            |   |  |   |  |   |  |            |   |  |   |  |            |   |  |   |  |  |  |  |  |  |  |  |
| 38 |           | <b>Structural Lookout Tower</b>                                | <b>20 days</b> | <b>Fri 17-06-09</b> | <b>Thu 17-07-06</b> |              | [Gantt Bar] |  |            |   |  |   |  |   |  |            |   |  |   |  |            |   |  |   |  |  |  |  |  |  |  |  |
| 39 |           | <b>Foundation</b>  | <b>9 days</b>  | <b>Fri 17-06-09</b> | <b>Wed 17-06-23</b> |              | [Gantt Bar] |  |            |   |  |   |  |   |  |            |   |  |   |  |            |   |  |   |  |  |  |  |  |  |  |  |
| 40 |           | Foundation Excavation  | 2 days         | Fri 17-06-09        | Mon 17-06-12        | 32           | [Gantt Bar] |  |            |   |  |   |  |   |  |            |   |  |   |  |            |   |  |   |  |  |  |  |  |  |  |  |

Project: CIVL 446 Detailed Design  
Date: Mon 17-03-20

|                 |  |                    |  |                       |  |                    |  |                 |
|-----------------|--|--------------------|--|-----------------------|--|--------------------|--|-----------------|
| Task            |  | Inactive Task      |  | Manual Summary Rollup |  | External Milestone |  | Manual Progress |
| Split           |  | Inactive Milestone |  | Manual Summary        |  | Deadline           |  |                 |
| Milestone       |  | Inactive Summary   |  | Start-only            |  | Critical           |  |                 |
| Summary         |  | Manual Task        |  | Finish-only           |  | Critical Split     |  |                 |
| Project Summary |  | Duration-only      |  | External Tasks        |  | Progress           |  |                 |



| ID | Task Mode | Task Name                                | Duration       | Start               | Finish              | Predecessors | Gantt Chart |            |   |   |   |            |   |   |            |   |   |
|----|-----------|--|----------------|---------------------|---------------------|--------------|-------------|------------|---|---|---|------------|---|---|------------|---|---|
|    |           |  |                |                     |                     |              | S           | '17 May 07 | T | M | F | '17 Jun 04 | T | S | '17 Jul 02 | W | S |
| 41 |           | Foundation Preparation and Reinforcement | 3 days         | Tue 17-06-13        | Thu 17-06-15        | 40           |             |            |   |   |   |            |   |   |            |   |   |
| 42 |           | Foundation Construction                  | 3 days         | Fri 17-06-16        | Tue 17-06-20        | 41           |             |            |   |   |   |            |   |   |            |   |   |
| 43 |           | Backfilling and Grading                  | 1 day          | Wed 17-06-21        | Wed 17-06-22        | 42           |             |            |   |   |   |            |   |   |            |   |   |
| 44 |           | <b>Tower</b>                             | <b>11 days</b> | <b>Thu 17-06-22</b> | <b>Thu 17-07-06</b> |              |             |            |   |   |   |            |   |   |            |   |   |
| 45 |           | <b>Level 1</b>                           | <b>4 days</b>  | <b>Thu 17-06-22</b> | <b>Tue 17-06-27</b> |              |             |            |   |   |   |            |   |   |            |   |   |
| 46 |           | Forming of Stairwell                     | 2 days         | Thu 17-06-22        | Fri 17-06-23        | 43,37        |             |            |   |   |   |            |   |   |            |   |   |
| 47 |           | Pour Concrete for Stairwell              | 1 day          | Mon 17-06-26        | Mon 17-06-27        | 46           |             |            |   |   |   |            |   |   |            |   |   |
| 48 |           | Strip Form of Stairwell                  | 1 day          | Tue 17-06-27        | Tue 17-06-27        | 47           |             |            |   |   |   |            |   |   |            |   |   |
| 49 |           | Erection of Column 1, 2, 3, 4            | 1 day          | Thu 17-06-22        | Thu 17-06-22        | 46SS         |             |            |   |   |   |            |   |   |            |   |   |
| 50 |           | Installation of Bacing                   | 1 day          | Fri 17-06-23        | Fri 17-06-23        | 49           |             |            |   |   |   |            |   |   |            |   |   |
| 51 |           | <b>Level 2</b>                           | <b>5 days</b>  | <b>Fri 17-06-23</b> | <b>Thu 17-06-29</b> |              |             |            |   |   |   |            |   |   |            |   |   |
| 52 |           | Installation of Platform                 | 1 day          | Fri 17-06-23        | Fri 17-06-23        | 49           |             |            |   |   |   |            |   |   |            |   |   |
| 53 |           | Forming of Stairwell                     | 2 days         | Mon 17-06-26        | Tue 17-06-27        | 52           |             |            |   |   |   |            |   |   |            |   |   |
| 54 |           | Pour Concrete for Stairwell              | 1 day          | Wed 17-06-28        | Wed 17-06-28        | 53           |             |            |   |   |   |            |   |   |            |   |   |
| 55 |           | Strip Form of Stairwell                  | 1 day          | Thu 17-06-29        | Thu 17-06-29        | 54           |             |            |   |   |   |            |   |   |            |   |   |
| 56 |           | Erection of Columns 1, 2, 3, 4           | 1 day          | Mon 17-06-26        | Mon 17-06-26        | 52           |             |            |   |   |   |            |   |   |            |   |   |
| 57 |           | Installation of Brancing                 | 1 day          | Tue 17-06-27        | Tue 17-06-27        | 56           |             |            |   |   |   |            |   |   |            |   |   |
| 58 |           | <b>Level 3</b>                           | <b>6 days</b>  | <b>Tue 17-06-27</b> | <b>Tue 17-07-04</b> |              |             |            |   |   |   |            |   |   |            |   |   |
| 59 |           | Installation of Platform                 | 2 days         | Tue 17-06-27        | Wed 17-06-28        | 56           |             |            |   |   |   |            |   |   |            |   |   |
| 60 |           | Forming of Stairwell                     | 2 days         | Thu 17-06-29        | Fri 17-06-30        | 59           |             |            |   |   |   |            |   |   |            |   |   |
| 61 |           | Pour Concrete for Stairwell              | 1 day          | Mon 17-07-03        | Mon 17-07-03        | 60           |             |            |   |   |   |            |   |   |            |   |   |
| 62 |           | Strip Form of Stairwell                  | 1 day          | Tue 17-07-04        | Tue 17-07-04        | 61           |             |            |   |   |   |            |   |   |            |   |   |
| 63 |           | Erection of Columns 1, 2, 3, 4           | 1 day          | Thu 17-06-29        | Thu 17-06-29        | 59           |             |            |   |   |   |            |   |   |            |   |   |
| 64 |           | Installation of Brancing                 | 1 day          | Fri 17-06-30        | Fri 17-06-30        | 63           |             |            |   |   |   |            |   |   |            |   |   |
| 65 |           | Installation of Roof Platform            | 1 day          | Mon 17-07-03        | Mon 17-07-03        | 64           |             |            |   |   |   |            |   |   |            |   |   |
| 66 |           | Installation of Stairs Guardrails        | 1 day          | Wed 17-07-05        | Wed 17-07-05        | 62           |             |            |   |   |   |            |   |   |            |   |   |
| 67 |           | Glass Façade Finishing                   | 1 day          | Tue 17-07-04        | Tue 17-07-04        | 65           |             |            |   |   |   |            |   |   |            |   |   |
| 68 |           | Finishing                                | 2 days         | Wed 17-07-05        | Thu 17-07-06        | 67           |             |            |   |   |   |            |   |   |            |   |   |
| 69 |           | <b>Curbs and Ramp Build</b>              | <b>13 days</b> | <b>Wed 17-06-07</b> | <b>Fri 17-06-23</b> |              |             |            |   |   |   |            |   |   |            |   |   |
| 70 |           | <b>North Side (Zone A)</b>               | <b>5 days</b>  | <b>Wed 17-06-07</b> | <b>Tue 17-06-13</b> |              |             |            |   |   |   |            |   |   |            |   |   |
| 71 |           | Form                                     | 3 days         | Wed 17-06-07        | Fri 17-06-09        | 24           |             |            |   |   |   |            |   |   |            |   |   |
| 72 |           | Pour Concrete                            | 1 day          | Mon 17-06-12        | Mon 17-06-12        | 71           |             |            |   |   |   |            |   |   |            |   |   |
| 73 |           | Finish                                   | 1 day          | Wed 17-06-07        | Wed 17-06-07        | 71SS         |             |            |   |   |   |            |   |   |            |   |   |
| 74 |           | Strip Forms                              | 1 day          | Tue 17-06-13        | Tue 17-06-13        | 72           |             |            |   |   |   |            |   |   |            |   |   |
| 75 |           | <b>South East Side (Zone B)</b>          | <b>4 days</b>  | <b>Wed 17-06-14</b> | <b>Mon 17-06-19</b> |              |             |            |   |   |   |            |   |   |            |   |   |
| 76 |           | Form                                     | 2 days         | Wed 17-06-14        | Thu 17-06-15        | 70           |             |            |   |   |   |            |   |   |            |   |   |
| 77 |           | Pour Concrete                            | 1 day          | Fri 17-06-16        | Fri 17-06-16        | 76           |             |            |   |   |   |            |   |   |            |   |   |
| 78 |           | Finish                                   | 1 day          | Wed 17-06-14        | Wed 17-06-14        | 76SS         |             |            |   |   |   |            |   |   |            |   |   |
| 79 |           | Strip Forms                              | 1 day          | Mon 17-06-19        | Mon 17-06-19        | 77           |             |            |   |   |   |            |   |   |            |   |   |
| 80 |           | <b>South West Side (Zone C)</b>          | <b>4 days</b>  | <b>Tue 17-06-20</b> | <b>Fri 17-06-23</b> |              |             |            |   |   |   |            |   |   |            |   |   |



|   |                 |  |                    |  |                       |  |                    |  |                 |  |
|---|-----------------|--|--------------------|--|-----------------------|--|--------------------|--|-----------------|--|
| Project: CIVL 446 Detailed Design<br>Date: Mon 17-03-20 | Task            |  | Inactive Task      |  | Manual Summary Rollup |  | External Milestone |  | Manual Progress |  |
|   | Split           |  | Inactive Milestone |  | Manual Summary        |  | Deadline           |  |                 |  |
|   | Milestone       |  | Inactive Summary   |  | Start-only            |  | Critical           |  |                 |  |
|   | Summary         |  | Manual Task        |  | Finish-only           |  | Critical Split     |  |                 |  |
|   | Project Summary |  | Duration-only      |  | External Tasks        |  | Progress           |  |                 |  |

| ID | Task Mode | Task Name                        | Duration      | Start               | Finish              | Predecessors | Gantt Chart |            |   |   |            |   |   |            |   |   |
|----|-----------|----------------------------------|---------------|---------------------|---------------------|--------------|-------------|------------|---|---|------------|---|---|------------|---|---|
|    |           |                                  |               |                     |                     |              | S           | '17 May 07 | M | F | '17 Jun 04 | T | S | '17 Jul 02 | W | S |
| 81 |           | Form                             | 2 days        | Tue 17-06-20        | Wed 17-06-27        | 75           |             |            |   |   |            |   |   |            |   |   |
| 82 |           | Pour Concrete                    | 1 day         | Thu 17-06-22        | Thu 17-06-22        | 81           |             |            |   |   |            |   |   |            |   |   |
| 83 |           | Finish                           | 1 day         | Tue 17-06-20        | Tue 17-06-20        | 81SS         |             |            |   |   |            |   |   |            |   |   |
| 84 |           | Strip Forms                      | 1 day         | Fri 17-06-23        | Fri 17-06-23        | 82           |             |            |   |   |            |   |   |            |   |   |
| 85 |           | <b>Sidewalks Build</b>           | <b>2 days</b> | <b>Mon 17-06-26</b> | <b>Tue 17-06-27</b> |              |             |            |   |   |            |   |   |            |   |   |
| 86 |           | Pour Concrete                    | 1 day         | Mon 17-06-26        | Mon 17-06-26        | 69           |             |            |   |   |            |   |   |            |   |   |
| 87 |           | Finish                           | 1 day         | Tue 17-06-27        | Tue 17-06-27        | 86           |             |            |   |   |            |   |   |            |   |   |
| 88 |           | Streets Paving                   | 2 days        | Wed 17-06-28        | Thu 17-06-29        | 85           |             |            |   |   |            |   |   |            |   |   |
| 89 |           | <b>Roundabout Build</b>          | <b>4 days</b> | <b>Fri 17-06-30</b> | <b>Wed 17-07-0</b>  |              |             |            |   |   |            |   |   |            |   |   |
| 90 |           | Form                             | 2 days        | Fri 17-06-30        | Mon 17-07-0         | 88           |             |            |   |   |            |   |   |            |   |   |
| 91 |           | Pour Concrete                    | 1 day         | Tue 17-07-04        | Tue 17-07-04        | 90           |             |            |   |   |            |   |   |            |   |   |
| 92 |           | Strip Forms                      | 1 day         | Wed 17-07-05        | Wed 17-07-05        | 91           |             |            |   |   |            |   |   |            |   |   |
| 93 |           | <b>Finishing</b>                 | <b>4 days</b> | <b>Thu 17-07-06</b> | <b>Tue 17-07-11</b> |              |             |            |   |   |            |   |   |            |   |   |
| 94 |           | Install Paintlines               | 2 days        | Thu 17-07-06        | Fri 17-07-07        | 89           |             |            |   |   |            |   |   |            |   |   |
| 95 |           | Install Road Signage             | 1 day         | Thu 17-07-06        | Thu 17-07-06        | 89           |             |            |   |   |            |   |   |            |   |   |
| 96 |           | Landscaping                      | 3 days        | Fri 17-07-07        | Tue 17-07-11        | 95           |             |            |   |   |            |   |   |            |   |   |
| 97 |           | <b>Construction Close-out</b>    | <b>3 days</b> | <b>Wed 17-07-12</b> | <b>Fri 17-07-14</b> |              |             |            |   |   |            |   |   |            |   |   |
| 98 |           | Site Clean Up                    | 2 days        | Wed 17-07-12        | Thu 17-07-13        | 96           |             |            |   |   |            |   |   |            |   |   |
| 99 |           | Construction Crew Demobilization | 1 day         | Fri 17-07-14        | Fri 17-07-14        | 98           |             |            |   |   |            |   |   |            |   |   |



|   |                 |  |                    |  |                       |  |                    |  |                 |  |
|---|-----------------|--|--------------------|--|-----------------------|--|--------------------|--|-----------------|--|
| Project: CIVL 446 Detailed Design<br>Date: Mon 17-03-20 | Task            |  | Inactive Task      |  | Manual Summary Rollup |  | External Milestone |  | Manual Progress |  |
|   | Split           |  | Inactive Milestone |  | Manual Summary        |  | Deadline           |  |                 |  |
|   | Milestone       |  | Inactive Summary   |  | Start-only            |  | Critical           |  |                 |  |
|   | Summary         |  | Manual Task        |  | Finish-only           |  | Critical Split     |  |                 |  |
|   | Project Summary |  | Duration-only      |  | External Tasks        |  | Progress           |  |                 |  |


**APPENDIX F – TRAFFIC MANAGEMENT PLAN**



**TRANSIT DETOUR (BUS 84 & 44):**



**SHUTTLE BUS PROVISION FOR MISSED BUS STOP:**



**SHUTTLE BUS DETOUR (BUS C18):**

