

University of British Columbia

Social Ecological Economic Development Studies (SEEDS) Sustainability Program

Student Research Report

Wesbrook Mall Phase 4 Redesign

Prepared by: Josh Bian, Joshua Chong, George Gu, Alvin Lok, Simar Sidhu, Jason Wongso

Prepared for:

Course Code: CIVL 446

University of British Columbia

Date: 4 April 2022

Disclaimer: "UBC SEEDS Sustainability Program provides students with the opportunity to share the findings of their studies, as well as their opinions, conclusions and recommendations with the UBC community. The reader should bear in mind that this is a student research project and is not an official document of UBC. Furthermore, readers should bear in mind that these reports may not reflect the current status of activities at UBC. We urge you to contact the research persons mentioned in a report or the SEEDS Sustainability Program representative about the current status of the subject matter of a report".



UBC Social Ecological Economic Development Studies (SEEDS) Sustainability Program

Student Research Report

Wesbrook Mall Phase 4 Redesign

Josh Bian, Joshua Chong, George Gu, Alvin Lok, Simar Sidhu, Jason Wongso

University of British Columbia

CIVL 446

April 4, 2022

Disclaimer: "UBC SEEDS Sustainability Program provides students with the opportunity to share the findings of their studies, as well as their opinions, conclusions and recommendations with the UBC community. The reader should bear in mind that this is a student research project/report and is not an official document of UBC. Furthermore, readers should bear in mind that these reports may not reflect the current status of activities at UBC. We urge you to contact the research persons mentioned in a report or the SEEDS Sustainability Program representative about the current status of the subject matter of a project/report".

Acknowledgments

This project would not have been possible without the help of UBC staff, SEEDS members, design instructors, and student designers involved with the Wesbrook Mall Redesign initiative. We would like to extend our gratitude to Dr. Yahya Nazhat for leading the project and coordinating plenaries. We are thankful to Dr. Clark Lim, Krista Falkner for guiding our team as design instructors. Continued guidance, mentorship, and support from UBC staff and SEEDS team helped immensely with the success of the preliminary design deliverables.

SEEDS Sustainability Program

Krista Falkner, P.Eng, Manager, Campus + Community Planning

David Gill, Program and Policy Planner

UBC Staff

Dr. Yahya Nazhat, Course Coordinator and Project Leader

Dr. Clark Lim, P.Eng, Design Instructor

Executive Summary

The final design of the Phase 4 Westbrook Mall Redesign will maximize safety for all transportation users, while minimizing costs and tree removals across the corridor. Active transportation modes and transit reliability was deemed as the main priority in the final design. This includes a 3.0m travel lane, 3.4m bus lane, and a 2.0m bike lane on the northbound (NB) side in place of the existing parking lane. Similar dimensions are used on the southbound (SB) side, with parts of the median removed to create space for a protected bike lane and on-street parking.

A 35m long underpass with dimensions of 3.3 x 3.1m (HxW) provides a safe and efficient pedestrian crossing path across Westbrook Mall. Blue Light Emergency Phones, fire suppression systems, and lighting enhances user safety. Impeller pumps with jellyfish filters are used to remove water from the underpass during heavy precipitation events.

Green Infrastructure in the form of permeable pavements and rain gardens are utilized to reduce polluted runoff and retain stormwater on-site.

Construction is scheduled to begin in June 2022, with the expected completion date of March 2023.

The final class A cost estimate for the project is \$4.5 million.

Table of Contents

Executive Summary	3
Table of Contents	4
List of Figures	7
List of Tables	7
1.0 Introduction	8
2.0 Design Criteria	10
3.0 Key Roadway Design Components	11
3.1 Travel Lanes	12
3.2 Bus Lanes	12
3.3 Bus Stops	12
3.4 Parking Lanes	14
3.5 Bike Lanes	15
3.6 Pedestrians	16
3.7 GI Infrastructure	16
3.8 Utilities	16
4.0 Technical Design Considerations	17
4.1 Roadworks	17
4.2 Underpass	18
5.0 Underpass	19
5.1 Demands	19
5.2 Additional Features	21
6.0 Green Infrastructure	22
6.1 Pervious Concrete	22
6.2 Permeable Interlocking Concrete Pavement	23
6.3 Rain Garden	24
7.0 Modeling	25
7.1 Modeling Methodology	25
7.2 Compilation of Available Data	25
7.3 Balancing & Developing 2021/2050 volumes	25
7.4 Results	28
7.5 Limitations	28
7.6 Sidra Modeling - 16th Ave	28
8.0 Construction Works	29

8.1 Schedule	29
8.2 Risks	30
8.3 Inflation	30
8.4 Interest Rates	30
8.5 Risk Register and Matrix	30
8.6 Class A Cost Estimate	32
9.0 Life Cycle Analysis	34
10.0 Additional Considerations	37
References	39
Appendix A - Construction Specifications	42
Appendix B - Scheduling	54
Appendix C - Class A Cost Estimate	55
Appendix D - Traffic Modeling	57
Appendix E - Underpass Design Load Calculations	58
Appendix F - Pump Design Calculations	59
Appendix G - Settlement Calculations	61

List of Figures

Figure 1. Map of Project Scope	9
Figure 2. Typical Cross Section	13
Figure 3. Southbound Thunderbird Boulevard Bus Stop - Planview	14
Figure 4. Southbound Hampton Place In-Lane Bus Stop - Planview	15
Figure 5. Typical Parking South of the Underpass - Planview	16
Figure 6. Underpass - Plan View	20
Figure 7. RISA Inputs and Results Design	21
Figure 8. Reinforcement Details	22
Figure 9. Standard Detailed Drawing of Pervious Concrete Sidewalk (ACI, 2011)	24
Figure 10. Standard Detailed Drawing of Permeable Interlocking Concrete Pavement (ICPI, 2022)	25
Figure 11. Standard Detailed Drawing of Rain Garden (City of North Vancouver, 2020)	25
Figure 12. Thunderbird Blvd 2021 Volumes	27
Figure 13. Thunderbird Blvd 2050 Volumes	27
Figure 14. Construction Phasing	30
Figure 15. Risk Matrix	32
Figure 16. Class A Cost Estimate Chart Breakdown.	34
Figure 17. Life Cycle Analysis Process	35
Figure 18. LCA Summary Chart	37

List of Tables

Table 1. Team Contributions & Review	10
Table 2. Transportation Facility - Minimum vs Design Widths	12
Table 3. Standards, Codes & Software Packages	12
Table 4. Thunderbird Blvd 2021 Synchro Model Output Results	29
Table 5. Thunderbird Blvd 2050 Synchro Model Output Results	29
Table 6. Construction Phasing Key Dates	31
Table 7. Risk Register	33
Table 8. Class A Cost Estimate Summary	35
Table 9. Life Cycle Analysis Stages	36
Table 10. LCA Impact Categories	36
Table 11: LCA Results	37
Table 12. Maintenance Plan	39

1.0 Introduction

Team 11 Consultants completed the Westbrook Mall Phase 4 redesign between Thunderbird Blvd. and 16th Ave as requested by UBC SEEDS in December 2021. Major components in the design include reallocation of surface auto, transit, biking, and pedestrian facilities along with construction of a pedestrian underpass south of the Thunderbird Arena.




Figure 1. Map of Project Scope

Team contributions are listed below:

Table 1. Team Contributions & Review

Team Member	Contributions	Review
Simar Sidhu	Drainage/Utility Drawings , X-sections, Key Design Components Write Up	Josh Bian, Alvin Lok
George Gu	Introduction, Initial design, Underpass Pump Design, Underpass Accessories, Technical Considerations	Simar Sidhu, Jason Wongso
Joshua Chong	Traffic Modeling & Forecasting, Planview Drawing, Standard Detail Drawings, Signage Plans	Josh Bian, Alvin Lok
Jason Wongso	Executive Summary, Green Infrastructure, Life-cycle Assessment	Joshua Chong, Simar Sidhu
Josh Bian	Underpass Design and Detailed Drawings	George Gu, Jason Wongso
Alvin Lok	Construction Management, Cost Estimate, Scheduling, Risk Analysis	Joshua Chong, George Gu

The scope of the project involves 5 main goals. This includes:

1. Encourage, prioritize, and maximize the safety of all active transportation modes including transit, cycling, and walking.
2. Design a pedestrian grade separated crossing to allow for safe and efficient pedestrian travel at Wesbrook Mall.
3. Incorporate GI infrastructure to retain stormwater on site.
4. Create a curbside management strategy working in conjunction with a separated bike facility to maintain safety and efficiency for users.
5. Reduce costs where possible.

The following sections describes the team's process and methodology used to develop a final design.

2.0 Design Criteria

To meet the goals mentioned above, the team applied best practice standards along with various requests made by the client. The final design followed the same criteria mentioned by the preliminary design; minimizing cost, tree removal, parking removal, utilities relocation as well as improving sustainability with Green Infrastructure, and prioritizing transit and active transportation. The recommended design widths are provided and listed below in Table 2.

Table 2. Transportation Facility - Minimum vs Design Widths

Facility Type	Design Constrained Widths (m)	Design Recommendation Widths (m)
Sidewalks	2.0	2.2
Bike Lane	1.8	2.0
Bus Lane	3.4	minimum
Travel Lane	3.0	3.2 - 4.0
Parking	2.2	2.5

2.1 Standards and Software

The team utilized various engineering standards, specifications, and software packages throughout the design phase of the project. The following table below outlines them:

Table 3. Standards, Codes & Software Packages

Standards / Codes	Software Packages
BC Active Transportation Design Guide (BCATDG)	Synchro 6
TAC (TAC) Geometric Design Guide for Canadian Roads	Sidra Intersection 9
City of Vancouver Engineering Design Manual	AutoCAD
Geometric Design of Highway and Streets AASHTO	CIVIL 3D
UBC Transportation Plan / City of Vancouver Transportation 2040	-
Manual on Uniform Traffic Control Devices (MUTCD)	-

3.0 Key Roadway Design Components

The key roadway design components are showcased in the detailed design drawings package prepared according to City of Vancouver Geometric Design guidelines with additional technical guidance from BCATDG and TAC. The drawing package includes five planview drawings of the project scope with detailed proposed design for the corridor. Proposed signage plans are included aligning with MUTCD standards to identify existing, relocated and new signage for implementation. Standard geometric details are also developed to help facilitate the design of detailed specifications. The planview drawings are supplemented with cross-section drawings detailing key locations and segments. The utility drawings highlight the existing drainage, relocation of catch basins, and other utilities in conflict with the proposed design. This section discusses in detail key components that guided the design for the Wesbrook Mall corridor. Drawing packages are attached before the Appendix.

The Phase 4 redesign of Wesbrook Mall prioritizes active transportation with focus on dedicated transit and bike lanes along the corridor. The proposed design includes raised bike lanes and bus lanes with reductions in travel lane width and removal of parking lanes. Additionally, changes are proposed for the existing sidewalks, bus stop locations, and utilities. The pedestrian crossing at Thunderbird Arena will see a significant improvement with a dedicated pedestrian underpass. Adhering to UBC's stormwater retention goals, GI infrastructure in the form of rain gardens, permeable pavement and concrete is incorporated at feasible locations. The proposed cross-section is within the existing right of way avoiding potential property conflicts. This section explains the components of each feature of the design in detail.

[Figure 2](#) below lists the dominant features of the design:




Figure 2. Typical Cross Section

3.1 Travel Lanes

The proposed design features one travel lane heading in the NB and SB directions separated by a median along the span of the corridor. Travel lanes are adjacent to the median with a width of 3.0-3.5m, accompanied by turn lanes at Thunderbird Blvd, and Thunderbird Arena. The turn lanes have an average width of 3.2m. The travel lanes and turning lane widths are minimized throughout the design to discourage single occupancy vehicles and provide additional right of way width for transit, sidewalks and bike lanes.

3.2 Bus Lanes

A key feature of the redesign are dedicated bus lanes to assist with projected volume of transit at peak hours. The SB direction has a 3.4m wide bus lane for the length of the corridor. In the NB direction, the 3.4m bus lane starts at Thunderbird Arena near the proposed underpass and ties into the Phase 2 bus lane at Thunderbird Blvd. The bus lanes are adjacent to the 0.9m proposed buffer, where feasible, to provide physical separation for vulnerable road users such as cyclists and pedestrians from motor vehicle traffic.

3.3 Bus Stops

Two bus stops are incorporated in the SB direction and a 3.0m bus bay in NB direction. The bus stop near Thunderbird Blvd requires relocation of the bus bulge to aid the required minimum widths for the SB cross-section of roadway. The second SB bus stop at Hampton Place is an in-lane stop to provide

comfortable pedestrian street space for boarding and alight and avoid potential utility conflicts at the location. [Figure 3](#) and [figure 4](#) show images of the bus stops in the SB direction.




Figure 3. Southbound Thunderbird Boulevard Bus Stop - Planview




Figure 4. Southbound Hampton Place In-Lane Bus Stop - Planview

3.4 Parking Lanes

Another key feature of the redesign is the reduction of the parking lanes. A parking inventory assessment during the morning and afternoon peak periods, determined the feasibility in removing the segment from Thunderbird Blvd to the underpass to provide right of way space for the exclusive bus lane and raised bike lane. Parking remains in the SB direction with a width of 2.4m from the underpass until Hampton Place. Parking also remains shortly after the SB Hampton in-lane bus to provide easy accessibility for field users. The 2.5m wide NB parking lane from the underpass to Hampton Place also serves as the loading zone at Hampton Place. [Figure 5](#) represents the typical parking remaining just south of the underpass.




Figure 5. Typical Parking South of the Underpass - Planview

3.5 Bike Lanes

Raised bike lanes are designed unidirectionally with a minimum width of 1.8m in both directions along the corridor. To provide safety, comfort, and additional space for a door zone for parked cars, a 0.6m to 0.9m buffer separation is implemented where feasible along Wesbrook Mall. The bike lanes are dedicated for other active transportation modes such as e-scooters and future micro mobility as well.

3.6 Pedestrians

Sidewalks are redeveloped to be 2.0m wide in both NB and SB directions. No significant modifications are proposed for the existing 2.0m sidewalks. The existing green boulevard separates pedestrians from bikes. Repavement is also required to install permeable material.

3.7 GI Infrastructure

Rain gardens are proposed at 3 locations to reduce water run-off and to enhance roadway aesthetics. Permeable pavement for the pedestrian sidewalk and parking pockets are designed to increase the infiltration and stormwater retention goal set by UBC. GI infrastructure is an important criteria for this project hence emphasis is placed to incorporate them as much as possible.

3.8 Utilities

Due to imprecise knowledge of underground utilities at project site, the team is required to exercise extreme caution during excavation. Because no new right of way was added, the majority of existing utilities such as the hydrants, telecom manholes, power manholes, existing gas valves, etc. are unaffected. The largest impact is on the 37 catch basins which require relocation. The underpass area has significant utility conflicts with several storm and sewer manholes requiring relocation. Gas lines, power lines, waterlines and sanitary lines will be redirected. The existing and abandoned utility pipes also require removal in the underpass construction area.

4.0 Technical Design Considerations

4.1 Roadworks

Technical design considerations for roadworks include:

1. Allocating space to optimize facilities for automobiles, transit, cyclists, and pedestrians.
 - a. Providing enough space to include dedicated transit lanes in areas assessed to develop a queue during busy times.
 - b. Establish continuous, raised bike lanes throughout the length of the road to provide cyclists with separation from motor vehicle traffic.
 - c. Weave cycling lanes behind bus stop landing pads to minimize conflicts between transit users and cyclists.
 - d. Retain parking spaces as much as possible to provide space for varsity field users and visitors to residences.

2. Minimizing tree removals

Tree removals were minimized by strategically placing new and realigned automobile, transit, and cycling lanes in avoidance of trees. Curb cuts on the center median are implemented on the SB side instead of the NB side to avoid tree removals: cycling lanes were weaved around bus stops to avoid existing trees.

3. Applying Green Infrastructure

Rain gardens and permeable pavements were efficiently designed at new catch basins and curb parking pockets to minimize changes to existing infrastructure while establishing more sustainable solutions for new GI infrastructure.

4. Establishing an aesthetical and spacious design for the pedestrian underpass

To ensure the pedestrian underpass fits the aesthetics of the local environment, the team designed the underpass with modest sized entrances while providing adequate of lighting and headspace underground to improve the user experience

4.2 Underpass

The main technical challenges for the underpass included facility design, tunneling, dewatering, and minimizing impacts on existing infrastructure.

1. Facility design

To ensure the underpass meets existing municipal design standards and guidelines, the dimensions, ramp grade, and stair height are carefully considered and incorporated into the final design.

2. Tunneling

The underpass tunnel will be prefabricated and placed using a cut and cover method. Because of factors relating to low excavation depth, soil conditions/type, and overall tunnel length, cut and cover was chosen as the preferred excavation mode compared to other methods such as blasting or boring. Soil conditions beneath and beside the proposed location have been assessed and geotechnical reports were analyzed to ensure feasibility of tunnel design.

3. Dewatering

A pump installed in a vault below the tunnel will remove excess water accumulated during storms. The pump was selected to meet the head and flow criteria while also considering maintenance and power consumption. Technical considerations also include additional pipes and electrical connections for the operation of the pump. Jellyfish filters from Langley Concrete reduce the impact of clogging of the pump due to debris. The pump includes water pressure sensors to only operate during precipitation events, and requires regular maintenance and inspection. The considerations are captured in the final design and can be found in [Appendix F](#)

4. Minimizing impacts on existing infrastructure and traffic

The depth, pathing, and grade of the underpass were designed to minimize utility relocations.

Traffic disruptions will be reduced by closing only half of the road, keeping a minimum number of lanes open during construction Detailed Design

5.0 Underpass

The pedestrian underpass dimensions were retained from the preliminary design phase and underwent further analysis and detailing to ensure adequate serviceability, aesthetics, and compatibility with the new roadway. The final detailed design has an overall span of 35m across with 1.75m wide entrances. The overall tunnel dimension is 3.3x3.1m (H x W) with 300mm walls. Details can be found in Drawing Number 24-30 of the drawing package.




Figure 6. Underpass - Plan View

5.1 Demands

Structural analysis was conducted to determine the critical demands on the structure. To ensure proper steps were followed, Team 11 used the following guidelines and manuals:

- CSA A-23.3 (2014) Design of Reinforced Concrete Structures

- CSA S-16 (2019) Design of Steel Structures
- CSA S-6 (2019) Canadian Highway Bridge Design Code
- BC Building Code (2018) Section 4.1: Structural Loads and Procedures
- BC Bridge Standards and Procedures Manual (2016)

Demands were computed based on vehicle/pedestrian live loads and soil/concrete dead loads. Lateral loads induced from soil pressure were also determined using soil mechanics principles. The tunnel was simplified into a box structure with fixed connections at each corner; the loads were then imputed into RISA to determine the critical moment and shear forces at their respective locations on the structure. The critical shear force and moment at the corners of the bottom slab are 138.6kN and 69.3kNm as shown on [Figure 7](#) below. Additionally, a bearing demand of 92.4kPa was also computed based on the identified soil classification.




Figure 7. RISA Inputs and Results Design

Reinforcement selection and placement was the primary focus during the detailed design phase. It was determined that a 75mm clear cover was required where the concrete is in contact with the soil while a 40mm cover was required to protect the interior face from freeze thaw cycles. In each wall, 20M longitudinal bars spaced at approximately 500mm were selected to resist the flexural demands. 20M transverse reinforcement was also used for adequate crack control. The resisting moment and shear

capacities were 74.9kNm and 167.1kN while the bearing capacity was 150 kPa. The design thus passed all required demand checks.




Figure 8. Reinforcement Details

Additionally, 10M transverse and longitudinal stair reinforcements at various spacings were used to minimize cracks and deflections. The load demands at the stairs were deemed not critical due to lower soil loads; hence, the stair walls and roof used the same 20M reinforcement design as described above.

5.2 Additional Features

To complete the design, 9 lights were selected to span across the ceiling with sprinklers placed in 2.3m intervals throughout. A UBC Campus Blue Phone will be used in the middle of the underpass. Handrails will be located along the stairs in compliance with BC Building Code Standards.

To ensure the underpass does not fail due to settlement, a check concluded acceptable final settlement of 3cm based on soil conditions provided by the UBC groundwater and geotechnical investigation. Detailed calculations can be found in [Appendix G](#).

The head requirement for the pump is 7m from the elevation of the pump vault to the catch basin at ground level. A design flow demand of 25GPM was determined based on a 1 in 100 year hourly

precipitation estimate of 10mm/hr. The design precipitation was assumed in reference to the historical rain event that occurred in November 2021. The underpass is situated on the highly permeable upper quadra sand layer (Piteau and Associate) while the groundwater is 45m below the surface. Therefore, infiltration into the tunnel will only occur through soil above the underpass.

Upon considering operational efficiency under varying flow conditions. The pump selected is a NS 4-23 CVBP end suction close coupled single stage pump that will operate when the pressure sensor is triggered when the pump is submerged. The pump will be connected to the existing AC main and powered on by a capacitor when an inflow is detected. The pump system and demand curve can be found in [Appendix F](#).

6.0 Green Infrastructure

Green Infrastructure in the form of permeable pavements and rain gardens is used across the corridor to retain stormwater on-site. The following section highlights the details of the GI Infrastructure implemented in the redesign.

6.1 Pervious Concrete

Pervious concrete will be used for the pedestrian sidewalk. It uses less sand and fine aggregates in the mix design, creating more voids in the material, which allows stormwater to seep through the surface, preventing standing water from forming in freezing temperatures. The absence of standing water and the increased roughness of the surface improve traction for pedestrians, improving safety and comfort. This also eliminates the need for de-icing salt reducing the long-term accumulation of chloride in the soil, which can negatively impact the environment.




Figure 9. Standard Detailed Drawing of Pervious Concrete Sidewalk (ACI, 2011)

6.2 Permeable Interlocking Concrete Pavement

Permeable Interlocking Concrete Pavement (PICP) is used in the parking pockets along Wesbrook Mall.

This form of permeable pavement promotes stormwater infiltration and groundwater recharge. The concrete pavers also form an interlocking pattern which improves aesthetics. The joints between the bricks are filled with permeable aggregates that filter stormwater before it reaches the soil subgrade.

While this comes at a higher cost compared to regular asphalt pavement, PICP has a longer expected service life, minimizing future maintenance costs and environmental impact. The surface of the PICP will need to be regularly cleaned using high pressure water to optimize the stormwater infiltration rate throughout its lifespan.




Figure 10. Standard Detailed Drawing of Permeable Interlocking Concrete Pavement (ICPI, 2022)

6.3 Rain Garden

Rain gardens will be installed along the curb extensions on both sides of the corridor (see Drawing Number 1-5 in Drawing Packages). These create more pervious area along the corridor, promoting stormwater infiltration and groundwater recharge. The soil filters out runoff pollutants before reaching the soil subgrade. Rain gardens also provide additional aesthetic value, although regular maintenance such as trash removal, weeding, and dead vegetation removal are required to keep the space clean.




Figure 11. Standard Detailed Drawing of Rain Garden (City of North Vancouver, 2020)

7.0 Modeling

Modeling was conducted to determine the extent of the NB bus lane redesign along the entire Wesbrook Mall corridor. The analysis of the 2021 Base Synchro Models and 2050 Design Models determined that the existing 95th percentile queue length is satisfactory for the bus lane to begin just north of the underpass.

7.1 Modeling Methodology

This section describes the process of developing Synchro models for the Thunderbird Blvd intersection accounting for the key considerations such as traffic volumes, signal timings, and Synchro model parameters.

7.2 Compilation of Available Data

The historical turning movement counts (TMC) provided by SEEDs were reviewed and compiled. The historical TMCs consisted of 2018 and 2019 counts. Signal timing reports were also provided for the Thunderbird Blvd and Wesbrook Mall intersection.

7.3 Balancing & Developing 2021/2050 volumes

Intersection volumes at Thunderbird Blvd and 16th Ave along Wesbrook mall were reviewed and adjustments were made for volume balancing based on reasonable estimates for changes such as land development. To account for recent population growth at UBC, a 1% compound annual growth rate was applied to both intersections. This growth rate was established based on a review of the historical traffic data from UBC's Annual Fall Transportation Plan and UBC statistics on students, staff, and faculty from UBC Data & Analytics. [Figures 12](#) and [13](#) below illustrate the 2021 and 2050 volumes developed in Synchro 6 models.




Figure 12. Thunderbird Blvd 2021 Volumes




Figure 13. Thunderbird Blvd 2050 Volumes

To determine the length of the NB bus lane leading into the Thunderbird Blvd intersection, analyses were conducted for the Synchro models to determine parameters including total delay, volume to capacity ratio (v/c), LOS, and the 95th percentile queue length. [Tables 4](#) and [5](#) outline the Synchro 6 model outputs for the above elements. The model outputs are separated into AM Peak Period, (MD Peak Period) and [PM Peak Period].

Table 4. Thunderbird Blvd 2021 Synchro Model Output Results

Approach	V/C Ratio	Total Delay (s)	LOS	95% Queue Length (m)
EBLT	0.60 (0.53) [0.76]	39.8 (37.8) [35.3]	D (D) [D]	20.4 (27.3) [48.2]
EBTH	0.22 (0.07) [0.17]	24.3 (25.3) [17.8]	C (C) [B]	14.5 (4.8) [10.8]
EBRT	0.20 (0.30) [0.54]	7.4 (8.1) [22.4]	A (A) [C]	2.8 (4.8) [39.1]
WBLT	0.62 (0.19) [0.53]	38.1 (27.8) [37.8]	D (C) [D]	23.6 (11.8) [23.7]
WBLT, WBTH	0.54 (0.16) [0.32]	29.7 (13.3) [22.3]	C (B) [C]	25.2 (8.9) [12.0]
NBLT	0.52 (0.23) [0.55]	9.7 (5.1) [29.3]	A (A) [C]	36.5 (12.8) [#32.3]
NBTH, NBRT	0.62 (0.28) [0.39]	10.9 (4.9) [11.7]	B (A) [B]	92.8 (29.6) [59.7]
SBLT	0.17 (0.10) [0.16]	18.9 (11.7) [12.3]	B (B) [B]	11.2 (7.5) [9.8]
SBTH	0.36 (0.30) [0.49]	17.9 (11.8) [13.7]	B (B) [B]	57.0 (49.3) [70.0]
SBRT	0.31 (0.15) [0.21]	9.9 (6.4) [8.3]	A (A) [A]	22.6 (12.3) [13.4]
Intersection	-	17.6 (11.3) [19.8]	B (B) [B]	-

Table 5. Thunderbird Blvd 2050 Synchro Model Output Results

Approach	V/C Ratio	Total Delay (s)	LOS	95% Queue Length (m)
EBLT	0.75 (0.61) [0.95]	47.9 (38.2) [55.7]	D (D) [E]	26.3 (33.2) [#64.6]
EBTH	0.23 (0.08) [0.19]	21.0 (23.1) [16.2]	C (C) [B]	17.1 (5.4) [12.3]
EBRT	0.22 (0.33) [0.64]	5.6 (6.7) [24.8]	A (A) [C]	2.5 (4.5) [52.8]
WBLT	0.67 (0.22) [0.61]	35.4 (25.8) [38.3]	D (C) [D]	28.8 (13.6) [28.7]
WBLT, WBTH	0.58 (0.18) [0.37]	27.1 (11.5) [22.5]	C (B) [C]	30.7 (9.8) [14.9]
NBLT	0.78 (0.39) [1.02]	24.5 (7.8) [112.3]	C (A) [F]	#87.7 (19.5) [#54.1]
NBTH, NBRT	0.91 (0.41) [0.58]	29.9 (7.4) [17.1]	C (A) [B]	#200.2 (48.9) [97.6]
SBLT	0.62 (0.16) [0.36]	55.6 (15.6) [21.5]	E (B) [C]	#22.0 (10.8) [16.7]
SBTH	0.62 (0.46) [0.73]	27.2 (17.0) [22.3]	C (B) [C]	78.1 (79.5) [114.2]
SBRT	0.50 (0.23) [0.31]	16.6 (9.8) [11.5]	B (A) [B]	35.1 (20.5) [21.2]
Intersection	-	28.0 (13.7) [30.7]	C (B) [C]	-

Notation: AM (MD) [PM]

#: actual queue length may be longer. The values are still valid for design purposes.

m: queue lengths are metered out.

The HCM grades the LOS of a facility on a scale from A to F. All intersections with a LOS F have been bolded and highlighted in red. A review of the Synchro model results indicated that while most of the v/c ratios are below 1.0, a few movements, especially turning movements, do have a v/c ratio near or greater than 1.0.

7.4 Results

[Table 5](#) above indicates the NB left hand turning movement having an LOS F in the 2050 model. This LOS is reasonable because of the competing green time between the eastbound (EB) movement and students departing from campus via Thunderbird Parkade in the evening. This can be adjusted by retiming the signal for the intersection to optimize the phases within this rush hour period.

The maximum queue length for the morning peak NB through movements are 92.8m and 200.2m for 2021 and 2050 respectively, given that the exclusive bus lane within the design will occur approximately 140m away from the Thunderbird Blvd intersection. Sample 2050 synchro model reports are provided for the AM and PM peak periods in [Appendix D](#).

7.5 Limitations

The existing 2021 and 2050 design year models were coded in Synchro 6 without the exclusive bus lanes heading NB and SB. Operationally, the Synchro model results for through movements heading both NB & SB are expected to perform even better than the results provided in [Tables 4](#) and [5](#). Other alternative options were considered such as transit signal preemption for transition, but it was determined that the current operations would be adequate for this design.

7.6 Sidra Modeling - 16th Ave

A sample Sidra model was developed for the 16th Ave and Wesbrook Mall intersection to determine existing queue lengths headed SB, but it was concluded that no geometric changes or lane changes would occur at the roundabout. A sample report for Sidra lane movements and results are provided in [Appendix D](#).

8.0 Construction Works

8.1 Schedule

The construction schedule has been developed to minimize delays and reduce negative effects on traffic on Wesbrook Mall. Construction will begin with mobilization in June 2022, and continue on until March 2023. Mobilization for roadworks and the underpass will begin simultaneously, but excavation of the underpass will start only once the preceding road section is finished repaving. This reduces the time that Wesbrook Mall is closed, and allows for the simultaneous construction of both the roadworks and the underpass. The area's key dates for the completion of each stage are listed below in Table 6.:




Figure 14. Construction Phasing

Table 6. Construction Phasing Key Dates

Stage	Start	End
1	June 1, 2022	July 1, 2022
2	July 1, 2022	October 1, 2022
3	October 1, 2022	December 1, 2022
4	December 1, 2022	February 2, 2023
Cleanup and Demobilization	Feb 2, 2023	March 15, 2023

See a full breakdown of the schedule in [Appendix B](#).

8.2 Risks

Since Team 11 Consultants released the preliminary design report, changes in macroeconomic trends have caused significant changes to a few key risks. While factors such as safety, execution, and adverse weather are still just as harmful as they were previously, hazards relating to commodities prices, interest rates, or other macroeconomic factors have increased in both probability and impact.

8.3 Inflation

Russia's invasion of Ukraine, and subsequent sanctions imposed on them by western nations, has increased commodities prices drastically. The restrictions on Russian financial institutions makes it impossible to trade certain Russian exports, including items which are crucial to the construction industry such as crude oil, nickel, steel, iron, and other precious metals.

The current geopolitical crisis represents high volatility in global markets, and Team 11 Consultants is not confident in predictions of the prices of these goods in the short term. To mitigate the effects of uncertainty, we recommend the purchasing of futures contracts to secure prices of commodities. Due to the severe and current impacts of this volatility, we have assigned maximum probability and impact scores for this hazard.

8.4 Interest Rates

The United States Federal Reserve has announced its intention to aggressively raise interest rates to reduce spending and control inflation. The Bank of Canada has also signaled similar intentions. When interest rates increase, this will increase the cost of borrowing for all parties, thereby increasing cost of capital. The level of impact is dependent on the change in interest rates imposed, and as this rate is unpredictable. We have assigned a maximum probability and impact score to this hazard.

8.5 Risk Register and Matrix

Below is a risk register detailing the various risks discussed above, as well as a risk matrix showing the relative risk of each item.




Figure 15. Risk Matrix

Table 7. Risk Register

Item	Hazard	Impact	Probability Score	Impact Score	Risk Score
1	Project defaults on loans due to low cash flows	Project lockout and/or cancellation	1	5	5
2	Unexpected adverse weather conditions due to climate change	Delays levy heavy monetary costs and social costs due to increased public disruption	5	3	15
3	Increase in consumer price index during project	Cost of project increases	5	5	25
4	Increase in labor costs during project	Cost of project increases	4	3	12
5	Labor shortage during construction or operation	Halting or slowdown of activities, incurring high costs for owner	4.5	3	13.5
6	Bank of Canada increases interest rates	Increasing debt service raises project costs for owner	5	3	15
7	Unstable supply chain causes shortages to material or equipment	Halting or slowdown of activities, incurring high costs for owner	5	5	25

8	Public opposition to additional traffic	Delays or cancellation of project, leading to reputational and monetary losses	1	4	4
9	Poor implementation during EPC phase leading to unsafe designs or work conditions	Injury or death of project personnel or users	2	5	10
10	Shortage or mismanagement of project funds leads to bloated budget	Heavy costs for client and possible cancellation of project	2	3	6
11	Operational hazards due to construction flaws or user error	User safety threatened following project completion	4	5	20

8.6 Class A Cost Estimate

The cost estimate was developed with consideration of the risks in Section 8.2. RSMeans Estimating Software containing standard costs of construction items was used to model cost. Revisions to the roadworks scope of work and green infrastructure yield a final construction cost of \$4.5 million CAD, with an additional \$130,000 in consulting fees, bringing the total to \$4.7 million. This figure accounts for inflation, currency exchange rates, contractor markup, and bonds and insurance. Due to the factors mentioned above in Section 8.5, the contingency has been increased to 20%, up from 10%. A cost summary is shown below, and a full breakdown of project cost can be found in [Appendix C](#).

Table 8. Class A Cost Estimate Summary

Cost Summary	
Roadworks Cost	\$1,271,235
Underpass Cost	\$297,970
Adjustments	
Inflation	1.376
Currency	1.28
Contingency	1.2
Contractor Markup	1.2
Bonds and Insurance	1.05
Management and Permitting	1.085
Project Construction Cost	\$4,534,000
Consulting Fees	\$130,000
Final Project Cost	\$4,664,000




Figure 16. Class A Cost Estimate Chart Breakdown.

9.0 Life Cycle Analysis

Every engineering project has a wide range of environmental impacts, making it essential to understand the sources of those impacts to adopt proper mitigation policies. The Life Cycle Analysis (LCA) is a method used to assess the environmental impacts of the project throughout its life cycle. The life cycle stages included in this assessment are shown in the [figure 17](#) below.




Figure 17. Life Cycle Analysis Process

Table 9. Life Cycle Analysis Stages

LCA Stage	Description
Extraction and Production of Raw Materials	Impacts from extraction and production of construction materials
Transportation of Raw Material	Transportation of material and machines to construction Site
Road Construction	Impacts from on-site construction activities
Use of Road/Maintenance	Environmental impacts due to operations and maintenance

In this LCA, the environmental impacts of each life-cycle stage are quantified based on the following categories:

Table 10. LCA Impact Categories

Impact Category	Abbreviation	Unit of Measure
Global Warming Potential	GWP	kg CO ₂ eq.
Acidification Potential of Soil and Water	AP	kg SO ₂ eq.
Eutrophication Potential	EP	kg N eq.
Abiotic Depletion Potential (Fossil Fuel)	ADP	MJ

The table below shows the life cycle components and the resulting impact categories.

Table 11: LCA Results

Life Cycle Stage and Components			Impact Categories			
Material Production			GWP	AP	EP	ADP
Roadworks	Input	Unit	Total kg CO ₂ eq	Total kg SO ₂ eq	Total kg N eq	Total MJ eq
Asphalt	2842	m3	1.15E+06	1.03E+04	1.63E+02	4.81E+05
Permeable Pavements (Sidewalk, Parking Pockets)	230.2	m3	5.15E+04	1.66E+02	6.16E+01	3.90E+04
Underpass	Input	Unit	Total kg CO ₂ eq	Total kg SO ₂ eq	Total kg N eq	Total MJ eq
Steel	22080	kg	4.03E+04	1.63E+02	1.38E+02	1.65E+04
Concrete	76.44	m3	1.71E+04	5.52E+01	2.05E+01	1.29E+04
Material Transportation						
Transportation of Materials	Input	Unit	Total kg CO ₂ eq	Total kg SO ₂ eq	Total kg N eq	Total MJ eq
Transportation of concrete	4500	tkm	4.11E+02	1.54E+00	4.38E-01	9.20E+02
Transportation of steel	7000	tkm	6.39E+02	2.40E+00	6.82E-01	1.43E+03
Transportation of construction equipment	2000	tkm	1.83E+02	6.86E-01	1.95E-01	4.09E+02
Construction						
Road and Underpass Construction	Input	Unit	Total kg CO ₂ eq	Total kg SO ₂ eq	Total kg N eq	Total MJ eq
Earthworks	704	hrs	1.41E+00	6.68E-03	3.80E-04	2.83E+00
Fill	1408	hrs	6.15E+03	3.61E+01	5.81E+00	1.32E+04
Underpass	704	hrs	1.48E+06	8.67E+03	1.39E+03	3.16E+06
Use of Road/Maintenance						
Operation and Maintenance	Input	Unit	Total kg CO ₂ eq	Total kg SO ₂ eq	Total kg N eq	Total MJ eq

Life Cycle Stage and Components			Impact Categories			
Electricity for Annual Road Operation	876	kWh	5.46E+02	0.00E+00	0.00E+00	0.00E+00
Road Resurfacing	240	hrs	1.05E+03	6.16E+00	9.91E-01	2.24E+03
Waste	2000	kg	9.62E+00	5.07E-02	1.48E-03	1.60E+01
Transportation of waste	1000	tkm	5.22E+02	3.01E+00	7.20E-01	1.08E+03




Figure 18. LCA Summary Chart

The results of the life cycle analysis shows that most of the environmental impacts originate from the construction process. This means that further measures need to be taken to minimize the environmental risks during construction. As such, contractors are expected to prepare an environmental assessment plan as part of the tendering process.

Furthermore, a maintenance plan was developed to extend the service life of the main components of the project. The operations and maintenance costs can be found in [Appendix C](#). The table below provides a

summary of the maintenance plan for the main components of the corridor such as the main road, green infrastructure, and the pedestrian underpass.

Table 12. Maintenance Plan

Structure	Type of Work	Frequency
Road	Normal wear and tear (Potholes, minor cracks, paint damages on lane markings)	Annual or as needed
Road	De-icing, cleaning, tree trimming, road signage maintenance	Annual or as needed
Road	Road resurfacing	Every 20 years
Rain Garden	Trash and weed removal	Weekly
Rain Garden	Bioretention soil replacement	Every 2 years
Permeable Pavements (sidewalk and parking pockets)	Surface cleaning (high pressure water spraying and vacuum cleaning)	Weekly
Permeable Pavements (sidewalk and parking pockets)	Pavement Resurfacing	Every 20 years
Underpass	Structural Inspection	Annual
Underpass	Structural Maintenance	Every 5 years or as needed
Underpass	Cleaning and Graffiti Removal	Monthly or as needed
Underpass	Lighting Replacement and Maintenance	Every 6 months
Underpass	Pump maintenance	Monthly

10.0 Additional Considerations

This report concludes Team 11's scope of work as requested by UBC SEEDS, which covers all the technical steps and considerations leading up to construction. Permits were not considered in this report due to the project's scale and its location on University Endowment Lands. However, it is recommended for the contractor to check with UBC SEEDS and applicable regulatory bodies prior to commencing construction to minimize lead times and prevent delays. Furthermore, Team 11 is willing to continue

working alongside the selected contractor to overcome any unforeseen challenges. Additionally, Team 11 recommends UBC Seeds to continue conducting stakeholder consultation throughout the construction process to ensure that all stakeholder opinions and concerns are properly addressed.

References

American Association of State Highway and Transportation Officials. “*A Policy on Geometric Design of Highways and Streets*” Fourth Edition, 2001.

<https://sjnavarro.files.wordpress.com/2011/08/aashto-2001.pdf>

American Concrete Institute. “*Report on Pervious Concrete*” 2011.

<https://cecollection2.files.wordpress.com/2020/05/522r-10-report-on-pervious-concrete.pdf>

City of North Vancouver. “*Rain Garden Standard Drawing*” 2020.

<https://www.cnv.org/-/media/City-of-North-Vancouver/Documents/Development-Application-Resources/Engineering-Standards/Storm-and-Sanitary/S21S-RAIN-GARDEN-CURB-CUT-INLET-2020.ashx>

City of Vancouver. “*Engineering Design Manual*” 2019 Edition.

<https://vancouver.ca/files/cov/engineering-design-manual.PDF>

Chandrappa, Anush K and Krishna Prapoorna Biligiri. “*Pervious concrete as a sustainable pavement material – Research findings and future prospects: A state-of-the-art review.*” Construction and Building Materials (2016).

Credit Valley Conservation. “*Low Impact Development Road Retrofits.*” 2014. CVC. 20 November 2021.

Das, Braja M., and Nagaratnam Sivakugan. *Principles of Foundation Engineering*. SI Edition, 2019.

<https://www.structuralguide.com/settlement-of-shallow-foundations/>

Interlocking Concrete Pavement Institute. “*Permeable Pavement with Full Exfiltration to Soil Subgrade*”

2022. <https://icpi.org/permeable-interlocking-concrete-pavement-drawings>

Ministry of Transportation and Infrastructure. “*Bridge Standards and Procedures Manual*” Volume

1-Supplement to CHBDC S6-14, Oct.2016.

<https://www2.gov.bc.ca/gov/content/transportation/transportation-infrastructure/engineering-standards-guidelines/structural/standards-procedures/volume-1>

Ministry of Transportation and Infrastructure. “*British Columbia Active Transportation Design Guide 2019 Edition*” 2019.

<https://www2.gov.bc.ca/gov/content/transportation/transportation-infrastructure/engineering-standards-guidelines/traffic-engineering-safety/active-transportation-design-guide>

Piteau Associates. “*Hydrogeological and Geotechnical Assessment of Northwest Area of UBC Campus, Vancouver*” Sept. 2002.

Portland Cement Association. “*Permeable Interlocking Concrete Pavement*”2019. 20 November 2021.

Prasad. “Settlement of Shallow Foundations.” *Structural Guide*, 16 July 2020,

<https://www.structuralguide.com/settlement-of-shallow-foundations/>.

Province of British Columbia. “*BC Building Code 2018*” 2018. \

<https://free.bcpublications.ca/civix/content/public/bcbc2018/?xsl=/templates/browse.xsl&xsl=/templates/browse.xsl>

Standards Council of Canada. “*CSA A23.314. Design of Concrete Structures*” June 1, 2014.

The University of British Columbia. “*Integrated Stormwater Management Plan*” March 5, 2017.

https://planning.ubc.ca/sites/default/files/2019-11/PLAN_UBC_ISMP_Final2017.pdf

The University of British Columbia. “*Guidelines by Division Specification*”

http://www.technicalguidelines.ubc.ca/technical/divisional_specs.html

The University of British Columbia. “*Vancouver Campus Plan*”

<https://planning.ubc.ca/planning-development/policies-and-plans/campus-land-use-planning/vancouver-campus-plan>

The University of British Columbia “*UBC Transportation Plan.*” UBC Transportation Plan | UBC Campus & Community Planning

<https://planning.ubc.ca/transportation/transportation-planning/ubc-transportation-plan>

The University of British Columbia “*UBC Vancouver Transportation Status Report Fall 2019.*”

https://planning.ubc.ca/sites/default/files/2020-05/UBC2019-TransportationStatusReport-Mar5-2020_0.pdf.

The University of British Columbia “*UBC Data & Analytics.*” Planning and Institutional Research Office (PAIR)

<https://pair.ubc.ca/ubc-data-analytics/>.

WESBROOK MALL REDESIGN PHASE 4 DETAIL DESIGN DRAWINGS

PREPARED BY: JOSHUA CHONG, SIMAR SIDHU, JOSH BIAN, GEORGE GU

TEAM 11 CONSULTANTS




TABLE OF CONTENTS	
DWG #	TITLE
PART A: PLAN VIEW DRAWINGS	
01	WESBROOK MALL – THUNDERBIRD BOULEVARD
02	WESBROOK MALL – UNDERPASS
03	WESBROOK MALL – WESBROOK MALL FIELD
04	WESBROOK MALL – WESBROOK MALL TRACK
05	WESBROOK MALL – 16TH AVENUE ROUNDABOUT
PART B: CROSS SECTION DRAWINGS	
06	CROSS-SECTION 1 (STATION 0+65) & CROSS-SECTION 2 (STATION 0+90)
07	CROSS-SECTION 3 (STATION 3+82) & CROSS-SECTION 4 (STATION 4+60)
08	CROSS-SECTION 5 (STATION 5+47) & CROSS-SECTION 6 (STATION 6+00)
09	CROSS-SECTION 7 (STATION 6+62) & CROSS-SECTION 8 (STATION 7+25)
PART C: UTILITIES	
10	WESBROOK MALL – THUNDERBIRD BOULEVARD
11	WESBROOK MALL – UNDERPASS
12	WESBROOK MALL – WESBROOK MALL FIELD
13	WESBROOK MALL – WESBROOK MALL TRACK
14	WESBROOK MALL – 16TH AVENUE ROUNDABOUT

TABLE OF CONTENTS	
DWG #	TITLE
PART D: SIGNAGE DRAWINGS AND SPECIFICATIONS	
15	WESBROOK MALL – THUNDERBIRD BOULEVARD
16	WESBROOK MALL – UNDERPASS
17	WESBROOK MALL – WESBROOK MALL FIELD
18	WESBROOK MALL – WESBROOK MALL TRACK
19	WESBROOK MALL – 16TH AVENUE ROUNDABOUT
20	SPECIFICATIONS – STANDARD DETAIL DRAWING
21	SPECIFICATIONS – STANDARD DETAIL DRAWING
22	SPECIFICATIONS – STANDARD DETAIL DRAWING
23	SPECIFICATIONS – STANDARD DETAIL DRAWING
PART E: UNDERPASS DETAILS AND PUMP DESIGN	
24	UNDERPASS: GENERAL ELEVATION & PLAN VIEWS
25	UNDERPASS: STAIR & TUNNEL CROSS-SECTION VIEWS
26	UNDERPASS: DRAINAGE AND PUMP DETAILS
27	UNDERPASS: CONCRETE AND REINFORCEMENT-PLAN VIEW
28	UNDERPASS: CONCRETE AND REINFORCEMENT-ELEVATION VIEW

1. GENERAL NOTES

- ALL CONSTRUCTION AND MATERIALS SHALL BE IN ACCORDANCE WITH THE CURRENT UNIVERSITY OF BRITISH COLUMBIA AND CONSTRUCTION DOCUMENTS, SPECIFICATIONS AND STANDARD DRAWINGS; CONSTRUCTION PLANS AND DRAWINGS; WORKSAFEBC REQUIREMENTS AND APPLICABLE CONTRACT DOCUMENTS AND ALL SPECIFICATIONS REFERENCED THERIN.
- ALL APPLICABLE ON-SITE WORKS SHALL MEET THE REQUIREMENTS OF THE UNIVERSITY OF BRITISH COLUMBIA AND THE RELEVANT SECTIONS OF THE BC PLUMBING CODE.
- THE CONTRACTOR SHALL MAINTAIN COPIES OF THE ABOVE DOCUMENTS ON SITE AND SHALL ENSURE THAT ALL TRADES ARE THOROUGHLY FAMILIAR WITH THE APPLICABLE SECTIONS OF THESE DOCUMENTS.
- THE CONTRACTOR SHALL ENSURE THAT ALL APPROVALS REQUIRED FOR THE PROPOSED WORKS HAVE BEEN OBTAINED FROM ALL AUTHORITIES AND AGENCIES PRIOR TO COMMENCEMENT OF ANY CONSTRUCTION.
- THE LOCATIONS OF EXISTING UNDERGROUND SERVICES HAVE BEEN DETERMINED FROM RECORD INFORMATION OBTAINED FROM UNIVERSITY OF BRITISH COLUMBIA AND OTHERS. THE CONTRACTOR SHALL VERIFY THE LOCATION AND ELEVATION OF ALL THE EXISTING SERVICES PRIOR DISCREPANCIES, CONFLICTS OR OMISSIONS.
- THE CONTRACTOR SHALL USE EXTREME CARE WHEN WORKING NEAR EXISTING SERVICES. ANY SERVICES DISTUSTED SHALL BE REPLACED TO THE SATISFACTION OF UNIVERSITY OF BRITISH COLUMBIA AND OTHER AGENCIES AT THE EXPENSE OF THE CONTRACTOR.
- THE CONTRACTOR IS RESPONSIBLE FOR ALL MATERIALS TESTING. ALL TESTING SHALL BE CONDUCTED BY SUITABLY QUALIFIED FIRMS.
- THE CONTRACTOR IS RESPONSIBLE FOR SAFETY IN AND ABOUT EH JOB SITE DURING CONSTRUCTION. THE CONTRACTOR SHALL MAINTAIN ADEQUATE BARRIERS AND CONSTRUCTION SIGNS TO PREVENT INJURY TO THE PUBLIC AND ALL PERSONNEL ON SITE. THE CONTRACTOR SHALL CONDUCT A BC ONE CALL AND NOTIFY ALL APPROPRIATE PARTIES UNIVERSITY OF BRITISH COLUMBIA, BC HYDRO, AND AFFECTED UTILITY OWNERS, 48 HOURS PRIOR TO COMMENCING CONSTRUCTION. THE CONTRACTOR SHALL NOTIFY UNIVERSITY OF BRITISH COLUMBIA AND THE ENGINEER AT LEAST 48 HOURS IN ADVANCE OF COMMENCING CONSTRUCTION.
- THE CONTRACTOR SHALL MAKE ALL NECESSARY ARRANGEMENTS, IF REQUIRED, FOR THE INSPECTION OF ALL REQUIRED UTILITY CONNECTIONS.
- THE CONTRACTOR SHALL PROVIDE WRITTEN NOTICE TO ALL RESIDENTS AFFECTED BY CONSTRUCTION AT LEAST 48 HOURS PRIOR TO CONSTRUCTION. COPIES OF THE NOTICE SHALL BE PROVIDED TO UNIVERSITY OF BRITISH COLUMBIA AND THE ENGINEER.
- CONTRACTOR SHALL PROVIDE UNIVERSITY OF BRITISH COLUMBIA WITH ALL "AS CONSTRUCTED" INFORMATION AND SUPPLY UNIVERSITY OF BRITISH COLUMBIA WITH AN INDEPENDENT TOPOGRAPHIC SURVEY OF "AS-BUILT" LOCATIONS OF THE SURFACE FEATURES INCLUDING BUT NOT LIMITED TO ELEVATIONS FOR MANHOLE RIMS AND INVERTS, WATER VALVE BOXES, HYDRANTS AND SERVICE LOCATIONS. THE DATA SHALL BE PROVIDED IN ELECTRONIC FORMAT ACCEPTABLE TO UNIVERSITY OF BRITISH COLUMBIA AND SHALL INCLUDE THE DATE OF SURVEY, SURVEYORS NAMES AND CONTACT INFORMATION.
- TEMPORARY EXCAVATION FOR THE CONSTRUCTION OF UNDERGROUND SERVICES SHALL CONFORM TO WORKERS COMPENSATION BOARD INDUSTRIAL HEALTH AND SAFETY REGULATIONS. IF STEEPER SLOPES ARE REQUIRED, THEY SHALL BE REVIEWED BY A GEOTECHNICAL ENGINEER PRIOR TO WORKERS ENTERING THE EXCAVATION.
- THE CONTRACTORS SHALL ENSURE THAT STREETS ARE KEPT CLEAN AND FREE OF EQUIPMENT AND MATERIAL AT ALL TIMES WHEN CONSTRUCTION ACTIVITY IS NOT UNDERWAY.

2. SURVEY

- LEGAL AND TOPOGRAPHIC INFORMATION PROVIDED BY LIGMA SURVEYS.
- GROUND ELEVATIONS WERE OBTAINED BY FIELD SURVEYS CONDUCTED ON JAN. 01, 2022 AND WERE DERIVED FROM UNIVERSITY OF BRITISH COLUMBIA CONTROL MONUMENT 69S4200 ELEVATION 81.231 NAD 24.
- HORIZONTAL DISTANCES ARE GROUND-LEVEL DISTANCES UNLESS SPECIFIED OTHERWISE.
- THE ACCURACY AND COMPLETENESS OF THE TOPOGRAPHIC DATA IS CONSIDERED SUFFICIENT FOR ENGINEERING DESIGN PURPOSES AND HAS NOT BEEN VERIFIED.
- THE CONTRACTOR IS RESPONSIBLE FOR CONFIRMING THE ACCURACY AND COMPLETELY OF THE DATA PRIOR TO RELYING ON THE DATA FOR CONSTRUCTION PURPOSES.

3. EARTHWORKS AND GRADING

- OBTAIN THE GEOTECHNICAL ENGINEER'S ACCEPTANCE OF THE MATERIAL PROPOSED FOR USE AS STRUCTURAL FILL MATERIAL PRIOR TO THE MATERIAL BEING DELIVERED TO THE SITE.
- REMOVE VEGETATION AND ORGANIC MATERIAL AND ALL OTHER MATERIAL DEEMED UNSUITABLE BY THE GEOTECHNICAL ENGINEER, INCLUDING BUT NOT LIMITED TO BOULDERS AND WOOD WASTE, PRIOR TO PLACING STRUCTURAL FILL MATERIAL AND DISPOSE OFF-STIE AND AN APPROVED LOCATION THAT IS ACCEPTABLE TO UNIVERSITY OF BRITISH COLUMBIA.
- OBTAIN THE GEOTECHNICAL ENGINEER'S ACCEPTANCE OF EXCAVATED SUBGRADES PRIOR TO PLACING STRUCTURAL FILL MATERIAL.
- TRENCH BACKFILL IN AREAS THAT WILL BE PAVED OR OTHER SETTLEMENT-SENSITIVE AREAS SHALL CONSIST OF GRANULAR MATERIAL PLACED AND COMPACTED IN DISCRETE LIFTS OF MAXIMUM 300MM IN THICKNESS OR IN ACCORDANCE WITH THE GEOTECHNICAL ENGINEER'S REQUIREMENTS.
- BACKFILL WITHIN PAVED AREAS SHALL BE COMPACTED TO 95% MODIFIED PROCTOR DENSITY, OR IN ACCORDANCE WITH THE GEOTECHNICAL ENGINEER'S REQUIREMENTS. LANDSCAPE AREAS SHALL BE COMPACTED TO 90% MODIFIED PROCTOR DENSITY OR IN ACCORDANCE WITH THE GEOTECHNICAL ENGINEER'S REQUIREMENTS.
- THE CONTRACTOR IS RESPONSIBLE FOR COMPACTION TESTING AND SHALL PROVIDE UNIVERSITY OF BRITISH COLUMBIA AND THE ENGINEER WITH EVIDENCE THAT COMPACTION OF SUBGRADE FILL MATERIAL AND GRANULAR MATERIALS MEETS PROJECT SPECIFICATIONS.

4. WATERWORKS

- ALL WATERWORKS TO BE IN ACCORDANCE WITH MASTER MUNICIPAL SPECIFICATIONS SECTION 33 11 01 WATERWORKS AND THE RELEVANT SECTIONS OF THE BC PLUMBING CODE AND SHALL PASS THE INSPECTION OF THE UNIVERSITY OF BRITISH COLUMBIA PLUMBING INSPECTOR.
- CONFIRM WATERMAIN WORKING PRESSURE WITH ENGINEER PRIOR TO CONSTRUCTION.
- MINIMUM COVER ON MAINS SHALL BE 1.0M.
- PIPE SHALL BE CEMENT MORTAR LINED DUCTILE IRON PIPE CONFORMING TO AWWA 151 PRESSURES CLASS 350. PUSH-ON JOINT HUBS SHALL BE PROVIDED WITH TIE-ROD LUGS. 300MM PIPE SHALL BE PROVIDED WITH A MINIMUM OF FOUR LUGS.
- FITTINGS SHALL BE DUCTILE IRON CONFORMING TO AWWA C110 OR COMPACT DUCTILE IRON CONFORMING TO C153 AND CEMENT MORTAR LINED TO AWWA C104, SUITABLE FOR PRESSURE RATING OF 2415 KPA.
- FATE VALVES SHALL BE CAST DUCTILE IRON BODY CONFORMING TO AWWA C500 OR DUCTILE IRON BODY CONFORMING TO AWWA C509 TO WORKING PRESSURE 1380 KPA, SOLID WEDGE RESILIENT-SEATED NON-RISING STEM. JOINT RESTRAINTS SHALL BE UNI-FLANGE OR APPROVED EQUIVALENT SUITABLE FOR DUCTILE IRON PUSH-ON PIPE JOINTS.
- A MINIMUM 3M HORIZONTAL DISTANCE SHALL BE MAINTAINED BETWEEN A WATERMAIN AND A SANITARY OR STORM SEWER. MAINTAIN A MINIMUM OF 0.5M VERTICAL CLEARANCE WHERE SEWERS CROSS WATERMAINS.
- WATERMAIN PIPE JOINTS SHALL BE WRAPPED WHERE THE SEPARATION BETWEEN A WATERMAIN AND SANITARY OR STORM SEWER IS LESS THAN 3M. THE JOINTS SHALL BE WRAPPED WITH PETROLATUM TAPE, SUCH AS DENSO TAPE, OR APPROVED EQUIVALENT. MASTIC OR COMPOUND SHALL BE APPLIED TO EACH JOIN PRIOR TO WRAPPING. THE MASTIC SHALL BE DENSO PASTE OR APPROVED EQUIVALENT.
- THE PIPE SURFACE SHALL BE CLEANED PRIOR TO APPLICATION OF THE MASTIC. THE MASTIC SHALL BE APPLIED TO ALL IRREGULAR SURFACES TO ENSURE THE SMOOTH APPLICATION OF TAPE.
- TAPE SHALL BE WRAPPED OVER THE PREPARED SURFACE IN SMOOTH EVEN SPIRALS WITH AN OVERLAP OF 50%, FOR EACH SPIRAL. TENSION APPLIED DURING THE WRAPPING MUST NOT CAUSE STRETCHING OF THE TAPE. FOLDS AND AIR POCKETS SHALL BE PRESSED OUT BY HAND.
- MATERIALS AND APPLICATION SHALL CONFORM TO AWWA C217, CURRENT VERSION.
- DEFLECTION OF PIPE JOINTS SHALL NOT EXCEED ON-HALF MAXIMUM DEFLECTION SPECIFIED IN AWWA C600 OR ONE-HALF MAXIMUM DEFLECTION RECOMMENDED BY PIPE MANUFACTURER.
- TESTING, FLUSHING AND CHLORINATION OF WATERMAINS SHALL BE IN ACCORDANCE WITH MASTER MUNICIPAL SPECIFICATIONS SECTION 33 11 01 WATERWORKS. THE CONTRACTOR IS RESPONSIBLE FOR ARRANGING FOR THE COLLECTION AND TESTING OF BACTERIOLOGICAL SAMPLES. UNIVERSITY OF BRITISH COLUMBIA OR THE CITY'S REPRESENTATIVE SHALL WITNESS THE TESTING AND COLLECTION OF THE SAMPLES. NOTIFY UNIVERSITY OF BRITISH COLUMBIA AND THE ENGINEER 48 HOURS IN ADVANCE OF TESTING. BACTERIOLOGICAL TESTING SHALL BE CONDUCTED BY A SUITABLY QUALIFIED TESTING LABORATORY. PROVIDE TEST RESULTS TO UNIVERSITY OF BRITISH COLUMBIA AND THE ENGINEER.
- THE EXISTING WATER SUPPLY SYSTEM SHALL REMAIN IN OPERATION AND MAINTAINED AT ALL TIMES DURING THE PROJECT. THE CONTRACTOR SHALL PROVIDE ANY AND ALL BYPASS PIPING AND VALVES THAT MAY BE REQUIRED DURING TIE-IN TO AND COMMISSIONING OF THE NEW PUMP STATION.
- THE NEW WATERMAINS, PUMP STATION, AND CHAMBERS MUST BE CONSTRUCTED, TESTED, COMMISSIONED AND ACCEPTED BY UNIVERSITY OF BRITISH COLUMBIA PRIOR TO CONNECTING THE EXISTING DISTRIBUTION SYSTEM TO THE NEW WORKS.
- ON BEHALF OF THE CONTRACTOR UNIVERSITY OF BRITISH COLUMBIA AND THE ENGINEER WILL PROVIDE A MINIMUM OF 48 HOURS IN ADVANCE OF CLOSING ANY VALVES, DISCONNECTING ANY PIPE OR MAKING NEW CONNECTIONS. THE CONTRACTOR SHALL PROVIDE UNIVERSITY OF BRITISH COLUMBIA AND THE ENGINEER WITH A WORK PLAN FOR TESTING AND COMMISSIONING OF THE NEW WATERMAINS AND PUMP STATION. THE PLAN SHALL DEMONSTRATE HOW THE WATER SUPPLY TO RESIDENTS WILL BE MAINTAINED AT ALL TIMES DURING THE PROJECT, INCLUDING DURING TESTING AND COMMISSIONING.

5. STORM SEWER

- ALL STORM SEWER WORKS TO BE IN ACCORDANCE WITH MASTER MUNICIPAL SPECIFICATIONS SECTION 33 40 01 STORM SEWERS AND THE RELEVANT SECTIONS OF THE BC PLUMBING CODE AND SHALL PASS THE INSPECTION OF UNIVERSITY OF BRITISH COLUMBIA PLUMBING INSPECTOR.
- UNLESS OTHERWISE NOTED MAINS SHALL BE PVC DR35 PIPE CONFORMING TO ASTM D2412 AND ASTM D3034 AND CERTIFIED TO CSA 182.2. MAINS 250MM OR GREATER MAY BE NON-REINFORCED CONCRETE CLASS 3 PIPE CONFORMING TO ASTM C14 WITH THE PIPE DESIGN FOR RUBBER GASKET JOINTS.
- MANHOLES SHALL BE IN ACCORDANCE WITH MASTER MUNICIPAL SPECIFICATIONS SECTION 33 44 01 MANHOLES AND CATCHBASINS. UNLESS OTHERWISE NOTED MANHOLES SHALL BE 1050MM DIAMETER CONFORMING TO ASTM C478 WITH FRAME AND COVER TO ASTM A48 AND SUITABLE FOR H20 LOADING.
- CATCHBASINS SHALL BE 600MM DIAMETER WITH FRAME AND GRATE SUITABLE FOR H20 LOADING AND SHALL BE IN ACCORDANCE WITH MASTER MUNICIPAL SPECIFICATIONS SECTION 33 44 01 MANHOLES AND CATCHBASINS.
- CATCH BASIN LEADS SHALL BE 150MM PVC DR28 CONFORMING TO ASTM D3034 AND CERTIFIED TO CSA 182.2.

6. ROADWORKS

- ALL ROADWORKS SHALL BE IN ACCORDANCE WITH MASTER MUNICIPAL SPECIFICATIONS SECTIONS: 31 22 16 RESHAPING GRANULAR ROADBED, 32 11 23 GRANULAR BASE, 32 11 16.1 GRANULAR SUBBASE, AND 31 22 16.1 RESHAPING EXISTING SUBGRADE.
- OBTAIN THE GEOTECHNICAL ENGINEER'S ACCEPTANCE OF EXCAVATED AND CONSTRUCTED SUBGRADES PRIOR TO PLACING ANY GRANULAR MATERIALS.
- ALL AGGREGATE MATERIALS SHALL BE IN ACCORDANCE WITH MASTER MUNICIPAL SPECIFICATIONS SECTION 31 05 17 AGGREGATES AND GRANULAR MATERIALS.
- SUBGRADE AND GRANULAR BASE MATERIALS SHALL BE COMPACTED TO 95% MODIFIED PROCTOR DENSITY OR IN ACCORDANCE WITH THE GEOTECHNICAL ENGINEER'S REQUIREMENTS.
- THE CONTRACTOR IS RESPONSIBLE FOR COMPACTION TESTING AND SHALL PROVIDE EVIDENCE THAT COMPACTION OF GRANULAR MATERIALS MEETS PROJECT SPECIFICATIONS. ALL TESTING SHALL BE CONDUCTED BY A SUITABLY QUALIFIED FIRM.
- ASPHALT PACING SHALL BE IN ACCORDANCE WITH MASTER MUNICIPAL SPECIFICATIONS SECTION 21 12 16 HOT-MIX ASPHALT CONCRETE PAVING. IF THE ASPHALT PAVING IS PLACED IN TWO LAYERS, THE MIX TYPE SHALL BE MASTER MUNICIPAL SPECIFICATIONS LOWER COURSE #2 FOR BASE COURSE AND UPPER COURSE #2 FOR SURFACE COURSE. IF THE ASPHALT PAVEMENT WILL BE PLACED IN A SINGLE LAYER THE MIX TYPE SHALL BE MASTER MUNICIPAL SPECIFICATIONS UPPER COURSE #2.
- THE CONTRACTOR SHALL PROVIDE UNIVERSITY OF BRITISH COLUMBIA AND THE ENGINEER WITH A MIX DESIGN AND TRIAL MIX TEST RESULTS FOR THE ASPHALTIC CONCRETE THE CONTRACTOR INTENDS TO PLACE A MINIMUM OF 14 DAYS PRIOR TO PAVING. THE CONTRACTOR IS RESPONSIBLE FOR ASPHALT TESTING AND SHALL PROVIDE UNIVERSITY OF BRITISH COLUMBIA AND THE ENGINEER WITH EVIDENCE THAT THE THICKNESS AND PROPERTIES OF THE FINISHED PAVING MEETS PROJECT SPECIFICATIONS AND MIX DESIGN VALUES.
- THE CONTRACTOR SHALL CONFIRM THE ADEQUACY OF THE PAVEMENT STRUCTURE INDICATED FOR PAVED AREAS AND ROADWAYS WITH THE GEOTECHNICAL ENGINEER PRIOR TO PLACING SUBBASE GRAVELS.
- ALL VALVE BOXES, MANHOLES ETC. LOCATED IN PAVED AREAS SHALL BE ADJUSTED TO FINISHED GRADE PRIOR TO PAVING.

7. EROSION AND SEDIMENT CONTROL

- THE CONTRACTOR SHALL IMPLEMENT EROSION AND SEDIMENT CONTROL MEASURES DURING CONSTRUCTION OF THE WORKS. EROSION AND SEDIMENT CONTROL SHALL BE IN ACCORDANCE WITH UNIVERSITY OF BRITISH COLUMBIA REQUIREMENTS
- THE CONTRACTOR SHALL PROVIDE UNIVERSITY OF BRITISH COLUMBIA 24 HOUR EMERGENCY CONTACT NAMES AND TELEPHONE NUMBERS PRIOR TO COMMENCING CONSTRUCTION ACTIVITIES.
- ALL WORK SHALL BE UNDERTAKEN AND COMPLETED IN SUCH A MANNER AS TO PREVENT THE RELEASE OF SEDIMENT LADEN WATER INTO ANY WATER COURSE, STORM SEWER OR DRAINAGE SYSTEM. NO SEDIMENT LADEN WATER SHALL BE PUMPED OR OTHERWISE DISCHARGED DIRECTLY TO A WATER COURSE, STORM SEWER OR DRAINAGE SYSTEM IN A MANNER THAT BYPASSES SEDIMENTATION CONTROL FACILITIES.
- THE CONTRACTOR IS RESPONSIBLE FOR INSTALLING EROSION AND SEDIMENT CONTROL PRIOR TO COMMENCING CONSTRUCTION ACTIVITIES.
- THE CONTRACTOR IS RESPONSIBLE FOR MONITORING AND MAINTAIN ALL EROSION AND SEDIMENT CONTROL WORKS IN PROPER OPERATING CONDITION.
- THE EROSION AND SEDIMENT CONTROL WORKS SHALL BE INSPECTED ON A WEEKLY BASIS. THE INSPECTIONS SHALL BE RECORDED IN A LOG BOOK. THE LOG BOOK SHALL BE MADE AVAILABLE TO UNIVERSITY OF BRITISH COLUMBIA UPON REQUEST. DURING PERIODS OF SIGNIFICANT RAINFALL, ADDITIONAL INSPECTIONS, INCLUDING ON WEEKENDS, SHALL BE PERFORMED TO ENSURE SEDIMENT CONTROL WORKS ARE FUNCTIONING PROPERLY.
- SEDIMENT REMOVED FROM THE EROSION AND SEDIMENT CONTROL WORKS SHALL BE DISPOSED OF IN A MANNER THAT PREVENTS ITS RE-ENTRY INTO THE SITE DRAINAGE SYSTEM AND/OR ANY STORM SEWER SYSTEM OF WATER COURSE.
- INSTALL SEDIMENT BARRIERS AT CATCH BASINS OR OTHER DRAINAGE FACILITIES LOCATED WITHIN THE PROJECT SITE AND OUTSIDE OF THE PROJECT SITE THAT ARE NEAR THE WORK AREA PRIOR TO COMMENCING CONSTRUCTION ACTIVITIES.
- A STABILIZED CONSTRUCTION ENTRANCE, CONSISTING OF 75MM CLEAR CRUSH ROCK UNDERLAIN BY ARMTX 250 FILTER CLOTH, OR APPROVED EQUIVALENT, SHALL BE INSTALLED AT ALL CONSTRUCTION ENTRANCES TO PREVENT VEHICLES FROM TRACKING MATERIAL OFF THE SITE. IF MATERIAL CONNECT BE REMOVED FROM VEHICLES LEAVING THE SITE, THE CONTRACTOR SHALL INSTALL A WHEEL WASH.
- ROADWAYS, WHETHER PUBLIC OR PRIVATE, USED BY CONSTRUCTION-RELATED VEHICLES AND EQUIPMENT TO ACCESS THE SITE SHALL BE SWEEP DAILY. MECHANICALLY SWEEP CLEAN ROADWAYS FOR DURATION OF THE CONSTRUCTION PROGRAM. DO NOT SWEEP OR WASH SEDIMENT INTO CATCH BASINS, MANHOLES, DITCHES OR SWALES.
- STOCKPILED MATERIAL SHALL BE COVERED WITH 6MIL POLYETHYLENE SHEETING. THE SHEETING SHALL BE SECURED IN A PLACE IN MANNER THAT PREVENTS THE STOCKPILED MATERIAL FROM BEING EXPOSED TO THE ELEMENTS.
- USE DUST CONTROL MEASURES TO REDUCE DUST GENERATED BY CONSTRUCTION ACTIVITIES. EXCAVATED AREAS SHALL BE SPRINKLED UNTIL DAMP OR AT THE DISCRETION OF THE ENGINEER. DO NOT OVER WATER AS TO CREATE RUNOFF.
- THE CONTRACTOR SHALL ENSURE THAT THE TOTAL SUSPENDED SOLIDS OF THE WATER DISCHARGING FROM THE PROJECT SITE ARE AT ALL TIMES THAN 75MG/L WITH PH BETWEEN 6 AND 9
- FAILURE TO IMPLEMENT EROSION AND SEDIMENT CONTROL OR COMPLY WITH EROSION AND SEDIMENT CONTROL REQUIREMENTS MAY RESULT IN A STOP WORK ORDER.

"BY SEALING AND SIGNING THIS DRAWING, I CERTIFY THAT THE INFORMATION CONTAINED IN THESE ACCURATELY REFLECTS THE ORIGINAL DESIGN, ADDENDA, CHANGE ORDERS AND MATERIAL DESIGN CHANGES MADE DURING CONSTRUCTION AND FIELD REVIEWED BY ME, OR MY REPRESENTATIVE, AND THAT THE AS-CONSTRUCTED WORKS SUBSTANTIALLY COMPLY WITH THE ORIGINAL DESIGN INTENT, HOWEVER, I DO NOT ACCEPT RESPONSIBILITY OF THE ACCURACY OR COMPLETENESS OF THE AS-CONSTRUCTED INFORMATION SUPPLIED BY OTHERS CONTAINED IN THESE DRAWINGS."


ISSUED FOR
CONSTRUCTION
2022-03-26



SCALE 0 1 1:100 5m			
CAD FILE NAME _Westbrook Mall Phase 4		DATE 2022-03-26	
REV	DATE	REVISIONS	SIGNATURE
1	2021-11-23	ISSUED FOR PRELIMINARY DESIGN	
2	2022-03-26	ISSUED FOR CONSTRUCTION	

SENIOR DESIGNER
DATE 2022-03-26


TEAM 11
CONSULTANTS



DESIGNED Joshua Chong	DATE 2022-03-26
QUALITY CONTROL Alvin Lok	DATE 2022-03-26
QUALITY ASSURANCE Josh Bian	DATE 2022-03-26
DRAWN Joshua Chong	DATE 2022-03-26

WESBROOK MALL REDESIGN
PHASE 4
GENERAL NOTES - CONSTRUCTION SPECIFICATIONS

FILE NUMBER	PROJECT NUMBER	REG	DRAWING NUMBER	REV
01	1228	R	-	B



"BY SEALING AND SIGNING THIS DRAWING, I CERTIFY THAT THE INFORMATION CONTAINED IN THESE ADDENDA, CHANGE ORDERS AND MATERIAL DESIGN CHANGES MADE DURING CONSTRUCTION AND FIELD REVIEWED BY ME, OR MY REPRESENTATIVE, AND THAT THE AS-CONSTRUCTED WORKS SUBSTANTIALLY COMPLY WITH THE ORIGINAL DESIGN INTENT, HOWEVER, I DO NOT ACCEPT RESPONSIBILITY OF THE ACCURACY OR COMPLETENESS OF THE AS-CONSTRUCTED INFORMATION SUPPLIED BY OTHERS CONTAINED IN THESE DRAWINGS."

ISSUED FOR CONSTRUCTION

2022-03-26

SCALE 0 2 1:200 10m

CAD FILENAME _Westbrook Mall Phase 4

DATE 2022-03-26

REV	DATE	REVISIONS	SIGNATURE
1	2021-11-23	ISSUED FOR PRELIMINARY DESIGN	
2	2022-03-26	ISSUED FOR CONSTRUCTION	

SENIOR DESIGNER

DATE 2022-03-26

TEAM 11 CONSULTANTS

DESIGNED Joshua Chong DATE 2022-03-26

QUALITY CONTROL Alvin Lok DATE 2022-03-26


QUALITY ASSURANCE Josh Bian DATE 2022-03-26

DRAWN Joshua Chong DATE 2022-03-26

WESBROOK MALL REDESIGN PHASE 4

Westbrook Mall Plan

FILE NUMBER	PROJECT NUMBER	REG	DRAWING NUMBER	REV
01	1228	R	1	B



"BY SEALING AND SIGNING THIS DRAWING, I CERTIFY THAT THE INFORMATION CONTAINED IN THESE ACCURATELY REFLECTS THE ORIGINAL DESIGN, ADDENDA, CHANGE ORDERS AND MATERIAL DESIGN CHANGES MADE DURING CONSTRUCTION AND FIELD REVIEWED BY ME, OR MY REPRESENTATIVE, AND THAT THE AS-CONSTRUCTED WORKS SUBSTANTIALLY COMPLY WITH THE ORIGINAL DESIGN INTENT, HOWEVER, I DO NOT ACCEPT RESPONSIBILITY OF THE ACCURACY OR COMPLETENESS OF THE AS-CONSTRUCTED INFORMATION SUPPLIED BY OTHERS CONTAINED IN THESE DRAWINGS."

ISSUED FOR CONSTRUCTION
2022-03-26



SCALE		0 2 1:200 10m		CAD FILENAME _Westbrook Mall Phase 4	
				DATE 2022-03-26	
REV	DATE	REVISIONS		SIGNATURE	
1	2021-11-23	ISSUED FOR PRELIMINARY DESIGN			
2	2022-03-26	ISSUED FOR CONSTRUCTION			

TEAM 11 CONSULTANTS

DESIGNED Joshua Chong DATE 2022-03-26

QUALITY CONTROL Alvin Lok DATE 2022-03-26

QUALITY ASSURANCE Josh Bian DATE 2022-03-26


DRAWN Joshua Chong DATE 2022-03-26

SENIOR DESIGNER

DATE 2022-03-26

WESBROOK MALL REDESIGN PHASE 4
Westbrook Mall Plan

FILE NUMBER	PROJECT NUMBER	REG	DRAWING NUMBER	REV
01	1228	R	2	B



"BY SEALING AND SIGNING THIS DRAWING, I CERTIFY THAT THE INFORMATION CONTAINED IN THESE ADDENDA, CHANGE ORDERS AND MATERIAL DESIGN CHANGES MADE DURING CONSTRUCTION AND FIELD REVIEWED BY ME, OR MY REPRESENTATIVE, AND THAT THE AS-CONSTRUCTED WORKS SUBSTANTIALLY COMPLY WITH THE ORIGINAL DESIGN INTENT, HOWEVER, I DO NOT ACCEPT RESPONSIBILITY OF THE ACCURACY OR COMPLETENESS OF THE AS-CONSTRUCTED INFORMATION SUPPLIED BY OTHERS CONTAINED IN THESE DRAWINGS."

ISSUED FOR CONSTRUCTION
2022-03-26

SCALE 0 2 1:200 10m

CAD FILENAME Westbrook Mall Phase 4
DATE 2022-03-26

REV	DATE	REVISIONS	SIGNATURE
1	2021-11-23	ISSUED FOR PRELIMINARY DESIGN	
2	2022-03-26	ISSUED FOR CONSTRUCTION	


SENIOR DESIGNER
DATE 2022-03-26

TEAM 11 CONSULTANTS

DESIGNED Joshua Chong DATE 2022-03-26
QUALITY CONTROL Alvin Lok DATE 2022-03-26
QUALITY ASSURANCE Josh Bian DATE 2022-03-26
DRAWN Joshua Chong DATE 2022-03-26

WESBROOK MALL REDESIGN PHASE 4
Westbrook Mall Plan

FILE NUMBER	PROJECT NUMBER	REG	DRAWING NUMBER	REV
01	1228	R	3	B



"BY SEALING AND SIGNING THIS DRAWING, I CERTIFY THAT THE INFORMATION CONTAINED IN THESE ADDENDA, CHANGE ORDERS AND MATERIAL DESIGN CHANGES MADE DURING CONSTRUCTION AND FIELD REVIEWED BY ME, OR MY REPRESENTATIVE, AND THAT THE AS-CONSTRUCTED WORKS SUBSTANTIALLY COMPLY WITH THE ORIGINAL DESIGN INTENT, HOWEVER, I DO NOT ACCEPT RESPONSIBILITY OF THE ACCURACY OR COMPLETENESS OF THE AS-CONSTRUCTED INFORMATION SUPPLIED BY OTHERS CONTAINED IN THESE DRAWINGS."

ISSUED FOR CONSTRUCTION
2022-03-26

ubc sustainability

SCALE 0 2 1:200 10m

REV	DATE	REVISIONS	SIGNATURE
1	2021-11-23	ISSUED FOR PRELIMINARY DESIGN	
2	2022-03-26	ISSUED FOR CONSTRUCTION	

CAD FILENAME Wesbrook Mall Phase 4
DATE 2022-03-26


TEAM 11 CONSULTANTS

DESIGNED Joshua Chong DATE 2022-03-26
QUALITY CONTROL Alvin Lok DATE 2022-03-26
QUALITY ASSURANCE Josh Bian DATE 2022-03-26
DRAWN Joshua Chong DATE 2022-03-26

SENIOR DESIGNER _____
DATE 2022-03-26

WESBROOK MALL REDESIGN PHASE 4
Wesbrook Mall Plan

FILE NUMBER	PROJECT NUMBER	REG	DRAWING NUMBER	REV
01	1228	R	4	B



"BY SEALING AND SIGNING THIS DRAWING, I CERTIFY THAT THE INFORMATION CONTAINED IN THESE ADDENDA, CHANGE ORDERS AND MATERIAL DESIGN CHANGES MADE DURING CONSTRUCTION AND FIELD REVIEWED BY ME, OR MY REPRESENTATIVE, AND THAT THE AS-CONSTRUCTED WORKS SUBSTANTIALLY COMPLY WITH THE ORIGINAL DESIGN INTENT, HOWEVER, I DO NOT ACCEPT RESPONSIBILITY OF THE ACCURACY OR COMPLETENESS OF THE AS-CONSTRUCTED INFORMATION SUPPLIED BY OTHERS CONTAINED IN THESE DRAWINGS."

ISSUED FOR CONSTRUCTION
2022-03-26





SCALE		0 2 1:200 10m		CAD FILENAME _Westbrook Mall Phase 4	
				DATE 2022-03-26	
REV	DATE	REVISIONS		SIGNATURE	
1	2021-11-23	ISSUED FOR PRELIMINARY DESIGN			
2	2022-03-26	ISSUED FOR CONSTRUCTION			

TEAM 11
CONSULTANTS

DESIGNED Joshua Chong	DATE 2022-03-26
QUALITY CONTROL Alvin Lok	DATE 2022-03-26
QUALITY ASSURANCE Josh Bian	DATE 2022-03-26
DRAWN Joshua Chong	DATE 2022-03-26

WESBROOK MALL REDESIGN PHASE 4 Westbrook Mall Plan		FILE NUMBER	PROJECT NUMBER	REG	DRAWING NUMBER	REV
		01	1228	R	5	B



"BY SEALING AND SIGNING THIS DRAWING, I CERTIFY THAT THE INFORMATION CONTAINED IN THESE DRAWINGS ACCURATELY REFLECTS THE ORIGINAL DESIGN, ADDENDA, CHANGE ORDERS AND MATERIAL DESIGN CHANGES MADE DURING CONSTRUCTION AND FIELD REVIEWED BY ME, OR MY REPRESENTATIVE, AND THAT THE AS-CONSTRUCTED WORKS SUBSTANTIALLY COMPLY WITH THE ORIGINAL DESIGN INTENT, HOWEVER, I DO NOT ACCEPT RESPONSIBILITY OF THE ACCURACY OR COMPLETENESS OF THE AS-CONSTRUCTED INFORMATION SUPPLIED BY OTHERS CONTAINED IN THESE DRAWINGS."

**ISSUED FOR
PRELIMINARY DESIGN**
2022-03-26





SCALE		0 1 1:100 5m		CAD FILENAME _Wesbrook Mall Phase 4	
REV		DATE		DATE	
1	2021-11-23	ISSUED FOR PRELIMINARY DESIGN		2022-03-26	
2	2022-03-26	ISSUED FOR CONSTRUCTION			

**TEAM 11
CONSULTANTS**

SENIOR DESIGNER _____
DATE 2022-03-26

DESIGNED Simar Sidhu DATE 2022-03-26
QUALITY CONTROL George Gu DATE 2022-03-26
QUALITY ASSURANCE Josh Bian DATE 2022-03-26
DRAWN Simar Sidhu DATE 2022-03-26

WESBROOK MALL REDESIGN PHASE 4 Wesbrook Mall Plan			
FILE NUMBER	PROJECT NUMBER	REG	DRAWING NUMBER
01	1228	R	6
			REV
			B




"BY SEALING AND SIGNING THIS DRAWING, I CERTIFY THAT THE INFORMATION CONTAINED IN THESE ACCURATELY REFLECTS THE ORIGINAL DESIGN, ADDENDA, CHANGE ORDERS AND MATERIAL DESIGN CHANGES MADE DURING CONSTRUCTION AND FIELD REVIEWED BY ME, OR MY REPRESENTATIVE, AND THAT THE AS-CONSTRUCTED WORKS SUBSTANTIALLY COMPLY WITH THE ORIGINAL DESIGN INTENT, HOWEVER, I DO NOT ACCEPT RESPONSIBILITY OF THE ACCURACY OR COMPLETENESS OF THE AS-CONSTRUCTED INFORMATION SUPPLIED BY OTHERS CONTAINED IN THESE DRAWINGS."

ISSUED FOR
PRELIMINARY DESIGN
2022-03-26



SCALE		0 1 1:100 5m		CAD FILENAME: Wesbrook Mall Phase 4	
				DATE: 2022-03-26	
REV	DATE	REVISIONS		SIGNATURE	
1	2021-11-23	ISSUED FOR PRELIMINARY DESIGN			
2	2022-03-26	ISSUED FOR CONSTRUCTION			

TEAM 11
CONSULTANTS





SENIOR DESIGNER
DATE: 2022-03-26

DESIGNED	Simar Sidhu	DATE	2022-03-26
QUALITY CONTROL	George Gu	DATE	2022-03-26
QUALITY ASSURANCE	Josh Bian	DATE	2022-03-26
DRAWN	Simar Sidhu	DATE	2022-03-26

WESBROOK MALL REDESIGN
PHASE 4
Wesbrook Mall Plan

FILE NUMBER	PROJECT NUMBER	REG	DRAWING NUMBER	REV
01	1228	R	7	B




"BY SEALING AND SIGNING THIS DRAWING, I CERTIFY THAT THE INFORMATION CONTAINED IN THESE ACCURATELY REFLECTS THE ORIGINAL DESIGN, ADDENDA, CHANGE ORDERS AND MATERIAL DESIGN CHANGES MADE DURING CONSTRUCTION AND FIELD REVIEWED BY ME, OR MY REPRESENTATIVE, AND THAT THE AS-CONSTRUCTED WORKS SUBSTANTIALLY COMPLY WITH THE ORIGINAL DESIGN INTENT, HOWEVER, I DO NOT ACCEPT RESPONSIBILITY OF THE ACCURACY OR COMPLETENESS OF THE AS-CONSTRUCTED INFORMATION SUPPLIED BY OTHERS CONTAINED IN THESE DRAWINGS."

ISSUED FOR
PRELIMINARY DESIGN
2022-03-26



SCALE		0 1 1:100 5m		CAD FILENAME _Wesbrook Mall Phase 4	
				DATE 2022-03-26	
REV	DATE	REVISIONS		SIGNATURE	
1	2021-11-23	ISSUED FOR PRELIMINARY DESIGN			
2	2022-03-26	ISSUED FOR CONSTRUCTION			

TEAM 11
CONSULTANTS





DESIGNED	Simar Sidhu	DATE	2022-03-26
QUALITY CONTROL	George Gu	DATE	2022-03-26
QUALITY ASSURANCE	Josh Bian	DATE	2022-03-26
DRAWN	Simar Sidhu	DATE	2022-03-26

SENIOR DESIGNER
DATE 2022-03-26

WESBROOK MALL REDESIGN
PHASE 4
Wesbrook Mall Plan

FILE NUMBER	PROJECT NUMBER	REG	DRAWING NUMBER	REV
01	1228	R	8	B



"BY SEALING AND SIGNING THIS DRAWING, I CERTIFY THAT THE INFORMATION CONTAINED IN THESE ACCURATELY REFLECTS THE ORIGINAL DESIGN, ADDENDA, CHANGE ORDERS AND MATERIAL DESIGN CHANGES MADE DURING CONSTRUCTION AND FIELD REVIEWED BY ME, OR MY REPRESENTATIVE, AND THAT THE AS-CONSTRUCTED WORKS SUBSTANTIALLY COMPLY WITH THE ORIGINAL DESIGN INTENT. HOWEVER, I DO NOT ACCEPT RESPONSIBILITY OF THE ACCURACY OR COMPLETENESS OF THE AS-CONSTRUCTED INFORMATION SUPPLIED BY OTHERS CONTAINED IN THESE DRAWINGS."

ISSUED FOR
PRELIMINARY DESIGN
2022-03-26




SCALE		0 1 1:100 5m		CAD FILENAME _Wesbrook Mall Phase 4	
				DATE 2022-03-26	
REV	DATE	REVISIONS		SIGNATURE	
1	2021-11-23	ISSUED FOR PRELIMINARY DESIGN			
2	2022-03-26	ISSUED FOR CONSTRUCTION			

DESIGNED Simar Sidhu DATE 2022-03-26
QUALITY CONTROL George Gu DATE 2022-03-26
QUALITY ASSURANCE Josh Bian DATE 2022-03-26
DRAWN Simar Sidhu DATE 2022-03-26

SENIOR DESIGNER _____
DATE 2022-03-26

WESBROOK MALL REDESIGN PHASE 4 Wesbrook Mall Plan				
FILE NUMBER	PROJECT NUMBER	REG	DRAWING NUMBER	REV
01	1228	R	9	B



"BY SEALING AND SIGNING THIS DRAWING, I CERTIFY THAT THE INFORMATION CONTAINED IN THESE ACCURATELY REFLECTS THE ORIGINAL DESIGN. ADDENDUM: CHANGE ORDERS AND MATERIAL DESIGN CHANGES MADE DURING CONSTRUCTION AND FIELD REVIEWED BY ME, OR MY REPRESENTATIVE, AND THAT THE AS-CONSTRUCTED WORKS SUBSTANTIALLY COMPLY WITH THE ORIGINAL DESIGN INTENT, HOWEVER, I DO NOT ACCEPT RESPONSIBILITY OF THE ACCURACY OR COMPLETENESS OF THE AS-CONSTRUCTED INFORMATION SUPPLIED BY OTHERS CONTAINED IN THESE DRAWINGS."

ISSUED FOR CONSTRUCTION
2022-03-26




SCALE		0 2 1:200 10m	CAD FILENAME	Westbrook Mall Phase 4
			DATE	2022-03-26
REV	DATE	REVISIONS	SIGNATURE	
1	2021-11-23	ISSUED FOR PRELIMINARY DESIGN		
2	2022-03-26	ISSUED FOR CONSTRUCTION		

TEAM 11 CONSULTANTS

SENIOR DESIGNER _____
DATE 2022-03-26

DESIGNED	Simar Sidhu	DATE	2022-03-26
QUALITY CONTROL	Alvin Lok	DATE	2022-03-26
QUALITY ASSURANCE	Josh Bian	DATE	2022-03-26
DRAWN	Simar Sidhu	DATE	2022-03-26

WESBROOK MALL REDESIGN PHASE 4 Westbrook Mall Plan				
FILE NUMBER	PROJECT NUMBER	REG	DRAWING NUMBER	REV
01	1228	R	10	B



"BY SEALING AND SIGNING THIS DRAWING, I CERTIFY THAT THE INFORMATION CONTAINED IN THESE ACCURATELY REFLECTS THE ORIGINAL DESIGN. ADDENDA, CHANGE ORDERS AND MATERIAL DESIGN CHANGES MADE DURING CONSTRUCTION AND FIELD REVIEWED BY ME, OR MY REPRESENTATIVE, AND THAT THE AS-CONSTRUCTED WORKS SUBSTANTIALLY COMPLY WITH THE ORIGINAL DESIGN INTENT, HOWEVER, I DO NOT ACCEPT RESPONSIBILITY OF THE ACCURACY OR COMPLETENESS OF THE AS-CONSTRUCTED INFORMATION SUPPLIED BY OTHERS CONTAINED IN THESE DRAWINGS."

ISSUED FOR CONSTRUCTION
2022-03-26




SCALE		0 2 1:200 10m		CAD FILENAME: Westbrook Mall Phase 4		DATE: 2022-03-26	
REV	DATE	REVISIONS		SIGNATURE			
1	2021-11-23	ISSUED FOR PRELIMINARY DESIGN					
2	2022-03-26	ISSUED FOR CONSTRUCTION					

TEAM 11 CONSULTANTS

SENIOR DESIGNER _____
DATE: 2022-03-26

DESIGNED	Simar Sidhu	DATE	2022-03-26
QUALITY CONTROL	Alvin Lok	DATE	2022-03-26
QUALITY ASSURANCE	Josh Bian	DATE	2022-03-26
DRAWN	Simar Sidhu	DATE	2022-03-26

WESBROOK MALL REDESIGN PHASE 4 Westbrook Mall Plan					
FILE NUMBER	PROJECT NUMBER	REG	DRAWING NUMBER	REV	
01	1228	R	11	B	



"BY SEALING AND SIGNING THIS DRAWING, I CERTIFY THAT THE INFORMATION CONTAINED IN THESE DRAWINGS ACCURATELY REFLECTS THE ORIGINAL DESIGN. ADDENDUM, CHANGE ORDERS AND MATERIAL DESIGN CHANGES MADE DURING CONSTRUCTION AND FIELD REVIEWED BY ME, OR MY REPRESENTATIVE, AND THAT THE AS-CONSTRUCTED WORKS SUBSTANTIALLY COMPLY WITH THE ORIGINAL DESIGN INTENT, HOWEVER, I DO NOT ACCEPT RESPONSIBILITY OF THE ACCURACY OR COMPLETENESS OF THE AS-CONSTRUCTED INFORMATION SUPPLIED BY OTHERS CONTAINED IN THESE DRAWINGS."

ISSUED FOR CONSTRUCTION
2022-03-26



SCALE		0 2 1:200 10m		CAD FILENAME <u>Westbrook Mall Phase 4</u>	
				DATE <u>2022-03-26</u>	
REV	DATE	REVISIONS		SIGNATURE	
1	2021-11-23	ISSUED FOR PRELIMINARY DESIGN			
2	2022-03-26	ISSUED FOR CONSTRUCTION			

TEAM 11 CONSULTANTS

SENIOR DESIGNER _____
DATE 2022-03-26

DESIGNED	<u>Simar Sidhu</u>	DATE	<u>2022-03-26</u>
QUALITY CONTROL	<u>Alvin Lok</u>	DATE	<u>2022-03-26</u>
QUALITY ASSURANCE	<u>Josh Bian</u>	DATE	<u>2022-03-26</u>
DRAWN	<u>Simar Sidhu</u>	DATE	<u>2022-03-26</u>

WESTBROOK MALL REDESIGN PHASE 4 Westbrook Mall Plan				
FILE NUMBER	PROJECT NUMBER	REG	DRAWING NUMBER	REV
01	1228	R	12	B



"BY SEALING AND SIGNING THIS DRAWING, I CERTIFY THAT THE INFORMATION CONTAINED IN THESE ACCURATELY REFLECTS THE ORIGINAL DESIGN. ADDENDA, CHANGE ORDERS AND MATERIAL DESIGN CHANGES MADE DURING CONSTRUCTION AND FIELD REVIEWED BY ME, OR MY REPRESENTATIVE, AND THAT THE AS-CONSTRUCTED WORKS SUBSTANTIALLY COMPLY WITH THE ORIGINAL DESIGN INTENT, HOWEVER, I DO NOT ACCEPT RESPONSIBILITY OF THE ACCURACY OR COMPLETENESS OF THE AS-CONSTRUCTED INFORMATION SUPPLIED BY OTHERS CONTAINED IN THESE DRAWINGS."

ISSUED FOR CONSTRUCTION
2022-03-26




SCALE		0 2 1:200 10m	CAD FILENAME <u>Westbrook Mall Phase 4</u>	
			DATE <u>2022-03-26</u>	
REV	DATE	REVISIONS	SIGNATURE	
1	2021-11-23	ISSUED FOR PRELIMINARY DESIGN		
2	2022-03-26	ISSUED FOR CONSTRUCTION		

TEAM 11 CONSULTANTS

SENIOR DESIGNER _____
DATE 2022-03-26

DESIGNED	<u>Simar Sidhu</u>	DATE	<u>2022-03-26</u>
QUALITY CONTROL	<u>Alvin Lok</u>	DATE	<u>2022-03-26</u>
QUALITY ASSURANCE	<u>Josh Bian</u>	DATE	<u>2022-03-26</u>
DRAWN	<u>Simar Sidhu</u>	DATE	<u>2022-03-26</u>

WESBROOK MALL REDESIGN PHASE 4 Westbrook Mall Plan				
FILE NUMBER	PROJECT NUMBER	REG	DRAWING NUMBER	REV
01	1228	R	14	B



"BY SEALING AND SIGNING THIS DRAWING, I CERTIFY THAT THE INFORMATION CONTAINED IN THESE ADDENDA, CHANGE ORDERS AND MATERIAL DESIGN CHANGES MADE DURING CONSTRUCTION AND FIELD REVIEWED BY ME, OR MY REPRESENTATIVE, AND THAT THE AS-CONSTRUCTED WORKS SUBSTANTIALLY COMPLY WITH THE ORIGINAL DESIGN INTENT, HOWEVER, I DO NOT ACCEPT RESPONSIBILITY OF THE ACCURACY OR COMPLETENESS OF THE AS-CONSTRUCTED INFORMATION SUPPLIED BY OTHERS CONTAINED IN THESE DRAWINGS."

ISSUED FOR CONSTRUCTION
2022-03-26




SCALE 0 2 1:200 10m		CAD FILENAME _Westbrook Mall Phase 4	
		DATE 2022-03-26	
REV	DATE	REVISIONS	SIGNATURE

TEAM 11 CONSULTANTS

DESIGNED Joshua Chong	DATE 2022-03-26
QUALITY CONTROL Alvin Lok	DATE 2022-03-26
QUALITY ASSURANCE Josh Bian	DATE 2022-03-26
DRAWN Joshua Chong	DATE 2022-03-26

WESBROOK MALL REDESIGN PHASE 4 Westbrook Mall Signage Plan		FILE NUMBER	PROJECT NUMBER	REG	DRAWING NUMBER	REV
		01	1228	R	15	B



"BY SEALING AND SIGNING THIS DRAWING, I CERTIFY THAT THE INFORMATION CONTAINED IN THESE ADDENDA, CHANGE ORDERS AND MATERIAL DESIGN CHANGES MADE DURING CONSTRUCTION AND FIELD REVIEWED BY ME, OR MY REPRESENTATIVE, AND THAT THE AS-CONSTRUCTED WORKS SUBSTANTIALLY COMPLY WITH THE ORIGINAL DESIGN INTENT, HOWEVER, I DO NOT ACCEPT RESPONSIBILITY OF THE ACCURACY OR COMPLETENESS OF THE AS-CONSTRUCTED INFORMATION SUPPLIED BY OTHERS CONTAINED IN THESE DRAWINGS."

ISSUED FOR CONSTRUCTION
2022-03-26



SCALE 0 2 1:200 10m		CAD FILENAME _Westbrook Mall Phase 4	
		DATE 2022-03-26	
REV	DATE	REVISIONS	SIGNATURE


TEAM 11
CONSULTANTS

DESIGNED	Joshua Chong	DATE	2022-03-26
QUALITY CONTROL	Alvin Lok	DATE	2022-03-26
QUALITY ASSURANCE	Josh Bian	DATE	2022-03-26
DRAWN	Joshua Chong	DATE	2022-03-26

SENIOR DESIGNER

DATE 2022-03-26

WESBROOK MALL REDESIGN PHASE 4 Westbrook Mall Signage Plan			
FILE NUMBER	PROJECT NUMBER	REG	DRAWING NUMBER
01	1228	R	16
			REV
			B



"BY SEALING AND SIGNING THIS DRAWING, I CERTIFY THAT THE INFORMATION CONTAINED IN THESE ADDENDA, CHANGE ORDERS AND MATERIAL DESIGN CHANGES MADE DURING CONSTRUCTION AND FIELD REVIEWED BY ME, OR MY REPRESENTATIVE, AND THAT THE AS-CONSTRUCTED WORKS SUBSTANTIALLY COMPLY WITH THE ORIGINAL DESIGN INTENT, HOWEVER, I DO NOT ACCEPT RESPONSIBILITY OF THE ACCURACY OR COMPLETENESS OF THE AS-CONSTRUCTED INFORMATION SUPPLIED BY OTHERS CONTAINED IN THESE DRAWINGS."

ISSUED FOR CONSTRUCTION
2022-03-26



SCALE 0 2 1:200 10m		CAD FILENAME _Westbrook Mall Phase 4	
		DATE 2022-03-26	
REV	DATE	REVISIONS	SIGNATURE


TEAM 11
CONSULTANTS

DESIGNED	Joshua Chong	DATE	2022-03-26
QUALITY CONTROL	Alvin Lok	DATE	2022-03-26
QUALITY ASSURANCE	Josh Bian	DATE	2022-03-26
DRAWN	Joshua Chong	DATE	2022-03-26

SENIOR DESIGNER

DATE 2022-03-26

WESBROOK MALL REDESIGN PHASE 4 Westbrook Mall Signage Plan			
FILE NUMBER	PROJECT NUMBER	REG	DRAWING NUMBER
01	1228	R	17
			REV B



"BY SEALING AND SIGNING THIS DRAWING, I CERTIFY THAT THE INFORMATION CONTAINED IN THESE ACCURATELY REFLECTS THE ORIGINAL DESIGN, ADDENDA, CHANGE ORDERS AND MATERIAL DESIGN CHANGES MADE DURING CONSTRUCTION AND FIELD REVIEWED BY ME, OR MY REPRESENTATIVE, AND THAT THE AS-CONSTRUCTED WORKS SUBSTANTIALLY COMPLY WITH THE ORIGINAL DESIGN INTENT, HOWEVER, I DO NOT ACCEPT RESPONSIBILITY OF THE ACCURACY OR COMPLETENESS OF THE AS-CONSTRUCTED INFORMATION SUPPLIED BY OTHERS CONTAINED IN THESE DRAWINGS."

ISSUED FOR CONSTRUCTION
2022-03-26

SCALE 0 2 1:200 10m

REV	DATE	REVISIONS	SIGNATURE

CAD FILENAME Wesbrook Mall Phase 4
DATE 2022-03-26


TEAM 11 CONSULTANTS

DESIGNED	Joshua Chong	DATE	2022-03-26
QUALITY CONTROL	Alvin Lok	DATE	2022-03-26
QUALITY ASSURANCE	Josh Bian	DATE	2022-03-26
DRAWN	Joshua Chong	DATE	2022-03-26

SENIOR DESIGNER _____
DATE 2022-03-26

WESBROOK MALL REDESIGN PHASE 4
Wesbrook Mall Signage Plan

FILE NUMBER	PROJECT NUMBER	REG	DRAWING NUMBER	REV
01	1228	R	18	B



"BY SEALING AND SIGNING THIS DRAWING, I CERTIFY THAT THE INFORMATION CONTAINED IN THESE ADDENDA, CHANGE ORDERS AND MATERIAL DESIGN CHANGES MADE DURING CONSTRUCTION AND FIELD REVIEWED BY ME, OR MY REPRESENTATIVE, AND THAT THE AS-CONSTRUCTED WORKS SUBSTANTIALLY COMPLY WITH THE ORIGINAL DESIGN INTENT, HOWEVER, I DO NOT ACCEPT RESPONSIBILITY OF THE ACCURACY OR COMPLETENESS OF THE AS-CONSTRUCTED INFORMATION SUPPLIED BY OTHERS CONTAINED IN THESE DRAWINGS."

ISSUED FOR CONSTRUCTION
2022-03-26

SCALE 0 2 1:200 10m

CAD FILENAME Westbrook Mall Phase 4
DATE 2022-03-26

REV	DATE	REVISIONS	SIGNATURE









SENIOR DESIGNER _____
DATE 2022-03-26

TEAM 11 CONSULTANTS

DESIGNED	Joshua Chong	DATE	2022-03-26
QUALITY CONTROL	Alvin Lok	DATE	2022-03-26
QUALITY ASSURANCE	Josh Bian	DATE	2022-03-26
DRAWN	Joshua Chong	DATE	2022-03-26

**WESBROOK MALL REDESIGN
PHASE 4**
Westbrook Mall Signage Plan

FILE NUMBER	PROJECT NUMBER	REG	DRAWING NUMBER	REV
01	1228	R	19	B



"BY SEALING AND SIGNING THIS DRAWING, I CERTIFY THAT THE INFORMATION CONTAINED IN THESE ACCURATELY REFLECTS THE ORIGINAL DESIGN, ADDENDA, CHANGE ORDERS AND MATERIAL DESIGN CHANGES MADE DURING CONSTRUCTION AND FIELD REVIEWED BY ME, OR MY REPRESENTATIVE, AND THAT THE AS-CONSTRUCTED WORKS SUBSTANTIALLY COMPLY WITH THE ORIGINAL DESIGN INTENT, HOWEVER, I DO NOT ACCEPT RESPONSIBILITY OF THE ACCURACY OR COMPLETENESS OF THE AS-CONSTRUCTED INFORMATION SUPPLIED BY OTHERS CONTAINED IN THESE DRAWINGS."

ISSUED FOR
CONSTRUCTION
2022-03-26

ubc sustainability

SCALE 0 2 1:200 10m


REV	DATE	REVISIONS	SIGNATURE

CAD FILENAME Wesbrook Mall Phase 4

DATE 2022-03-26









TEAM 11
CONSULTANTS

DESIGNED	Joshua Chong	DATE	2022-03-26
QUALITY CONTROL	Alvin Lok	DATE	2022-03-26
QUALITY ASSURANCE	Josh Bian	DATE	2022-03-26
DRAWN	Joshua Chong	DATE	2022-03-26



WESBROOK MALL REDESIGN
PHASE 4
Standard Detail Geometric Drawings

FILE NUMBER	PROJECT NUMBER	REG	DRAWING NUMBER	REV
01	1228	R	20	B



"BY SEALING AND SIGNING THIS DRAWING, I CERTIFY THAT THE INFORMATION CONTAINED IN THESE ACCURATELY REFLECTS THE ORIGINAL DESIGN, ADDENDA, CHANGE ORDERS AND MATERIAL DESIGN CHANGES MADE DURING CONSTRUCTION AND FIELD REVIEWED BY ME, OR MY REPRESENTATIVE, AND THAT THE AS-CONSTRUCTED WORKS SUBSTANTIALLY COMPLY WITH THE ORIGINAL DESIGN INTENT, HOWEVER, I DO NOT ACCEPT RESPONSIBILITY OF THE ACCURACY OR COMPLETENESS OF THE AS-CONSTRUCTED INFORMATION SUPPLIED BY OTHERS CONTAINED IN THESE DRAWINGS."

ISSUED FOR
CONSTRUCTION
2022-03-26

ubc sustainability

SCALE 0 2 1:200 10m


REV	DATE	REVISIONS	SIGNATURE

CAD FILE NAME: Wesbrook Mall Phase 4
DATE: 2022-03-26

SENIOR DESIGNER
DATE: 2022-03-26





TEAM 11
CONSULTANTS

DESIGNED	Joshua Chong	DATE	2022-03-26
QUALITY CONTROL	Alvin Lok	DATE	2022-03-26
QUALITY ASSURANCE	Josh Bian	DATE	2022-03-26
DRAWN	Joshua Chong	DATE	2022-03-26



WESBROOK MALL REDESIGN
PHASE 4
Standard Detail Geometric Drawings


FILE NUMBER	PROJECT NUMBER	REG	DRAWING NUMBER	REV
01	1228	R	22	B




DETAIL-A
N.T.S

NOTES:
- ALL UNITS IN METERS (M) UNLESS OTHERWISE SPECIFIED
- DIMENSIONS ARE SUBJECT TO CHANGE IN DETAILED DESIGN PHASE
- DRAINAGE PIPES TO BE SIZED AFTER DETAILED ANALYSES


SECTION C-C




ELEVATION VIEW



ELEVATION VIEW



PLAN VIEW



PLAN VIEW

NOTES:
- ALL UNITS IN METERS (M) UNLESS OTHERWISE SPECIFIED
- DIMENSIONS ARE SUBJECT TO CHANGE IN DETAILED DESIGN PHASE
- ALL PUMPS, FILTERS, PIPES, AND VAULT SIZES TO BE RE-SIZED DURING FROM DETAILED ANALYSES

"BY SEALING AND SIGNING THIS DRAWING, I CERTIFY THAT THE INFORMATION CONTAINED IN THESE ACCURATELY REFLECTS THE ORIGINAL DESIGN, ADDENDA, CHANGE ORDERS AND MATERIAL DESIGN CHANGES MADE DURING CONSTRUCTION AND FIELD REVIEWED BY ME, OR MY REPRESENTATIVE, AND THAT THE AS-CONSTRUCTED WORKS SUBSTANTIALLY COMPLY WITH THE ORIGINAL DESIGN INTENT, HOWEVER, I DO NOT ACCEPT RESPONSIBILITY OF THE ACCURACY OR COMPLETENESS OF THE AS-CONSTRUCTED INFORMATION SUPPLIED BY OTHERS CONTAINED IN THESE DRAWINGS."

ISSUED FOR
CONSTRUCTION
2022-04-01

SCALE 1:05

CAD FILENAME Westbrook Mall Phase 4
DATE 2021-11-30

REV	DATE	REVISIONS	SIGNATURE

MINISTRY OF TRANSPORTATION
AND INFRASTRUCTURE







REGION NAME
BRANCH

SENIOR DESIGNER
DATE 2021-11-30

DESIGNED Josh Bian DATE 2021-11-30
QUALITY CONTROL George Gu DATE 2021-11-30
QUALITY ASSURANCE George Gu DATE 2021-11-30
DRAWN Josh Bian DATE 2021-11-30





WESBROOK MALL REDESIGN
PHASE 4
Pedestrian Underpass Details

FILE NUMBER	PROJECT NUMBER	REG	DRAWING NUMBER	REV
01	1228	R	26	A



NOTES:
- ALL UNITS IN METERS (M) UNLESS OTHERWISE SPECIFIED
- DIMENSIONS ARE SUBJECT TO CHANGE IN DETAILED DESIGN PHASE

"BY SEALING AND SIGNING THIS DRAWING, I CERTIFY THAT THE INFORMATION CONTAINED IN THESE ACCURATELY REFLECTS THE ORIGINAL DESIGN, ADDENDA, CHANGE ORDERS AND MATERIAL DESIGN CHANGES MADE DURING CONSTRUCTION AND FIELD REVIEWED BY ME, OR MY REPRESENTATIVE, AND THAT THE AS-CONSTRUCTED WORKS SUBSTANTIALLY COMPLY WITH THE ORIGINAL DESIGN INTENT, HOWEVER, I DO NOT ACCEPT RESPONSIBILITY OF THE ACCURACY OR COMPLETENESS OF THE AS-CONSTRUCTED INFORMATION SUPPLIED BY OTHERS CONTAINED IN THESE DRAWINGS."	ISSUED FOR CONSTRUCTION 2022-04-01	SCALE 1:75		CAD FILENAME <u>Westbrook Mall Phase 4</u> DATE <u>2021-11-30</u>		MINISTRY OF TRANSPORTATION AND INFRASTRUCTURE REGION NAME BRANCH		WESBROOK MALL REDESIGN PHASE 4 Pedestrian Underpass Details						
		REV	DATE	REVISIONS	SIGNATURE									
							SENIOR DESIGNER _____ DATE 2021-11-30		DESIGNED <u>Josh Bian</u> DATE <u>2021-11-30</u> QUALITY CONTROL <u>George Gu</u> DATE <u>2021-11-30</u> QUALITY ASSURANCE <u>George Gu</u> DATE <u>2021-11-30</u> DRAWN <u>Josh Bian</u> DATE <u>2021-11-30</u>	FILE NUMBER 01	PROJECT NUMBER 1228	REG R	DRAWING NUMBER 27	REV A



SOUTHBOUND ENTRANCE STAIRS

NORTHBOUND ENTRANCE STAIRS

NOTES:
- ALL UNITS IN METERS (M) UNLESS OTHERWISE SPECIFIED
- DIMENSIONS ARE SUBJECT TO CHANGE IN DETAILED DESIGN PHASE

<div>"BY SEALING AND SIGNING THIS DRAWING, I CERTIFY THAT THE INFORMATION CONTAINED IN THESE ACCURATELY REFLECTS THE ORIGINAL DESIGN, ADDENDA, CHANGE ORDERS AND MATERIAL DESIGN CHANGES MADE DURING CONSTRUCTION AND FIELD REVIEWED BY ME, OR MY REPRESENTATIVE, AND THAT THE AS-CONSTRUCTED WORKS SUBSTANTIALLY COMPLY WITH THE ORIGINAL DESIGN INTENT, HOWEVER, I DO NOT ACCEPT RESPONSIBILITY OF THE ACCURACY OR COMPLETENESS OF THE AS-CONSTRUCTED INFORMATION SUPPLIED BY OTHERS CONTAINED IN THESE DRAWINGS."</div> <div>ISSUED FOR CONSTRUCTION</div> <div>2022-04-01</div>	SCALE 1:75		CAD FILENAME <u>Westbrook Mall Phase 4</u>		MINISTRY OF TRANSPORTATION AND INFRASTRUCTURE		WESBROOK MALL REDESIGN PHASE 4 Pedestrian Underpass Details				
	DATE <u>2021-11-30</u>		DATE <u>2021-11-30</u>								
	REV	DATE	REVISIONS	SIGNATURE	REGION_NAME BRANCH						
					DESIGNED <u>Josh Bian</u> DATE <u>2021-11-30</u>		FILE NUMBER	PROJECT NUMBER	REG	DRAWING NUMBER	REV
					QUALITY CONTROL <u>George Gu</u> DATE <u>2021-11-30</u>		01	1228	R	28	A
					QUALITY ASSURANCE <u>George Gu</u> DATE <u>2021-11-30</u>						
					DRAWN <u>Josh Bian</u> DATE <u>2021-11-30</u>						
					SENIOR DESIGNER						
					DATE <u>2021-11-30</u>						

Appendix A - Construction Specifications

1. Concrete Walks, Curbs and Gutters

1.1. GENERAL

1.1.1. Related Work

1.1.1.1. Storm Sewers

1.2. PRODUCTS

1.2.1. Polyvinyl Chloride (PVC) or Acrylonitrile Butadiene-Styrene (ABS) plastics shall meet the requirements of the latest revision of CAN / CSA 182.1. Pipe shall be available in 3m lengths with nominal diameter of 100mm and perforations as detailed in Section 4.1.4 of CAN / CSA 182.1 for leach field pipe. The pipe will include bell and spigot design suitable for solvent welding, where required. The pipe shall have an SDR of 28 or lower and 700kPa at 5% deflection.

1.3. EXECUTION

1.3.1. Formwork

1.3.1.1. At lanes, crossings and other similar locations, formwork shall be left in place until the concrete has attained sufficient strength to bear traffic loads without edge damage. Sufficient strength generally means minimum 20MPa in concrete strength

1.3.2. Driveway Crossings and Wheel Chair Ramp

1.3.2.1. Wheel Chair Ramps

1.3.2.1.1. Ramps shall land wheelchair and other users safely in the crosswalk and in the desired direction of travel.

1.3.2.1.2. The ramp and the directional score lines shall lead into the crosswalk, lining up with the ramp across the Street and be parallel with the crossing or marked crosswalk.

1.3.2.2. Double Curb Ramp

1.3.2.2.1. Minimum 1.0m full curb is required between the two ramps as per Standard Detail Drawing C8.1. Double curb ramps are preferred, and shall be implemented whenever possible, over large single curb ramps

1.3.2.3. Large Single Curb Ramp

1.3.2.3.1. The ramp must adequately land a pedestrian in both crosswalks as per Standard Detail Drawing C8.2.

1.3.2.4. Lane Curb Ramp

1.3.2.4.1. The ramp and the directional score lines shall line up with the ramp across the lane and be parallel with the crossing as per Standard Detail Drawing C9.1.

1.3.2.4.2. The minimum thickness of all residential concrete driveway crossings shall be 200mm as per Standard Detail Drawing C7.1. The minimum thickness for commercial crossings is 300mm as per Standard Detail Drawing C7.2.

1.3.3. Control Joints

1.3.3.1. Walks 1.5m, 1.8m, and 2.0m in width shall be marked off in panels 1.5m, 1.8m, or 2.0m long respectively unless otherwise directed by the Owner Representative. Control joints to control and minimize cracking shall be installed to the satisfaction of the Owner Representative. The scoring pattern of the sidewalk is governed by the distance between features such as tree pits and water valve boxes. Keep the scoring pattern as square as possible for the sidewalk panels.

1.3.4. Isolation Joints

1.3.4.1. Carefully fit, cut, and mark the sidewalk around all features such as water valve boxes, lamp standards, poles, and hydrants to prevent cracking of the slabs, to the satisfaction of the Owner Representative.

1.3.5. Finishing

1.3.5.1. Cutting and marking tools shall have a cutting edge not less than 25mm in depth and the edge of the panel shall be rounded to a 6mm radius. Trowel edge to be as close to

flush as possible with broom finish. The broom finish shall extend to the edge of the panel.

1.3.5.2. Finished curb and gutter shall have a smooth and uniform surface, true to line, grade, and section and shall be free from voids, sags, bumps, or other irregularities to the satisfaction of the Owner Representative.

1.3.5.3. All control joints are to be sawcut only (no trowel marks) and shall be done 24 hours after the pour to avoid any cracking.

1.3.5.4. All score lines are to be trowelled only.

1.3.6. Acceptance

1.3.6.1. Any portion marked or damaged by vandalism, rain, frost, equipment, traffic, or other, to be replaced at the Contractor's cost.

1.3.6.2. The Contractor shall be responsible for any damage to existing concrete walks, curbs, and gutters at their Site or any damages at adjacent sites, and shall make all necessary repairs, at their cost, to any damage caused from their construction activities to the satisfaction of the Owner Representative.

2. Cast-in-Place Concrete

2.1. PRODUCTS

2.1.1. Materials

2.1.1.1. All concrete used under this specification shall be ready-mixed concrete, proportioned and mixed in an approved mixing plant.

2.1.2. Concrete Mixes

2.1.2.1. All concrete supplied shall meet the requirements of CAN / CSA-A23.1 and City-specified mix requirements unless otherwise allowed by the Owner Representative. Concrete shall be normal weight, and the Contractor and its supplier shall assume responsibility for the quality and performance of the concrete as per

CAN / CSA-A23.1 Table 5 Alternative 1. Submit mix designs to the Contract

Administrator for review and record upon request.

2.2. EXECUTION

2.2.1. Cold Weather Placement

- 2.2.1.1. Cold weather requirements apply when the air temperature is at or below 5°C, or is forecast to fall below 5°C within 24 hours of placing. Do not schedule or place concrete during periods that have a high probability of rain or snow. Protect concrete against potential rain and frost until it has cured sufficiently to the satisfaction of the Owner Representative.
- 2.2.1.2. When concrete is to be placed in cold weather, have all materials and equipment needed for adequate protection and curing on hand and ready for use before concrete placement is started. Obtain prior authorization from the Owner Representative for the proposed enclosures, equipment, and procedures for cold weather concreting.
- 2.2.1.3. Do not place concrete against any surface that has a temperature of less than 5°C. Remove all snow and ice. Preheat such surfaces for 24 hours or as required to obtain surface temperatures of 5°C minimum, whichever is longer, prior to placing concrete.
- 2.2.1.4. Design and construct heating and hoarding protection measures including heated enclosures, coverings, insulation, or a suitable combination of these methods in accordance with CAN / CSA-A23.1.
- 2.2.1.5. Inspect heating and hoarding measures at least every four hours and verify that enclosures, coverings, and insulation are in place, there is adequate heater fuel, and the specified temperatures are being maintained.
- 2.2.1.6. Provide a sufficient number of adequately sized and properly vented heaters. Do not place heaters at locations that may cause rapid drying of freshly placed concrete. Use fans to constantly circulate warm air within the enclosure. Do not use tiger torches or other open flame burners as heaters.

2.2.2. Hot Weather Placement

- 2.2.2.1. Hot weather requirements apply when the air temperature is at or above 25°C, or is forecast to rise to 25°C within 24 hours of placement.
- 2.2.2.2. Protect formwork, reinforcement, and concrete equipment from the direct rays of the sun, or cool by fogging and evaporation. Dampen subgrade surfaces prior to concrete placement.
- 2.2.2.3. Provide adequate personnel and equipment to transport, place, consolidate, and finish the concrete at the fastest possible rate. Obtain prior authorization from the Owner Representative for the proposed equipment and procedures for hot weather concreting.
- 2.2.2.4. Provide protection from drying in accordance with CAN / CSA-A23.1.

3. Excavating, Trenching and Backfilling

3.1. GENERAL

3.1.1. Limitations of Open Trench

- 3.1.1.1. All backfilling procedures shall be carried out as promptly as possible behind pipe laying. Under no circumstances shall an inactive open trench be open for more than 5 Days unless otherwise approved by the Contract Administrator. In addition, no more than one Block may remain un-backfilled at any given time, unless approved in advance by the Contract Administrator.
- 3.1.1.2. The use of road plates to cover excavations and restore travel lanes is generally not permitted. Where construction necessitates their use, a letter signed by an Engineer must be submitted ensuring the installation is safe and that the plate will support H-20 traffic loading. Plates need to be properly secured (either pinned or recessed into the pavement) and feathered a minimum 300mm with existing road asphalt. Plates need to extend a minimum 300mm beyond the trench, and any pavement damage related to the plate installation will need to be repaired.

3.1.2. Permits and Approvals

- 3.1.2.1. Conduct a Condition Survey with the Contract Administrator prior to commencing any excavation unless otherwise directed by the Owner Representative.

3.1.3. Measurement and Payment

- 3.1.3.1. Unless otherwise noted in the Contract Documents, payment for trench excavation by hand (hand dig) or hydro-vacuum excavation will be incidental to payment for Work described in other Sections.
- 3.1.3.2. Unless otherwise noted in the Contract Documents, payment for all charges or fees related to inspection from third-party utility companies and / or external authorities / agencies will be incidental to payment for Work described in other Sections
- 3.1.3.3. Payment for additional paving, including saw-cutting, removal of existing asphalt and base, and preparation of new base shall be made as per the relevant unit price item as indicated in the Schedule of Quantities and Prices.

Payment for additional paving connected to mainline trench pavement repair shall be paid using the lowest unit rate in the Schedule of Quantities and Prices.
- 3.1.3.4. Unless otherwise noted in the Contract Documents, payment for all costs incurred to obtain professional geotechnical services will be incidental to payment for Work described in other Sections.
- 3.1.3.5. Unless otherwise noted in the Contract Documents, payment for all costs of vertical trench timbering or sheeting protection will be incidental to payment for Work described in other Sections.

3.1.4. Inspection and Testing

- 3.1.4.1. Sources and gradation curves for backfill materials must be submitted to the Contract Administrator at least two weeks prior to construction. Material samples are required if requested by the Owner Representative.

- 3.1.4.2. Compaction tests will be performed as outlined in the Contract Documents and approved by the Owner Representative. Separate compaction tests at each depth are not required at the same station if storm and sanitary sewers are in a common trench.
- 3.1.4.3. The Contractor shall ensure all compaction test results (for all failed and passed tests) and test certificates are submitted to the Contract Administrator within 48 hours.
Compaction test results shall be submitted by third parties to the Contract Administrator.

3.2. PRODUCTS

3.2.1. Use of Specified Materials

- 3.2.1.1. Backfill for over-excavated trench to be one of the following, as indicated in the Contract Documents or as directed by the Owner Representative:
 - 3.2.1.1.1. 75mm Minus Crushed Tailings (City of Vancouver Aggregate #13).
 - 3.2.1.1.2. 19mm Minus Combined Crushed Aggregate Fill (Mulch) (City of Vancouver Aggregate #9).
 - 3.2.1.1.3. 19mm Clear Drain Rock (City of Vancouver Aggregate #7) (for waterworks only – only where approved by the Owner Representative).
 - 3.2.1.1.4. 20mm Clear Crushed Aggregate (City of Vancouver Aggregate #15) (for waterworks only – only where approved by the Owner Representative).
 - 3.2.1.1.5. 25mm Minus Combined Crushed Recycled Aggregate (City of Vancouver Aggregate #30) (for sewers only).
- 3.2.1.2. Backfill for trenches and excavations to be one of the following, as indicated in the Contract Documents or as directed by the Owner Representative:
 - 3.2.1.2.1. Approved granular native material:
 - 3.2.1.2.1.1. Native silts and / or clay materials shall not be used
 - 3.2.1.2.1.2. Native granular materials (primarily sand) are permissible for backfilling up to 1.2m below the finished grade. All approved native granular

materials shall be compacted to the minimum densities in 3.5.4 of this Section. In addition to the compaction requirements, the granular native material must be proven to be stable enough to provide a good foundation for the lifts of granular base on top. The acceptance of certain native granular materials will be at the sole discretion of the Owner Representative. The Owner Representative may also impose additional acceptance requirements as deemed necessary for the use of approved native granular material.

3.2.1.2.2. Granular or Sand Backfill:

3.2.1.2.2.1. Use imported granular fill materials as per SECTION 31 05 17 of the City of Vancouver Construction Specifications unless otherwise specified or approved by the Owner Representative.

3.2.1.2.3. Controlled Density Fill

3.2.1.2.3.1. Controlled density fill shall meet the requirements in Section 31 23 23 Controlled Density Fill.

3.2.1.2.3.2. Backfill material shall be free of large stones and or frozen material.

3.3. EXECUTION

3.3.1. Site Preparation

3.3.1.1. The Contractor shall continuously cut existing pavement to its full depth along neat straight lines with a cutting tool to confine the width of the pavement to be disturbed. The Contractor shall not disturb the pavement beyond the maximum trench width defined on the Drawings or contained herein, or unless approved otherwise by the Owner Representative.

3.3.2. Stockpiling

3.3.2.1. Do not block curb and gutter drainage with granular materials.

3.3.3. Excavation

- 3.3.3.1. Excavations shall be to the alignment and grades shown on the Drawings and as set in the field by the construction survey. Vertical walls on all trenches shall be maintained. If, in the opinion of the Contract Administrator, it is impossible or impractical to maintain vertical walls for certain sewer trenches, a “Y” type of excavation will be permitted to a point 300mm above the top of the pipe; trench walls below this point shall be maintained vertical using appropriate shoring methods.
- 3.3.3.2. For pipe bedding, the Contractor shall over excavate the trench as per Standard Detail Drawing G4.2, G4.3 and G4.4 or as specified herein or on the Drawings. If the bottom of the excavation extends beyond the required depth, the over-excavation shall be refilled at the Contractor’s expense with approved compacted granular material. The use of trench digging machinery will be permitted except where its operations will cause damage to trees, buildings, existing utilities, or existing structures above or below ground. At such locations, hand methods shall be employed to avoid such damage.
- 3.3.3.3. Vertical trench timbering or sheeting shall be placed in accordance with the requirements of WorkSafeBC or as may be necessary to protect life and property adjacent to or on the Site. The Contractor shall be responsible for the adequacy of such bracing and shoring. Unless otherwise accepted by the Contract Administrator, or as WorkSafeBC Rules and Regulations dictate, vertical trench timbering or sheeting shall be placed so as not to extend below the springline of the largest pipe. No timbering or sheeting shall be left in without the written approval of the Owner Representative, and when removed, the void left by the raised sheeting shall be backfilled and thoroughly compacted.
- 3.3.4. Backfill and Compaction
- 3.3.4.1. Care must be exercised in selecting compaction equipment. In City Streets, there are many utilities with service connections that are susceptible to damage. The use of drop

hammer type compactors and large vibrating rollers shall not be allowed, except under special conditions approved by the Owner Representative. The Contractor shall assume all responsibility for costs / damages caused to any existing utility.

3.3.4.2. All backfilling shall be controlled. The final acceptance to use the backfill method shall be at the sole discretion of the Owner Representative. No claim shall be made for the proposed backfill method being unaccepted.

3.3.4.3. Backfill materials shall be placed in uniform lifts not exceeding 300mm in loose thickness, 200mm for approved granular native material, and compacted to specified densities unless otherwise specified or allowed by the Owner Representative.

4. Aggregates and Granular Materials

4.1. PRODUCTS

4.1.1. General

4.1.1.1. Approved Granulars, as referenced in the Standard Detail Drawings, refers to 2.2, 2.3, 2.5, 2.6, 2.7, 2.9, 2.10, 2.11, and 2.13 of this Section.

4.1.2. Native Material

4.1.2.1. Granular native material may be used only with the express written permission of the Owner Representative, and provided it can be compacted to the requirement stated. All costs for Quality Control testing of granular native materials shall be covered by the Contractor.

4.1.2.2. The Owner Representative may require analytical laboratory confirmation that the native materials meet the applicable BC Ministry of Environment land use standards (residential or industrial).

4.1.3. Native Material

5. Granular Subbase

5.1. PRODUCTS

5.1.1. Specified Materials

5.1.1.1. Pit Run Gravel as per SECTION 31 05 17 of the City of Vancouver Construction Specifications.

5.1.1.2. 75mm Minus Crushed Tailings as per SECTION 31 05 17 of the City of Vancouver Construction Specifications.

5.1.1.3. Granular Native Material as per SECTION 31 05 17 of the City of Vancouver Construction Specifications.

5.1.1.4. Sand Fill as per SECTION 31 05 17 of the City of Vancouver Construction Specifications.

6. Granular Base

6.1. PRODUCTS

6.1.1. Granular Base

6.1.1.1. 19mm Minus Combined Crushed Aggregate Fill as per SECTION 31 05 17 of the City of Vancouver Construction Specifications.


Appendix B - Scheduling

WESBROOK MALL REDESIGN - PHASE 4


Project Start	19-Sep-21
Project End	21-Mar-23

ID's

Schedule ID	Component	WBS #	WBS Line Item	Complete	Duration (days)	Start	End
1	Underpass	1	Tunnel		361	13-Sep-21	9-Sep-22
2	Underpass	1.1	Site Delivery	yes	200	13-Sep-21	1-Apr-22
3	Underpass	1.1.1	Survey	yes	39	14-Sep-21	23-Oct-21
4	Underpass	1.1.1.1	Subsurface Investigation	yes	7	14-Sep-21	21-Sep-21
5	Underpass	1.1.1.2	Geotechnical Report	yes	7	22-Sep-21	29-Sep-21
6	Underpass	1.1.1.3	Ground Behavior, Control	yes	7	30-Sep-21	7-Oct-21
7	Underpass	1.1.1.4	Third-Party Impacts	yes	7	8-Oct-21	15-Oct-21
8	Underpass	1.1.1.5	Hazards Investigation	yes	7	16-Oct-21	23-Oct-21
9	Underpass	1.1.2	Preliminary Design	yes	40	24-Oct-21	3-Dec-21
10	Underpass	1.1.2.1	Project Layout	yes	8	25-Oct-21	2-Nov-21
11	Underpass	1.1.2.2	Excavation Planning	yes	7	3-Nov-21	10-Nov-21
12	Underpass	1.1.2.3	Construction Method Selection	yes	7	11-Nov-21	18-Nov-21
13	Underpass	1.1.2.4	Mapping and Engineering	yes	14	19-Nov-21	3-Dec-21
14	Underpass	1.1.3	Detailed Design	no	118	4-Dec-21	1-Apr-22
15	Underpass	1.1.3.1	Finalize Design	no	39	4-Dec-21	12-Jan-22
16	Underpass	1.1.3.2	Final Feasibility Study	no	39	12-Jan-22	20-Feb-22
17	Underpass	1.1.3.3	Preconstruction Engineering	no	39	20-Feb-22	1-Apr-22
18	Underpass	1.2	Drawing Approval	no	56	4-Apr-22	30-May-22
19	Underpass	1.2.1	Documents	no	19	4-Apr-22	22-Apr-22
20	Underpass	1.2.1.1	Design Memo	no	7	4-Apr-22	11-Apr-22
21	Underpass	1.2.1.2	Construction Documents	no	7	11-Apr-22	18-Apr-22
22	Underpass	1.2.1.3	Engineering Review	no	7	18-Apr-22	25-Apr-22
23	Underpass	1.2.1.4	Specifications	no	7	25-Apr-22	2-May-22
24	Underpass	1.2.2	Public Engagement	no	19	22-Apr-22	11-May-22
25	Underpass	1.2.2.1	Environmental Review	no	7	22-Apr-22	29-Apr-22
26	Underpass	1.2.2.2	Stakeholder Consultation	no	7	29-Apr-22	6-May-22
27	Underpass	1.2.2.3	Public Hearings	no	5	6-May-22	11-May-22
28	Underpass	1.2.3	Bidding	no	19	11-May-22	30-May-22
29	Underpass	1.2.3.1	Bid packages	no	7	11-May-22	18-May-22
30	Underpass	1.2.3.2	Project Information Systems	no	4	14-May-22	18-May-22
31	Underpass	1.2.3.3	Bid Review and Selection	no	11	18-May-22	29-May-22
32	Underpass	1.3	Mobilization	no	7	30-May-22	6-Jun-22
33	Underpass	1.3.1	Procurement	no	2	30-May-22	1-Jun-22
34	Underpass	1.3.1.1	Bill of Quantities	no	2	30-May-22	1-Jun-22
35	Underpass	1.3.1.2	Machinery	no	2	30-May-22	1-Jun-22
36	Underpass	1.3.1.3	Utility and Safety Equipment	no	2	30-May-22	1-Jun-22
37	Underpass	1.3.2	Fabricate Structural Elements	no	7	30-May-22	6-Jun-22
38	Underpass	1.3.2.1	Fabricate Floor Slab	no	2	30-May-22	1-Jun-22
39	Underpass	1.3.3	Site Preparation	no	2	6-Jun-22	8-Jun-22
40	Underpass	1.3.3.1	Utility Relocation	no	2	6-Jun-22	8-Jun-22
41	Underpass	1.3.3.2	Staging Area	no	2	6-Jun-22	8-Jun-22
42	Underpass	1.3.3.3	Backup Systems	no	2	6-Jun-22	8-Jun-22
43	Underpass	1.4	Construction	no	88	9-Jun-22	5-Sep-22
44	Underpass	1.4.1	Excavation	no	21	9-Jun-22	30-Jun-22
45	Underpass	1.4.1.1	Cut and Cover	no	21	9-Jun-22	30-Jun-22
46	Underpass	1.4.2	Support	no	7	30-Jun-22	7-Jul-22
47	Underpass	1.4.2.1	Support Columns	no	7	30-Jun-22	7-Jul-22
48	Underpass	1.4.2.2	Temporary Lining	no	7	30-Jun-22	7-Jul-22
49	Underpass	1.4.3	Lining	no	38	7-Jul-22	14-Aug-22
50	Underpass	1.4.3.1	Lining Segments Staged	no	19	7-Jul-22	26-Jul-22
51	Underpass	1.4.3.2	Floor Slab Installed	no	19	7-Jul-22	26-Jul-22
52	Underpass	1.4.3.3	Support Walls Installed	no	19	26-Jul-22	14-Aug-22
53	Underpass	1.4.3.4	Ceiling Slab Installed	no	19	26-Jul-22	14-Aug-22
54	Underpass	1.4.3.5	Entrance/Exit Staircase Installed	no	19	26-Jul-22	14-Aug-22
55	Underpass	1.4.4	Finishing	no	21	15-Aug-22	5-Sep-22
56	Underpass	1.4.4.1	Concrete Protective Coating Applied	no	13	15-Aug-22	28-Aug-22
57	Underpass	1.4.4.2	Guardrail Cast In	no	13	15-Aug-22	28-Aug-22
58	Underpass	1.4.4.3	Stormwater Drainage System Installed	no	13	15-Aug-22	28-Aug-22
59	Underpass	1.4.4.4	Lighting System Installed	no	7	29-Aug-22	5-Sep-22
60	Underpass	1.4.4.5	Fire Suppression System Installed	no	7	29-Aug-22	5-Sep-22
61	Underpass	1.4.4.6	Security System Installed	no	7	29-Aug-22	5-Sep-22
62	Underpass	1.5	Closing	no	25	5-Sep-22	30-Sep-22
63	Underpass	1.5.1	Testing	no	7	5-Sep-22	12-Sep-22
64	Underpass	1.5.1.1	Test Safety Systems	no	7	5-Sep-22	12-Sep-22
65	Underpass	1.5.1.2	Certifications	no	7	5-Sep-22	12-Sep-22
66	Underpass	1.5.2	Training	no	17	5-Sep-22	22-Sep-22
67	Underpass	1.5.2.1	Emergency Operations Training	no	17	5-Sep-22	22-Sep-22
68	Underpass	1.5.3	Demobilization	no	7	23-Sep-22	30-Sep-22
69	Underpass	1.5.3.1	Decommission Staging Site	no	7	23-Sep-22	30-Sep-22
70	Underpass	1.5.3.2	Remove Equipment	no	7	23-Sep-22	30-Sep-22
71	Underpass	1.5.3.3	Final Paving	no	7	23-Sep-22	30-Sep-22



Schedule ID	Component	WBS #	WBS Line Item	Complete	Duration (days)	Start	End
72	Roadworks	2	Roadworks, Sidewalk, Multi Use Pathway	no	553	13-Sep-21	20-Mar-23
73	Roadworks	2.1	Site Delivery	no	200	13-Sep-21	1-Apr-22
74	Roadworks	2.1.1	Survey	no	39	14-Sep-21	23-Oct-21
75	Roadworks	2.1.1.1	Subsurface Investigation	no	7	14-Sep-21	21-Sep-21
76	Roadworks	2.1.1.2	Geotechnical Report	no	7	22-Sep-21	29-Sep-21
77	Roadworks	2.1.1.3	Ground behavior, Control	no	7	30-Sep-21	7-Oct-21
78	Roadworks	2.1.1.4	Third-Party Impacts	no	7	8-Oct-21	15-Oct-21
79	Roadworks	2.1.1.5	Hazards Investigation	no	7	16-Oct-21	23-Oct-21
80	Roadworks	2.1.2	Preliminary Design	no	40	24-Oct-21	3-Dec-21
81	Roadworks	2.1.2.1	Project Layout	no	8	25-Oct-21	2-Nov-21
82	Roadworks	2.1.2.2	Excavation Planning	no	7	3-Nov-21	10-Nov-21
83	Roadworks	2.1.2.3	Construction Method Selection	no	7	11-Nov-21	18-Nov-21
84	Roadworks	2.1.2.4	Mapping and Engineering	no	14	19-Nov-21	3-Dec-21
85	Roadworks	2.1.3	Detailed Design	no	118	4-Dec-21	1-Apr-22
86	Roadworks	2.1.3.1	Finalize Design	no	39	4-Dec-21	12-Jan-22
87	Roadworks	2.1.3.2	Final Feasibility Study	no	39	12-Jan-22	20-Feb-22
88	Roadworks	2.1.3.3	Preconstruction Engineering	no	39	20-Feb-22	1-Apr-22
89	Roadworks	2.2	Drawings Approval	no	56	4-Apr-22	30-May-22
90	Roadworks	2.2.1	Documents	no	19	4-Apr-22	22-Apr-22
91	Roadworks	2.2.1.1	Design Memo	no	7	4-Apr-22	11-Apr-22
92	Roadworks	2.2.1.2	Construction Documents	no	7	11-Apr-22	18-Apr-22
93	Roadworks	2.2.1.3	Engineering Review	no	7	18-Apr-22	25-Apr-22
94	Roadworks	2.2.1.4	Specifications	no	7	25-Apr-22	2-May-22
95	Roadworks	2.2.2	Public Approval	no	19	22-Apr-22	11-May-22
96	Roadworks	2.2.2.1	Environmental Review	no	7	22-Apr-22	29-Apr-22
97	Roadworks	2.2.2.2	Stakeholder Consultation	no	7	29-Apr-22	6-May-22
98	Roadworks	2.2.2.3	Public Hearings	no	5	6-May-22	11-May-22
99	Roadworks	2.2.3	Bidding	no	19	11-May-22	30-May-22
100	Roadworks	2.2.3.1	Bid packages	no	7	11-May-22	18-May-22
101	Roadworks	2.2.3.2	Project Information Systems	no	4	14-May-22	18-May-22
102	Roadworks	2.2.3.3	Bid Review and Selection	no	11	18-May-22	29-May-22
103	Roadworks	2.3	Mobilization	no	7	30-May-22	6-Jun-22
104	Roadworks	2.3.1	Procurement	no	4	30-May-22	2-Jun-22
105	Roadworks	2.3.1.1	Bill of Quantities	no	4	30-May-22	2-Jun-22
106	Roadworks	2.3.1.2	Machinery	no	4	30-May-22	2-Jun-22
107	Roadworks	2.3.1.3	Utility and Safety Equipment	no	4	30-May-22	2-Jun-22
108	Roadworks	2.3.2	Fabricate Elements	no	4	30-May-22	2-Jun-22
109	Roadworks	2.3.2.1	Construct Planters	no	4	30-May-22	2-Jun-22
110	Roadworks	2.3.3	Site Preparation	no	7	30-May-22	6-Jun-22
111	Roadworks	2.3.3.1	Utility Relocation	no	9	30-May-22	8-Jun-22
112	Roadworks	2.3.3.2	Staging Area	no	9	30-May-22	8-Jun-22
113	Roadworks	2.3.3.3	Backup Systems	no	9	30-May-22	8-Jun-22
114	Roadworks	2.4	Construction	no	264	9-Jun-22	28-Feb-23
115	Roadworks	2.4.1	Earthworks	no	88	9-Jun-22	5-Sep-22
116	Roadworks	2.4.1.1	Excavation and Ripping	no	88	9-Jun-22	5-Sep-22
117	Roadworks	2.4.2	Fill	no	176	5-Sep-22	28-Feb-23
118	Roadworks	2.4.2.1	Subbase Pavement	no	59	5-Sep-22	2-Nov-22
119	Roadworks	2.4.2.2	Base Pavement	no	59	2-Nov-22	31-Dec-22
120	Roadworks	2.4.2.3	Geotextile Placement	no	59	31-Dec-22	28-Feb-23
121	Roadworks	2.5	Closing	no	21	28-Feb-23	21-Mar-23
122	Roadworks	2.5.1	Testing	no	6	28-Feb-23	6-Mar-23
123	Roadworks	2.5.1.1	Asphalt and Concrete Compaction Testing	no	7	6-Mar-23	13-Mar-23
124	Roadworks	2.5.1.2	Certifications	no	7	6-Mar-23	13-Mar-23
125	Roadworks	2.5.2	Training	no	6	7-Mar-23	13-Mar-23
126	Roadworks	2.5.2.1	Emergency Operations Training	no	6	7-Mar-23	13-Mar-23
127	Roadworks	2.5.3	Demobilization	no	7	14-Mar-23	21-Mar-23
128	Roadworks	2.5.3.1	Decommission Staging Site	no	7	14-Mar-23	21-Mar-23
129	Roadworks	2.5.3.2	Remove Equipment	no	7	14-Mar-23	21-Mar-23
130	Roadworks	2.5.3.3	Final Paving	no	7	14-Mar-23	21-Mar-23



Appendix C - Class A Cost Estimate

WB Mall Estimate

Qty	Line Number	Group	Description	Crew	Unit	Labor Hours	Daily Output	Extended Material	Extended Labor	Extended Equipment	Extended Total	Extended Total O&P
3727	321123230301	Sidewalk	Base course drainage layers, aggregate base course for roadways and large paved areas, crushed stone base, compacted, crushed 1-1/2" stone base, to 4" deep	B36B	S.Y.	0.011	6,000.00	\$ 19,007.70	\$ 1,229.91	\$ 2,497.09	\$ 22,734.70	\$ 25,679.03
2748	320116715320	Raised Bike Lane	Cold milling asphalt paving, asphalt pavement, 1" to 3" deep, removal from concrete base, rip, load and sweep, excludes hauling	B70	S.Y.	0.007	8,000.00		\$ 577.08	\$ 522.12	\$ 1,099.20	\$ 1,538.88
2748	321216130200	Raised Bike Lane	Plant-mix asphalt paving, for highways and large paved areas, binder course, 4" thick, no hauling included	B25	S.Y.	0.021	4,140.00	\$ 38,197.20	\$ 1,703.76	\$ 1,648.80	\$ 41,549.76	\$ 46,661.04
3	311313201600	General	Selective felling trees and piling, large tract clearing & piling, firm level terrain, no boulders, softwood, per tree, 300 H.P. dozer, 12" to 24" diameter	B10M	Ea.	0.04	200.00		\$ 4.20	\$ 24.15	\$ 28.35	\$ 33.39
3	311313202100	General	Selective clearing and grubbing, 1-1/2 C.Y. excavator, 14" to 24" diameter, stump removal on site by hydraulic excavator	B30	Ea.	0.96	25.00		\$ 85.50	\$ 235.50	\$ 321.00	\$ 399.00
1386	241131760000	Site Prep	Demolish, remove pavement & curb, remove concrete curbs, plain, excludes hauling and disposal fees	B6	L.F.	0.067	360.00		\$ 2,661.12	\$ 1,233.54	\$ 3,894.66	\$ 5,779.62
38	334413131582	Site Prep	RELOCATION: Utility Area Drains, catch basins or manholes curb inlet frame, grate, and curb box, large, heavy duty, 24" x 36", excludes footing, excavation, and backfill	B24	Ea.				\$ 13,870.00		\$ 13,870.00	\$ 47,880.00
38	24113420400	Site Prep	Selective demolition, manholes & catch basins, manhole top, precast 8" thick, 4'-6" dia, excludes excavation	B6	Ea.	3	8.00		\$ 3,287.00	\$ 1,520.00	\$ 4,807.00	\$ 7,106.00
3000	312316130050	Multiuse Path/Si	Excavating, trench or continuous footing, common earth, 3/8 C.Y. excavator, 1' to 4' deep, excludes sheeting or dewatering	B11C	B.C.Y.	0.107	150.00		\$ 9,810.00	\$ 6,420.00	\$ 16,230.00	\$ 23,250.00
3350	321723130020	General	Painted pavement markings, acrylic waterborne, white or yellow, 4" wide	B78	L.F.	0.002	20,000.00	\$ 636.50	\$ 167.50	\$ 67.00	\$ 871.00	\$ 1,105.00
1	2	General	Bus Shelter Relocation	A1F	Ea.				\$ 2,000.00	\$ 2,000.00	\$ 4,000.00	\$ 4,000.00
45000	320610100450	Multiuse Path/Si	Sidewalks, driveways, and patios, sidewalks, concrete, excludes base, for 4" thick bank run gravel base, add	B18	S.F.	0.01	2,500.00	\$ 22,950.00	\$ 11,700.00	\$ 900.00	\$ 35,550.00	\$ 45,900.00
2005	321613130404	Roadworks	Cast-in place concrete curbs & gutters, concrete, wood forms, straight 6" x 18", incudes concrete	C2A	L.F.	0.096	500.00	\$ 9,624.00	\$ 6,235.55		\$ 15,859.55	\$ 20,952.25
1	265613103000	General	REMOVAL: Light poles, anchor base, aluminum, 20' high, excluding concrete bases	R3	Ea.			\$ 930.00	\$ 273.00	\$ 44.50	\$ 1,247.50	\$ 1,519.00
4320	329226130300	Green Infrastruct	Sprigging, stolonizing, broadcast, 6 bushels per M.S.F., hydro Green Infrastructure	B64	M.S.F.	0.16	100.00	\$ 40,500.00	\$ 9,136.80	\$ 6,523.20	\$ 56,160.00	\$ 66,268.80
1370	312316130050	Sidewalk	Excavating, trench or continuous footing, common earth, 3/8 C.Y. excavator, 1' to 4' deep, excludes sheeting or dewatering	B11C	B.C.Y.	0.107	150.00		\$ 4,479.90	\$ 2,931.80	\$ 7,411.70	\$ 10,617.50
1600	320116715200	Sidewalk	Cold milling asphalt paving, 1" to 3" asphalt pavement, over 25,000 S.Y., cold planing & cleaning	B71	S.Y.	0.009	6,000.00		\$ 448.00	\$ 1,744.00	\$ 2,192.00	\$ 2,672.00
1600	321123230301	Sidewalk	Base course drainage layers, aggregate base course for roadways and large paved areas, crushed stone base, compacted, crushed 1-1/2" stone base, to 4" deep	B36B	S.Y.	0.011	6,000.00	\$ 8,160.00	\$ 528.00	\$ 1,072.00	\$ 9,760.00	\$ 11,024.00
1600	321123230304	Sidewalk	Base course drainage layers, aggregate base course for roadways and large paved areas, crushed stone base, compacted, crushed 1-1/2" stone base, to 12" deep	B36B	S.Y.	0.017	3,800.00	\$ 24,480.00	\$ 832.00	\$ 1,696.00	\$ 27,008.00	\$ 30,192.00
1600	334626100188	Sidewalk	Geotextile Subsurface Drainage Filtration, soil drainage mat on vertical wall, 0.25" thick	2 Clab	S.Y.	0.053	300.00	\$ 2,464.00	\$ 2,256.00		\$ 4,720.00	\$ 6,480.00
1600	334626100188	Sidewalk	Geotextile Subsurface Drainage Filtration, soil drainage mat on vertical wall, 0.25" thick	2 Clab	S.Y.	0.053	300.00	\$ 2,464.00	\$ 2,256.00		\$ 4,720.00	\$ 6,480.00
14410	321416100620	Sidewalk	Brick paving, bedding, mortar, 2" thick	D1	S.F.	0.08	200.00	\$ 18,877.10	\$ 35,016.30		\$ 53,893.40	\$ 78,246.00
4000	24113175200	Sidewalk	Demolish, remove pavement & curb, remove concrete, mesh reinforced, to 150 mm thick, hydraulic hammer, excludes hauling and disposal fees	B38	S.Y.	0.188	213.00		\$ 29,200.00	\$ 21,400.00	\$ 50,600.00	\$ 67,600.00
189	34713170900	Green Infrastruct	Security vehicle barriers, concrete Green Infrastructure, exposed aggregate finish, rectangle, 96" long x 24" wide x 30" high, excludes filling material	B11M	Ea.	2	8.00	\$ 67,567.50	\$ 5,811.75	\$ 4,110.75	\$ 77,490.00	\$ 88,338.60
14210	321123230302	Roadworks	Base course drainage layers, aggregate base course for roadways and large paved areas, crushed stone base, compacted, crushed 1-1/2" stone base, to 6" deep	B36B	S.Y.	0.012	5,400.00	\$ 108,706.50	\$ 5,257.70	\$ 10,515.40	\$ 124,479.60	\$ 139,417.15
14210	320116715280	Roadworks	Cold milling asphalt paving, 1" to 3" asphalt pavement, 5,000 to 10,000 S.Y., cold planing & cleaning	B71	S.Y.	0.014	4,000.00	\$ -	\$ 6,110.30	\$ 23,304.40	\$ 29,414.70	\$ 35,591.79
14210	321123230302	Roadworks	Base course drainage layers, aggregate base course for roadways and large paved areas, crushed stone base, compacted, crushed 1-1/2" stone base, to 6" deep	B36B	S.Y.	0.012	5,400.00	\$ 108,706.50	\$ 5,257.70	\$ 10,515.40	\$ 124,479.60	\$ 139,417.15
14210	321126130550	Roadworks	Asphalt Paving, plant mixed asphaltic base courses for roadways and large paved areas, bituminous concrete, 6" thick	B25	S.Y.	0.024	3,700.00	\$ 298,410.00	\$ 9,804.90	\$ 9,520.70	\$ 317,735.60	\$ 352,686.52
1	3	Roadworks	Consulting and Engineering Fees for Signal Retiming	ENG	Ea.			\$ 3,400.00	\$ 1,000.00		\$ 4,400.00	\$ 4,400.00
								\$ 775,081.00	\$ 170,999.97	\$ 110,446.35	\$ 1,056,527.32	\$ 1,271,234.72

Inflation	1.28
CPI	1.31
Currency	1.28
Contingency	1.1
Contractor Markup	1.2
Bonds and Insurance	1.05
Management and Permitting	1.085
	\$4,103,080

Underpass Cost Estimate























Qty	Line Number	Group	Description	Crew	Unit	Labor Hours	Daily Output	Extended Material	Extended Labor	Extended Equipment	Extended Total	Extended Total O&P
60	55213500020		Railing, pipe, aluminum, satin finish, 2 rails, 3'-6" high, posts @ 5' O.C., 1-1/4" dia, shop fabricated	E4	L.F.	0.2	160	\$ 1,890.00	\$ 444.00	\$ 40.80	\$ 2,374.80	\$ 2,958.00
2223	312316420200		Excavating, bulk bank measure, 1 C.Y. capacity = 75 C.Y./hour, backhoe, hydraulic, crawler mounted, excluding truck loading	B12A	B.C.Y	0.02	800		\$ 1,378.26	\$ 2,022.93	\$ 3,401.19	\$ 4,512.69
1	282323500400		CB 9-S GATEKEEPER ENCLOSURE: Video surveillance, internet protocol (IP) network, day/night, color, includes power supply		Ea.			\$ 3,000.00	\$ 124.00		\$ 3,124.00	\$ 1,376.00
100	33053401900		Structural concrete, in place, elevated slab (4000 psi), flat slab with drop panels, 125 psf superimposed load, 20' span, includes forms(4 uses), WTIHOUT REINFORCING STEEL, concrete, placing and finishing	C14B	C.Y.			\$ 23,400.00	\$ 18,100.00	\$ 1,985.00	\$ 43,485.00	\$ 58,400.00
112	33053406800		Structural concrete, in place, stairs (3500 psi), 3'-6" wide, free standing, includes forms(4 uses), reinforcing steel, concrete, placing and finishing, WITH safety treads	C14H	LF Nose			\$ 560.00	\$ 2,576.00	\$ 31.36	\$ 3,167.36	\$ 4,234.72
170	312514160060		Synthetic erosion control, nylon, 3 dimensional geomatrix, 9 mil thick	B80A	S.Y.	0.034	700	\$ 289.00	\$ 154.70	\$ 52.70	\$ 496.40	\$ 634.10
7	32110500200		Reinforcing Steel, average price, cut, bent and delivered, A615, grade 40, material only		Ton			\$ 6,160.00			\$ 6,160.00	\$ 6,790.00
251	321123230304		Base course drainage layers, aggregate base course for roadways and large paved areas, crushed stone base, compacted, crushed 1-1/2" stone base, to 12" deep	B36B	S.Y.	0.017	3800	\$ 3,840.30	\$ 130.52	\$ 266.06	\$ 4,236.88	\$ 4,736.37
20	265623101190		Metal halide fixture, exterior, wall pack, 250 Watt, incl lamps	1 ELEC	Ea.	2	4	\$ 5,800.00	\$ 1,610.00		\$ 7,410.00	\$ 9,020.00
79	24113176000		Demolish, remove pavement & curb, remove concrete curbs, plain, excludes hauling and disposal fees	B6	L.F.	0.067	360		\$ 151.68	\$ 70.31	\$ 221.99	\$ 329.43
1	210523506320		Sprinkler System Valve Alarm, 8" size, incl. retard chamber, trim, gauges & alarm line strainer	Q13	Ea.	10.667	3	\$ 1,825.00	\$ 375.00		\$ 2,200.00	\$ 2,615.00
1	221123111020		Pump, turbine pump, cast iron, 100 GPM, 3 H.P., 4" discharge	Q2	Ea.	25	0.96	\$ 8,225.00	\$ 860.00		\$ 9,085.00	\$ 7,150.00
1	330516130050		Utility structures, utility vaults precast concrete, excludes excavation and backfill	B13	Ea.			\$ 2,425.00	\$ 680.00	\$ 375.00	\$ 3,480.00	\$ 4,210.00
2	221319130440		Drain, deck, auto park, cast iron, 13" top, 3", 4", 5" and 6" pipe size	Q1	Ea.	2	8	\$ 2,250.00	\$ 143.00		\$ 2,393.00	\$ 2,734.00
3767	321123230302		Base course drainage layers, aggregate base course for roadways and large paved areas, crushed stone base, compacted, crushed 1-1/2" stone base, to 6" deep	B36B	S.Y.	0.012	5400	\$ 28,817.55	\$ 1,393.79	\$ 2,787.58	\$ 32,998.92	\$ 37,029.61
3767	320116715280		Cold milling asphalt paving, 1" to 3" asphalt pavement, 5,000 to 10,000 S.Y., cold planing & cleaning	B71	S.Y.	0.014	4000		\$ 1,619.81	\$ 6,177.88	\$ 7,797.69	\$ 9,417.50
3767	321123230302		Base course drainage layers, aggregate base course for roadways and large paved areas, crushed stone base, compacted, crushed 1-1/2" stone base, to 6" deep	B36B	S.Y.	0.012	5400	\$ 28,817.55	\$ 1,393.79	\$ 2,787.58	\$ 32,998.92	\$ 37,029.61
3767	321126130550		Asphalt Paving, plant mixed asphaltic base courses for roadways and large paved areas, bituminous concrete, 6" thick	B25	S.Y.	0.024	3700	\$ 79,107.00	\$ 2,599.23	\$ 2,523.89	\$ 84,230.12	\$ 93,722.96
3000	312323200044		Cycle hauling(wait, load,travel, unload or dump & return) time per cycle, excavated or borrow, loose cubic yards, 10 min wait/load/unload, 8 C.Y. truck, cycle 4 miles, 25 MPH, excludes loading equipment	B34A	L.C.Y.	0.042	192		\$ 3,390.00	\$ 4,920.00	\$ 8,310.00	\$ 11,070.00
								\$ 196,406.40	\$ 37,123.78	\$ 24,041.09	\$ 257,571.27	\$ 297,969.99

Inflation	1.376
Currency	1.28
Contingency	1.2
Contractor Markup	1.2
Bonds and Insurance	1.05
Management and Permitting	1.085
Adjusted Cost	\$ 860,958.98

Appendix D - Traffic Modeling


Lanes, Volumes, Timings
3: Thunderbird Boulevard & Wesbrook Mall

2050 AM BASE MODEL
2021-11-30

												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Lane Width (m)	2.9	3.3	3.3	3.5	4.0	3.5	3.5	4.0	3.5	3.1	3.5	3.3
Storage Length (m)	60.0		40.0	0.0		30.0	110.0		0.0	50.0		12.0
Storage Lanes	1		1	1		0	1		0	1		1
Total Lost Time (s)	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0
Leading Detector (m)	6.5	6.5	1.5	6.5	6.5		6.5	6.5		6.5	6.5	1.5
Trailing Detector (m)	1.5	1.5	0.0	1.5	1.5		1.5	1.5		1.5	1.5	0.0
Turning Speed (k/h)	25		15	25		15	25		15	25		15
Lane Util. Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Ped Bike Factor	0.89		0.79	0.84	0.97		0.94	0.87				0.82
Frt			0.850		0.982			0.932				0.850
Flt Protected	0.950			0.950			0.950			0.950		
Satd. Flow (prot)	1632	1801	1531	1750	1853	0	1750	1574	0	1671	1842	1531
Flt Permitted	0.449			0.680			0.247			0.154		
Satd. Flow (perm)	684	1801	1210	1056	1853	0	428	1574	0	271	1842	1250
Right Turn on Red			Yes			Yes			Yes			Yes
Satd. Flow (RTOR)			88		10			78				106
Headway Factor	1.11	1.04	1.04	1.01	0.94	1.01	1.01	0.94	1.01	1.08	1.01	1.04
Link Speed (k/h)		50			50			50				50
Link Distance (m)		153.9			112.5			755.2			92.2	
Travel Time (s)		11.1			8.1			54.4			6.6	
Volume (vph)	101	79	52	129	150	33	359	417	229	45	339	211
Confl. Peds. (#/hr)	133		193	193		133	92		100	100		92
Confl. Bikes (#/hr)			39			42			52			7
Peak Hour Factor	0.69	0.66	0.59	0.64	0.55	0.86	0.86	0.84	0.56	0.75	0.83	0.81
Parking (#/hr)									0			
Adj. Flow (vph)	146	120	88	202	273	38	417	496	409	60	408	260
Lane Group Flow (vph)	146	120	88	202	311	0	417	905	0	60	408	260
Turn Type	Perm		Perm	Perm			pm+pt			Perm		Perm
Protected Phases		4			8		5	2			6	
Permitted Phases	4		4	8			2			6		6
Detector Phases	4	4	4	8	8		5	2		6	6	6
Minimum Initial (s)	7.0	7.0	7.0	7.0	7.0		6.0	10.0		10.0	10.0	10.0
Minimum Split (s)	31.3	31.3	31.3	33.3	33.3		12.5	21.9		28.9	28.9	28.9
Total Split (s)	34.0	34.0	34.0	34.0	34.0	0.0	16.0	46.0	0.0	30.0	30.0	30.0
Total Split (%)	42.5%	42.5%	42.5%	42.5%	42.5%	0.0%	20.0%	57.5%	0.0%	37.5%	37.5%	37.5%
Maximum Green (s)	27.7	27.7	27.7	27.7	27.7		9.5	40.1		24.1	24.1	24.1
Yellow Time (s)	3.6	3.6	3.6	3.6	3.6		3.4	3.6		3.6	3.6	3.6
All-Red Time (s)	2.7	2.7	2.7	2.7	2.7		3.1	2.3		2.3	2.3	2.3
Lead/Lag							Lead			Lag	Lag	Lag
Lead-Lag Optimize?							Yes			Yes	Yes	Yes
Vehicle Extension (s)	3.0	3.0	3.0	3.0	3.0		2.5	4.0		4.0	4.0	4.0
Recall Mode	None	None	None	None	None		None	C-Min		C-Min	C-Min	C-Min
Walk Time (s)	7.0	7.0	7.0	7.0	7.0			7.0		7.0	7.0	7.0
Flash Dont Walk (s)	18.0	18.0	18.0	20.0	20.0			9.0		16.0	16.0	16.0
Pedestrian Calls (#/hr)	0	0	0	0	0			0		0	0	0
Act Effct Green (s)	22.8	22.8	22.8	22.8	22.8		49.2	49.2		28.6	28.6	28.6
Actuated g/C Ratio	0.28	0.28	0.28	0.28	0.28		0.62	0.62		0.36	0.36	0.36

Lanes, Volumes, Timings
3: Thunderbird Boulevard & Wesbrook Mall

2050 AM BASE MODEL
2021-11-30

												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
v/c Ratio	0.75	0.23	0.22	0.67	0.58		0.78	0.91		0.62	0.62	0.50
Control Delay	47.9	21.0	5.6	35.4	27.1		24.5	29.9		55.6	27.2	16.6
Queue Delay	0.0	0.0	0.0	0.0	0.0		0.0	0.0		0.0	0.0	0.0
Total Delay	47.9	21.0	5.6	35.4	27.1		24.5	29.9		55.6	27.2	16.6
LOS	D	C	A	D	C		C	C		E	C	B
Approach Delay		28.3			30.4			28.2			25.8	
Approach LOS		C			C			C			C	
Queue Length 50th (m)	20.8	14.4	0.0	28.0	40.4		31.2	108.5		8.2	55.9	19.0
Queue Length 95th (m)	26.3	17.1	2.5	28.8	30.7		#87.7	#200.2		#22.0	78.1	35.1
Internal Link Dist (m)		129.9			88.5			731.2			68.2	
Turn Bay Length (m)	60.0		40.0				110.0			50.0		12.0
Base Capacity (vph)	257	675	509	396	701		538	998		97	659	515
Starvation Cap Reductn	0	0	0	0	0		0	0		0	0	0
Spillback Cap Reductn	0	0	0	0	0		0	0		0	0	0
Storage Cap Reductn	0	0	0	0	0		0	0		0	0	0
Reduced v/c Ratio	0.57	0.18	0.17	0.51	0.44		0.78	0.91		0.62	0.62	0.50

Intersection Summary

Area Type: Other

Cycle Length: 80

Actuated Cycle Length: 80

Offset: 16 (20%), Referenced to phase 2:NBTL and 6:SBTL, Start of Green

Natural Cycle: 90

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 0.91

Intersection Signal Delay: 28.0

Intersection LOS: C

Intersection Capacity Utilization 87.9%

ICU Level of Service E

Analysis Period (min) 15

95th percentile volume exceeds capacity, queue may be longer.























Queue shown is maximum after two cycles.

Splits and Phases: 3: Thunderbird Boulevard & Wesbrook Mall















Lanes, Volumes, Timings
3: Thunderbird Boulevard & Wesbrook Mall

2050 PM BASE MODEL
2021-11-30

												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Lane Width (m)	2.9	3.3	3.3	3.5	4.0	3.5	3.5	4.0	3.5	3.1	3.5	3.3
Storage Length (m)	60.0		40.0	0.0		30.0	110.0		0.0	50.0		12.0
Storage Lanes	1		1	1		0	1		0	1		1
Total Lost Time (s)	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0
Leading Detector (m)	6.5	6.5	1.5	6.5	6.5		6.5	6.5		6.5	6.5	1.5
Trailing Detector (m)	1.5	1.5	0.0	1.5	1.5		1.5	1.5		1.5	1.5	0.0
Turning Speed (k/h)	25		15	25		15	25		15	25		15
Lane Util. Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Ped Bike Factor	0.87		0.87	0.91	0.94			0.91				0.63
Frt			0.850		0.955			0.966				0.850
Flt Protected	0.950			0.950			0.950			0.950		
Satd. Flow (prot)	1632	1801	1531	1750	1745	0	1750	1709	0	1671	1842	1531
Flt Permitted	0.575			0.673			0.138			0.196		
Satd. Flow (perm)	856	1801	1327	1128	1745	0	254	1709	0	345	1842	960
Right Turn on Red			Yes			Yes			Yes			Yes
Satd. Flow (RTOR)			17		30			21				41
Headway Factor	1.11	1.04	1.04	1.01	0.94	1.01	1.01	0.94	1.01	1.08	1.01	1.04
Link Speed (k/h)		50			50			50				50
Link Distance (m)		153.9			112.5			755.2			92.2	
Travel Time (s)		11.1			8.1			54.4			6.6	
Volume (vph)	325	71	278	110	57	34	110	359	97	52	539	124
Confl. Peds. (#/hr)	121		113	113		121	193		149	149		193
Confl. Bikes (#/hr)			43			11			14			35
Peak Hour Factor	0.84	0.54	0.85	0.75	0.55	0.78	0.81	0.89	0.81	0.79	0.77	0.76
Parking (#/hr)									0			
Adj. Flow (vph)	387	131	327	147	104	44	136	403	120	66	700	163
Lane Group Flow (vph)	387	131	327	147	148	0	136	523	0	66	700	163
Turn Type	pm+pt		Perm	Perm			Perm			Perm		Perm
Protected Phases	7	4			8			2			6	
Permitted Phases	4		4	8			2			6		6
Detector Phases	7	4	4	8	8		2	2		6	6	6
Minimum Initial (s)	6.0	7.0	7.0	7.0	7.0		10.0	10.0		10.0	10.0	10.0
Minimum Split (s)	12.5	31.3	31.3	33.3	33.3		21.9	21.9		28.9	28.9	28.9
Total Split (s)	13.0	47.0	47.0	34.0	34.0	0.0	33.0	33.0	0.0	33.0	33.0	33.0
Total Split (%)	16.3%	58.8%	58.8%	42.5%	42.5%	0.0%	41.3%	41.3%	0.0%	41.3%	41.3%	41.3%
Maximum Green (s)	6.5	40.7	40.7	27.7	27.7		27.1	27.1		27.1	27.1	27.1
Yellow Time (s)	3.6	3.6	3.6	3.6	3.6		3.6	3.6		3.6	3.6	3.6
All-Red Time (s)	2.9	2.7	2.7	2.7	2.7		2.3	2.3		2.3	2.3	2.3
Lead/Lag	Lead			Lag	Lag							
Lead-Lag Optimize?	Yes			Yes	Yes							
Vehicle Extension (s)	2.5	3.0	3.0	3.0	3.0		4.0	4.0		4.0	4.0	4.0
Recall Mode	None	None	None	None	None		C-Min	C-Min		C-Min	C-Min	C-Min
Walk Time (s)		7.0	7.0	7.0	7.0		7.0	7.0		7.0	7.0	7.0
Flash Dont Walk (s)		18.0	18.0	20.0	20.0		9.0	9.0		16.0	16.0	16.0
Pedestrian Calls (#/hr)		0	0	0	0		0	0		0	0	0
Act Effct Green (s)	30.1	30.1	30.1	17.1	17.1		41.9	41.9		41.9	41.9	41.9
Actuated g/C Ratio	0.38	0.38	0.38	0.21	0.21		0.52	0.52		0.52	0.52	0.52

Lanes, Volumes, Timings
3: Thunderbird Boulevard & Wesbrook Mall

2050 PM BASE MODEL
2021-11-30

												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
v/c Ratio	0.95	0.19	0.64	0.61	0.37		1.02	0.58		0.36	0.73	0.31
Control Delay	55.7	16.2	24.8	38.3	22.5		112.3	17.1		21.5	22.3	11.5
Queue Delay	0.0	0.0	0.0	0.0	0.0		0.0	0.0		0.0	0.0	0.0
Total Delay	55.7	16.2	24.8	38.3	22.5		112.3	17.1		21.5	22.3	11.5
LOS	E	B	C	D	C		F	B		C	C	B
Approach Delay		37.6			30.4			36.7			20.3	
Approach LOS		D			C			D			C	
Queue Length 50th (m)	49.8	13.9	40.1	21.5	16.1		~21.6	50.9		5.8	80.2	10.0
Queue Length 95th (m)	#64.6	12.3	52.8	28.7	14.9		#54.1	97.6		16.7	114.2	21.2
Internal Link Dist (m)		129.9			88.5			731.2			68.2	
Turn Bay Length (m)	60.0		40.0				110.0			50.0		12.0
Base Capacity (vph)	409	968	721	423	673		133	905		181	965	523
Starvation Cap Reductn	0	0	0	0	0		0	0		0	0	0
Spillback Cap Reductn	0	0	0	0	0		0	0		0	0	0
Storage Cap Reductn	0	0	0	0	0		0	0		0	0	0
Reduced v/c Ratio	0.95	0.14	0.45	0.35	0.22		1.02	0.58		0.36	0.73	0.31

Intersection Summary

Area Type: Other

Cycle Length: 80

Actuated Cycle Length: 80

Offset: 16 (20%), Referenced to phase 2:NBTL and 6:SBTL, Start of Green

Natural Cycle: 90

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 1.02

Intersection Signal Delay: 30.7

Intersection LOS: C

Intersection Capacity Utilization 71.4%

ICU Level of Service C

Analysis Period (min) 15


~ Volume exceeds capacity, queue is theoretically infinite.

Queue shown is maximum after two cycles.

95th percentile volume exceeds capacity, queue may be longer.

Queue shown is maximum after two cycles.

Splits and Phases: 3: Thunderbird Boulevard & Wesbrook Mall



LANE SUMMARY

 Site: 103 [16th Avenue (Site Folder: 2021_AM_MODEL)]

New Site

Site Category: 2021_AM_BASE

Roundabout

Lane Use and Performance													
	DEMAND FLOWS [Total HV] veh/h %		Cap. veh/h	Deg. Satn v/c	Lane Util. %	Aver. Delay sec	Level of Service	95% BACK OF QUEUE [Veh Dist] m		Lane Config	Lane Length m	Cap. Adj. %	Prob. Block. %
South: Wesbrook Mall													
Lane 1 ^d	809	2.9	1150	0.703	100	3.1	LOS A	6.6	47.2	Full	37	0.0	12.4
Approach	809	2.9		0.703		3.1	LOS A	6.6	47.2				
East: 16th Avenue													
Lane 1	118	0.0	744	0.158	100	11.2	LOS B	1.1	7.4	Full	169	0.0	0.0
Lane 2 ^d	146	13.0	923	0.158	100	5.9	LOS A	1.2	9.0	Full	169	0.0	0.0
Approach	264	7.2		0.158		8.2	LOS A	1.2	9.0				
North: Wesbrook Mall													
Lane 1 ^d	319	29.7	960	0.333	100	7.0	LOS A	1.7	14.6	Full	538	0.0	0.0
Lane 2	168	2.9	890	0.189	57 ⁵	4.5	LOS A	0.8	6.0	Full	538	0.0	0.0
Approach	487	20.4		0.333		6.1	LOS A	1.7	14.6				
West: 16th Avenue													
Lane 1	98	0.0	1027	0.096	97 ⁵	4.5	LOS A	0.6	3.9	Full	285	0.0	0.0
Lane 2 ^d	109	28.4	1105	0.098	100	9.5	LOS A	0.6	5.1	Full	285	0.0	0.0
Approach	207	14.9		0.098		7.1	LOS A	0.6	5.1				
Intersection	1767	9.8		0.703		5.2	LOS A	6.6	47.2				

Site Level of Service (LOS) Method: Delay (SIDRA). Site LOS Method is specified in the Parameter Settings dialog (Site tab).

Roundabout LOS Method: SIDRA Roundabout LOS.

Lane LOS values are based on average delay per lane.

Intersection and Approach LOS values are based on average delay for all lanes.

Roundabout Capacity Model: SIDRA Standard.

Delay Model: SIDRA Standard (Geometric Delay is included).

Queue Model: SIDRA Standard.

Gap-Acceptance Capacity: SIDRA Standard (Akçelik M3D).

HV (%) values are calculated for All Movement Classes of All Heavy Vehicle Model Designation.

⁵ Lane under-utilisation found by the program

^d Dominant lane on roundabout approach

Approach Lane Flows (veh/h)											
South: Wesbrook Mall											
Mov.	L2	T1	R2	Total	%HV		Deg. Satn	Lane Util.	Prob. SL	Ov. Lane	
From S To Exit:	W	N	E			Cap. veh/h	v/c	%	%	No.	
Lane 1	283	344	181	809	2.9	1150	0.703	100	NA	NA	
Approach	283	344	181	809	2.9		0.703				
East: 16th Avenue											
Mov.	L2	T1	R2	Total	%HV		Deg. Satn	Lane Util.	Prob. SL	Ov. Lane	
From E To Exit:	S	W	N			Cap. veh/h	v/c	%	%	No.	
Lane 1	102	16	-	118	0.0	744	0.158	100	NA	NA	
Lane 2	-	102	44	146	13.0	923	0.158	100	NA	NA	
Approach	102	117	44	264	7.2		0.158				

North: Westbrook Mall											
Mov.	L2	T1	R2	Total	%HV		Deg.	Lane	Prob.	Ov.	
From N						Cap.	Satn	Util.	SL Ov.	Lane	
To Exit:	E	S	W			veh/h	v/c	%	%	No.	
Lane 1	51	268	-	319	29.7	960	0.333	100	NA	NA	
Lane 2	-	-	168	168	2.9	890	0.189	57 ⁵	NA	NA	
Approach	51	268	168	487	20.4		0.333				
West: 16th Avenue											
Mov.	L2	T1	R2	Total	%HV		Deg.	Lane	Prob.	Ov.	
From W						Cap.	Satn	Util.	SL Ov.	Lane	
To Exit:	N	E	S			veh/h	v/c	%	%	No.	
Lane 1	-	58	40	98	0.0	1027	0.096	97 ⁵	NA	NA	
Lane 2	109	-	-	109	28.4	1105	0.098	100	NA	NA	
Approach	109	58	40	207	14.9		0.098				
Total %HV Deg.Satn (v/c)											
Intersection	1767	9.8		0.703							

Lane flow rates given in this report are based on the arrival flow rates subject to upstream capacity constraint where applicable.

⁵ Lane under-utilisation found by the program

Merge Analysis											
	Exit Lane Number	Short Lane Length m	Percent Opng in Lane %	Opposing Flow Rate veh/h	Critical Gap sec	Follow-up Headway sec	Lane Flow Rate veh/h	Capacity veh/h	Deg. Satn v/c	Min. Delay sec	Merge Delay sec
South Exit: Westbrook Mall											
Merge Type: Not Applied											
Full Length Lane	1	Merge Analysis not applied.									
East Exit: 16th Avenue											
Merge Type: Not Applied											
Full Length Lane	1	Merge Analysis not applied.									
Full Length Lane	2	Merge Analysis not applied.									
North Exit: Westbrook Mall											
Merge Type: Not Applied											
Full Length Lane	1	Merge Analysis not applied.									
West Exit: 16th Avenue											
Merge Type: Not Applied											
Full Length Lane	1	Merge Analysis not applied.									
Full Length Lane	2	Merge Analysis not applied.									

SIDRA INTERSECTION 9.0 | Copyright © 2000-2020 Akcelik and Associates Pty Ltd | sidrasolutions.com

Organisation: UNIVERSITY OF BRITISH COLOMBIA CIVIL ENGINEERING | Licence: EDU NETWORK / Special | Processed: November 28, 2021 4:01:58 PM

Project: C:\Users\2josh\OneDrive - The University Of British Columbia\CIVL 445\Sidra\2021 AM Model.sip9

Appendix E - Underpass Design Load Calculations

APPENDIX E: UNDERPASS DESIGN CALCS.

Soil Parameters:

Soil angle of friction $\phi = 30^\circ$

Soil unit weight $\gamma_{\text{soil}} = 19 \text{ kN/m}^3$

Allow. Soil pressure: 144 kPa

Vehicle loading: Cusing CSA 5-67 (Live)

wheel load = 72.5 kN (highway code)

$$2000 \text{ mm} < 2400 \text{ mm} \therefore h_f = 2000$$
$$\text{Loading width} = 2000 + 250 = 2250$$

→ using online calculator:

Linear load on top slab = 7.14 kpa

Dynamic Load Allowance $I_M = 33(1 - 0.0004(h_f)) = 5.94\%$


$$W_{\text{vehicle}} = 7.14 + (7.14 \cdot \frac{IM}{100} \cdot 1.20) = 9.1 \text{ kN/m}$$

Dead Loads from Soil Pressure

Top slab: $w_{\text{soil}} = 2000(19)(1) = 38.0 \text{ kN/m}$

$$W_{sw_1} = 300(23.5)(1) = 7.05 \text{ kN/m}$$

Side Slabs:



$$K_a = \frac{1 - \sin \phi}{1 + \sin \phi} = 0.33, \text{ Surcharge due to top soil} = 38 \text{ kPa}$$

$$K_{ah_{top}} = 0.33 \gamma_{soil} (2.0) = 12.54$$

$$K_{ah} = 0.338_{\text{sol}} (3000 + 2000) = 31.7 \text{ kN/m}$$

$$P_{S_{W_2}} = (2)(0.3)(3 - 0.3 - 0.3)(23.5) = 33.8 \text{ kN}$$

Bottom Slabs: $\frac{P_{sw2}}{3.1} + W_{sw1} + W_{soil} + \gamma_{concrete} (3.1) (1)$

$W_{sw3} = 63 \text{ kN/m}$


$W_{vehicle} = 9.1 \text{ kN/m}$

Load Factors: Live = 1.5, Dead = 1.2 S, horizontal pressure: 1.5

Final Loading Diagrams:


Soil Loads

$1.2S(W_{sw1} + W_{soil}) = 56.31 \text{ kN/m}$




$1.2S(W_{sw3}) = 78.8 \text{ kN/m}$

Soil pressure Loads






Vehicle Loads

$1.5(W_{vehicle}) = 13.62 \text{ kN/m}$



$1.5(W_{sw3}) = 13.62 \text{ kN/m}$

Structural Analysis (using Risa 2D)



Max moment = 69.3 kN-m @ bottom slab ends

Max shear = 138.6 kN @ bottom slab ends

To be conservative, use as design forces throughout!


Reinforcement Detailing:

Concrete touching soil \therefore 75mm required

Concrete not touching soil: 40mm required

BLL (face touching soil.)

$$\text{Spacing: } \frac{A_s}{s_t} \geq 0.002 \quad S \leq \frac{300}{0.002(300)} = 500, \rightarrow \text{Try } 200\text{mm}$$




$$M_r = \phi_s f_y A_s \left(d - \frac{\phi_s f_y A_s}{2 \phi_c f'_c b} \right)$$
$$= 340(1200) \left(215 - \frac{(340)(1200)}{2(0.79)(0.85)(40)(1000)} \right) = 84.6 \text{ kN}\cdot\text{m} > 69.3 \quad \checkmark$$

\therefore GOOD

TUL (face towards inside)

$$S \leq 500 \rightarrow \text{Try } 3 \times 20\text{M Bars } (A_s = 900)$$



$$M_r = 340(900) \left(250 - \frac{340 \cdot 900}{2(0.79)(0.85)(40)(1000)} \right) = 74.8 > 69.3 \text{ kN}\cdot\text{m} \quad \checkmark$$

GOOD


BVL & TBL

$$BVL = \frac{A_b}{s_t} = 0.002, \quad S < 500 \text{ for } 20\text{M bars } \therefore$$

use 20M at 500mm spacing

Development length on bars:

$$l_d = 23(20) = 460\text{mm} \rightarrow$$



Shear check Concrete Strength only

$$V_c = \phi_c \beta \sqrt{f'_c} b_w d_v \quad d_v = 0.9(215) = 193.5\text{mm}$$

$$= (0.65)(0.21)(40)^{1/2}(1000)(193.5)$$

$$= 167.1\text{ kN} > 138.6\text{ kN} \quad \checkmark \quad \text{GOOD}$$

Bearing Pressure Check:



92.4 kN/m

$$92.4 \frac{\text{kN}}{\text{m}} / 1.0\text{m slab width}$$

$$= 92.4\text{ kPa.}$$

Allowable bearing Pressure = 150 kPa

$$\therefore \text{FOS} = \frac{150}{92.4} > 1 \quad \checkmark \quad \text{GOOD}$$

Summary

	Moment, M	Shear, V	Bearing
<u>Demand</u>	69.3 kN-m	138.8 kN	92.4 kPa
<u>Capacity</u>	74.9 kN-m	167.1 kN	150 kPa
<u>Status:</u>	GOOD	GOOD	GOOD


Appendix F - Pump Design Calculations

Head Requirement - 8 meters

Flow Requirement - 10mm/hr * (4m * 35m) Underpass Plan View Dim. = 25 GPM

- Based on 1 in 100 year hourly rainfall at UBC Vancouver above underpass
- Groundwater water table 45 meters below surface (no influence)

Pump Curve and System Curve - Selected Pump MODEL NS 4-23 CVBP



Source: <https://product-selection.grundfos.com/>

Operating Point Summary


Target Flow = 25 GPM or 1.57 L/s

Target Head Clearance = 7.1 meters

Operating Point = 26.7 GPM at 9.1 meters of head

Appendix G - Settlement Calculations

Underpass Settlement



Assumptions:

1. Shallow foundation
2. Elastic Settlement
(Drained sand)
3. No size or depth factors (conservative estimate)


Equation:

$$\text{Settlement} = q_0 (\alpha B') \left(\frac{(1 - \mu_s^2)}{E_s} \right)$$

- q_0 - net pressure
- μ_s - Poisson ratio of soil
- E_s - Average MOE of soil
- P_{conc} - density of concrete
- $g = 9.81\text{m/s}^2$ • $A = \text{cross section}$
- $\alpha = 4$

$$B' = \frac{B}{2}$$

Dimensions (Not to Scale)



Density of concrete
 $P_{conc} = 2400\text{kg/m}^3$

q_0 calculations:

$$q_0 = P_g A / B$$

$$q_0 = 2400\text{kg/m}^3 \cdot 9.81\text{m/s}^2 \cdot \frac{(3 \times 2.8)}{2.7 \times 2.8}$$

$$q_0 = \frac{357\text{kN}}{2.8\text{m}}$$

$$q_0 = 127\text{kN/m}$$

Settlement

$$S = q_0 (\alpha B') \left(\frac{(1 - \mu_s^2)}{E_s} \right)$$

$$S = 127 \frac{\text{kN}}{\text{m}} \left(4 \times \frac{3.1}{2} \right) \left(\frac{(1 - 0.3^2)}{22\text{MPa}} \right)$$

$$S = 3\text{cm}$$

Acceptable settlement
for framed structure
5-cm



pass

Source: Principles of Foundation Engineering
theconstructor.org